P.O. Box 13427 Tallahassee, FL 32317-3427 Phone or Fax (850) 877-0673 e-mail: frankden@nettally.com

RIGINAL

RECEIVED

00 JAN 24 AM 8: 31

Management & Regulatory Consultants, Inc.

COMMISSION CLERK

January 23, 2006

Hand Delivered

Mr. Troy Rendell Public Utilities Supervisor Florida Public Service Commission 2540 Shumard Oak Boulevard Tallahassee, FL 32399-0850

Re: Application for a Staff Assisted Rate Case by MSM Utilities, LLC, Docket No. 050587-WS Staff's First Data Request

Dear Mr. Rendell:

This response to Items 11 and 12 of Staff's First Data request dated January 3, 2006 regarding the Meter Installation Fee and Service Availability Charges is provided on behalf of MSM Utilities, LLC. Responses to Items 1 through 10 will be filed by the due date of February 15, 2006.

	Item 11.	The following items relate to a meter installation fee. See the attached example, Order No. PSC-05-0776-TRF-WS.				
	a.	-	iic dollar	amount requested	for the meter installation	
CMP		fee. <u>RESPONSE:</u> \$183.00	for a 5/8	3" x 3/4" meter. All c	others at actual cost.	
COM	b.	•	•	-	uested meter installation fee. to, the following: 1)meter,	
ECR					, 5) labor and supervision,	
GCL		and 6) transportation	i, tools a	nd supplies.		
OPC		RESPONSE:				
RCA		5/8" x 3/4" meter	\$	28.64		
	·········	Meter box		13.62		
SGA		Couplings		6.76	DOCUMENT NUMBER-DAT	E
отн		RECEIVED & FILED			00655 JAN 24 s) F
		EPSC-BUREAU OF REC	<u>`0000</u>	_	FPSC-COMMISSION CLER	K

Page 2

Curbstop	26.90
Dual check valve	 29.54
	\$ 108.46
Sales tax	 7.59
Total parts	\$ 116.05
Labor & Supervision	50.00
Misc 10%	 16.61
Total, installed	182.66

Item 12. The following items relate to service availability charges.

c. What is the utility's estimated buildout date?

<u>RESPONSE</u>: With regard to buildout of the service area, no buildout date has been set as it is customer driven. With regard to the first phase of water and wastewater treatment facility expansion, it is estimated that they will be built out by 2011 or 5 years from completion of construction.

- MSM has stated that it intends to abandon its existing water and wastewater treatment plants and build new plants by 2007. 1) If applicable, provide a copy of the utility's capacity reports for its existing water and wastewater treatment plants. <u>RESPONSE</u>: See attached wastewater Updated Capacity Analysis, February 6, 2004. A water capacity analysis is not yet required. Also, please note that MSM intends only to abandon its existing wastewater treatment plant and relocate the new plant to a larger site. It is currently planned that the existing water treatment plant will continue to be used and will be expanded at its present location. 2) What are the utility's estimated dates that MSM will reach its current design capacity of the utility's new water and wastewater treatment plants? <u>RESPONSE</u>: Based on projected flows and customer growth, the expanded water treatment plant should reach capacity by 2011 and the new wastewater treatment plant should reach capacity by 2010. This assumes completion and availability of the plants in 2007.
- e. Does the utility plan to completely abandon its existing treatment plants or does it plan to use parts of its existing plants in the new plants? Please discuss any parts from the existing facilities the utility may use. <u>RESPONSE</u>: As stated in response to 12.d. above, the utility plans to utilize all of the existing water treatment plant and expand it. The existing wastewater treatment plant will be completely removed from service. It cannot be expanded at its present location. The plant is completely depreciated. It appears that the only salvageable equipment will be the blowers which represent only a few hundred dollars. The remaining tankage and equipment do not appear to be worth saving.
- f. Provide cost estimates of any plant improvements necessary to provide

Page 3

service to future customers, e.g., treatment plant, new wells, distribution lines, collection lines, etc.

RESPONSE: MSM has had its engineer prepare a cost expansion estimate and has had its regulatory consultant develop Service Availability Charges (SACs) based on that cost information and estimated growth and flow projections. The information is provided in the attachment SERVICE AVAILABILITY CHARGES and PLANT EXPANSION COSTS. As you may be aware, MSM does not currently have any approved SACs nor does it have an approved Meter Installation Fee. It is MSM's intent that such charges be proposed and approved as a part of this SARC. MSM had not specifically requested that SACs be set as a part of the SARC. But, based on prior experience, MSM anticipated that Staff would analyze the SAC situation as a part of its SARC analysis. Without knowledge of the outcome of the SARC, MSM did not have a base from which to determine said charges. MSM now has that information from the Staff's Audit Report. Since MSM intends to expand its facilities in 2007 and has requested an expansion of its service territory in Docket No. 050820-WS, it is essential that SAC charges be approved prior to new customers coming on line. As indicated in the attached document, MSM believes that the appropriate SAC charges are a System Capacity Charge per ERC of \$638.10 for water and \$1,762.40 for wastewater. In addition MSM believes that \$183.00 is the appropriate Meter Installation Fee for a 5/8" x 3/4" meter. MSM also intends that its main extension policy shall be that, for new developments, the water distribution and sewage collection systems be contributed. All of these factors were assumed in developing the SAC charges.

Very truly yours,

Frank Seidman

cc: Division of the Commission Clerk and Administrative Services - Hand Delivered Ms. Patti Daniel, Public Utilities Supervisor - Hand Delivered Mr. Ben Maltese, MSM Utilities, LLC Gerald Buhr, Esq.

UPDATED CAPACITY ANALYSIS

۰ ۲

REPORT

FOR

Rivers Edge

Vastewater Treatment Plant

Charlotte County, Florida Facility ID: FLA014062 Permit No.: FLA014062 Expires: April 22, 2004

Prepared For: The Oaks at River's Edge Inc. 1601 Hunter Creek Dr Punta Gorda, Florida, 33982

February 6, 2004

Prepured By: McDonald Group International, Inc. 9030 S. Brittany Path Inverness, Florida 34452 680



CAPACITY ANALYSIS

REPORT

FOR

Rivers Edge

Wastewater Treatment Plant

Charlotte County, Florida

The information contained in this report was prepared in accordance with sound engineering principals, and the recommendations contained within have been discussed with the permittee

Date:

George J. McDonald, P.E., FL PROFESSIONAL ENGINEER NO. 44740 McDonald Group International, Inc. CA-0007580 9030 S. Brittany Path, Inverness, Florida 34452 (352)-637-1652

I am fully aware and intend to comply with the recommendations and schedules included in this report

Date:

Zola M. MacLachlan The Oaks at River's Edge Inc. 1601 Hunter Creek Dr Punta Gorda, Florida,33982 941-639-2810

CAPACITY ANALYSIS REPORT FOR Rivers Edge WASTEWATER TREATMENT PLANT

Table of Contents

1.0 **INTRODUCTION**

- 1.1 Authorization
- 1.2 Related Reports and Documents
- 1.3 Service Area Description

2.0 EXISTING CONDITIONS AND PERMITTED CAPACITIES

- 2.1 Influent Strength
- 2.2 Updated Flow Information
- 2.2.1 Flow Calibration
- 2.2.2 Plant Flow Characteristics
- 2.2.3 Peak Hour and Daily Flows
- 2.3 Effluent Quality
- 2.4 Design and Current Loadings
- 2.5 Effluent Disposal and Reuse
- 2.6 Waste Sludge Disposal or Reuse System

3.0 FUTURE CONDITIONS - WASTEWATER FLOW PROJECTION

- 3.1 Unit Waste Generation Rate
- 3.2 Build Out Flow
- 3.3 Growth Rate

4.0 SUMMARY AND RECOMMENDATIONS

<u>Tables</u>

- Table 2.0 Permit Effluent Limitation Standards
- Table 2.1 -Influent Characteristics
- Table 2.2- Flow and Performance History
- Table 2.3 Effluent Quality
- Table 2.4 Process Data
- Table 2.5 Effluent Disposal
- Table 2.6 Sludge Disposal
- Table 3.2 Future Possible Average Flow

Figures

- Figure 1.1 Location Map
- Figure 1.2 USGS. Map
- Figure 1.3 Process Diagram
- Figure 1.4 Site Plan
- Figure 2.2 Flow Chart

CAPACITY ANALYSIS REPORT

1.0 **INTRODUCTION**

Florida Department of Environmental Protection (FDEP) rule 62-600.405(4) F.A.C. requires that a capacity analysis report be submitted to the Department with a permit application to renew a Wastewater facility permit.

This capacity analysis is submitted to the FDEP by McDonald Group International, George J. McDonald, P.E., consultant engineer for The Oaks at River's Edge Inc., the owner and operator of the Rivers Edge Wastewater Treatment Plant located in Charlotte County, Florida in order to comply with rule 62-600.405, F.A.C. The last capacity analysis report is believed to have been performed during the last permit renewal.

The facility is located at 1601 Hunter Creek Drive, Punta Gorda, Florida. A location map and USGS quad map are provided in Figures 1.1 and 1.2 respectively.

1.1 <u>Authorization</u>

The Oaks at River's Edge Inc. has retained George J. McDonald, P.E. to study their plant's historical flows, service area characteristics, and issues which effect changes in future capacity requrements of their wastewater treatment plant in order to provide a capacity analysis report (CAR) in support of the wastewater plant permit application.

1.2 Related Reports and Documents

Accompanying this report is an Operations and Maintenance Performance Report, as well as FDEP Forms 1 and 2A for a domestic wastewater treatment plant. Additional information is contained in the accompanying reports and documents.

1.3 General Service Area Description

The treatment facility serves River's Edge. This area consists of approximately 45 modular homes at present.

1.4 Facility Information

This Wastewater Treatment Plant is presently permitted for the flow capacity and discharge limitation standards in the following table:

Rivers Edge Wastewater Treatment Plant

- Maximum flow capacity 0.015 MGD 1.
- BOD and TSS maximum concentrations -2.

20 mg/L annual average 30 mg/L monthly average 45 mg/L weekly average

- 60 mg/L any one sample
- pH range 6.00 to 8.50 3
- 4. Fecal Coliform -

200 #/100 annual average

- 800 #/100 maximum
- Minimum Cl_2 conc. 0.5 mg/L 5. Nitrate 6
 - 12 mg/L max

The Rivers Edge Wastewater Treatment Plant has been active since 1984.

Process

It is an activated sludge waste treatment facility operating in the extended aeration mode. The treatment process comprises the following: aeration, final settling; sludge digestion, disinfection. A process plan follows the USGS map in the following pages.

Modifications

The facility has not been reported to have been modified in the last 5 years. A permit to expand the plant was applied for but the construction was not begun.

Notices of violation

According to the Owner and the Operator, one NOV was reported, apparently seeking the annual residuals summary ...

1.5 Scope of Report

Although containing many elements of a regular capacity analysis report, the depth and scope of this report is meant to equal or exceed the requirements for an "abbreviated" capacity analysis report.

1.6 Information Sources

This report is prepared based on information supplied by the permittee, information that may be found in FDEP public databases, the current permit, and information supplied by the operator. The report relies on the accuracy of this information for all analysis and opinions.

Figure 1.1 Street Location Map





Figure 1.2 USGS Map









.

,










Figure 1.4 Site Plan (Line Drawing)

.

•

2.0 **EXISTING CONDITIONS AND PERMITTED CAPACITIES**

The Rivers Edge Wastewater Treatment Plant has been active since 1984. It is an activated sludge waste treatment facility operating in the extended aeration mode. The current operating permit, FLA014062 is due to expire April 22, 2004.

The Wastewater Treatment Plant is presently permitted to discharge effluent meeting the Secondary Treatment Technology Based Effluent Standards listed in the table in section 1.4.

2.1 Influent Strength

•

The major parameters used to evaluate influent strength are influent BOD, TSS, TKN.

Based on available test data, the influent strength is estimated to be as follows:

Table 2.1				
Influent Strength				
<u>Parameter</u>	Characterization			
CBOD ₅	159 mg/L			
TSS	331 mg/L			

2.2 Updated Flow Information -

2.2.1 Flow Calibration

Flows to this wastewater plant are determined by elapsed time meters, influent lift station.

The accuracy of this method was last hecked by the Florida Rural Water Association . 12/16/2002

2.2.2 Plant Flow Characteristics

Data from Discharge Monitoring Reports (DMRs) were studied to determine the present plant flow characteristics. Table 2.2 summarizes the data taken from the DMRs for the period reviewed.

Figure 2.2 graphically illustrates the annual average and rolling three month average flow for the period reviewed:




Figure 2.2 Flow Chart

Historical Flow

Table 2.2 Flow and Performance History

.

	рН MN	рН MO	TSS Mb	TSS Mk	TSS MN	Nitrate MB	Fecal MK	Fecal MN	Fecal WA	TRC MO	BOD AB	BOD MK	BOD	TSS Infl	BOD Infl	Flow MK
2/28/1999	7.4	6.8	M D	12.6		MLQ.	1				~D	2		278	537	0.002
3/31/1999	7.4	6.7		12.0			1					34.9		194	380	0.001
4/30/1999	7.4	6.8		4.4			1			0.8		2		104	132	0.001
	7.8	6.4		3			1			0.7		2		54.9	117	0.001
5/31/1999 6/30/1999	7.0	6.2		2.1	2.1		1	1	,1	1		2	2	400	219	0.001
7/31/1999	7.3	6.8		5	5		1	1	1	0.8		2	2	32	10	0.001
8/31/1999	7.4	6.8		4	4		1	1	1	0.8		2.03	2.03	25.5	480	0.001
		6.7		4	4		1	1	•	1		7.38	7.38	146	287	0.001
9/30/1999	7.1 7	6.5		3.2	3.2		22	22	22	0.6		3.54	3.54	70	88	0.001
10/31/1999		6.7		5.2 6.4	5.2 6.4		60	60	nodi	0.7		2	2	212	44	0.001
11/30/1999 12/31/1999	7.8 7.9	7		2.6	2.6		1	1	1	0.5		2	2	200	157	0.001
1/31/2000	7.4	7		3	3		3	3	nodi	0.5		2	2	156	30	0.001
2/29/2000	7.4	7.2		60	60		136	200	noai	2		2	2	2560	191	0.001
3/31/2000	7.9	7.2		6.6	6.6		130	200	nr	1		2	2	142	110	0.001
4/30/2000	7.6	7		2.3	2.3		136	200	NR	0.5		6.3	6.3	116	224	0.001
5/31/2000	7.8	6.9		2.3	2.3		1	1	1	0.9		2.39	2.39	36.4	131	0.001
6/30/2000	7.8	6.5		1	1		1	1	1	0.5		2.55	2.33	20.3	86	0.001
7/31/2000	7.4	6.5		1.7	1.7		1	1	NA	1		2	2	60	70	0.001
8/31/2000	8.1	7		0.6	0.6	1.47	1	1	na	1		2	2	38	58	0.002
8/31/2000	8.1	7		0.6	0.6	1.47	1	1	NA	1		2	2	NA	21.9	0.002
9/30/2000	0.1 7.9	6.8		NA	NA	3.92	1	1	1	1		2	2	48	52.2	0.002
9/30/2000	7.9	6.8		NA	NA	0.52	1	1	1	•		2	2	40	01.1	0.002
10/31/2000	8.1	7		1.3	1.3	5.74	1	1	1	2		2	2			0.002
1/31/2001	7.6	6.9		7.4	7.4	0.199	40	40	40	0.6		2	2	66.7	227	0.002
2/28/2001	7.6	6.8		5	5	0.133	1	1	1	2		2	2	88.9	266	0.002
3/31/2001	7.5	6,9		2	2	0.323	1	1	1	0.8		2	2	105	200	0.001
4/30/2001	7.5	6.9		1.4	1.4	0.292	1	1	1	2		2	2	67.6	120	0.001
5/31/2001	8	7.1		0.8	0.8	0.295	1	1	1	0.5		2	2	68	186	0.001
6/30/2001	7.8	7		2.3	2.3	0.255	1	1	i	1		2	2	86	104	0.001
7/31/2001	7.6	7		11.2	11.2	1.54	1	1	1	0.5		2	2	46	58.5	0.002
8/31/2001	7.6	7		1.4	1.4	3.62	1	1	1	0.6		2	2	148	68.4	0.002
9/30/2001	7.8	7		4.4	4.4	1.03	1	i	1	0.9		2	2	117	107	0.002
10/31/2001	7.6	7		4.5	4.5	1.68	i	1	1	0.7		2	2	279	173	0.002
11/30/2001	7.5	7.1		3	3	0.904	1	1	1	0.6		2.1	2.1	276	129	0.002
12/31/2001	7.4	7		2.6	2.6	0.011	1	1	1	0.6		2.3	2.3	95	112	0.002
1/31/2002	7.6	7		2.9	2.9	2.15	1	1	1	0.7		2	2	332	212	0.002
2/28/2002	7.5	7		3.8	3.8		6	6	6	1.2		2.1	2.1	993	392	0.002
3/31/2002	7.4	7		3	3		ĩ	1	1	0.7		3.1	3.1	446	233	0.002
4/30/2002	7.5	7		1	1	0.36	7	7	7	0.6		1.4	1.4	248	283	0.002
5/31/2002	7.8	7.1	3.5	2	2	1.94	1	1	1	1	2.2	3.3	3.3	130	233	0.005
6/30/2002	7.7	7.1	3.7	4.3	4.3	5.94	1	i	1	4	2.1	1.3	1.3	126	130	0.005
7/31/2002	7.7	6.9	3.3	6.75	6.75	0.1	1	1	1	1.3	2.1	1.74	1.74	110	43.5	0.008
8/31/2002	8	7.2	3.4	2.25	2.25	0.17	1	1	1	0.8	2.1	1.99	1.99	54	86.8	0.006
9/30/2002	7.5	6.9	3.3	2.11	2.11	0.28	5	5	5	1	2.1	2	2	3650	84	0.001
10/31/2002	7.7	7	3.1	4.8	4.8	0.191	1	1	1	1	2	2	2	25	66.7	0.001
11/30/2002	7.7	7.1	8.1	23.8	23.8	0.05	23	23	23	1	3.1	7.78	7.78	220	146	0.002
12/31/2002	7.3	7.1	1.44	1.44	1.44	0.55	2	2	2	1.1	2	2	2	170	84.7	0.0088
1/31/2003	7.6	7.2	6	6	• 6	0.01	400/4	400/4	400/4	3	2.66	2.66	2.66	84	82.7	0.0079
2/28/2003	7.6	7	8.29	11.6	11.6	0.104	400/4	400/4	400/4	1.1	3.07	2.00	2.00	340	113	0.0058
3/31/2003	7.3	7.1	0.23	9.2	9.2	0.112	4	4	4	3.5	5.07	2	2	2490	649	0.0064
4/30/2003	7.3	7.3	7.8	9.2 4.2	9.2 4.2	0.07	4	4	4	2.5	3.02	2.8	2.8	2490 70	134	0.0084
	7.4	7	7.6	4.Z 6.22	4.2 6.22	0.136	4	4	4	4	2.76	3.68	3.68	620	66.7	0.0036
5/31/2003		7		6.22 2	6.22 2	0.135	4	4	4	4 3.2	2.76	2.44	3.68 2.44	172	66.7	0.0038
6/30/2003	7.3	7.1	7.64		12.4	0.155	4	4	4	3.2 2.5	2.7	2.44 3.65	2.44 3.65	630	66.7	0.0049
7/31/2003	7.6		7.61	12.4	12.4		4	4	4		3 2.91		3.65	160	78 06.7	0.0045
8/31/2003	7.6	6.8	7.1	4 44	1 44	0.584	4	•	•	2.5		2 2	2		78 147	0.0054
9/30/2003	7.4	7.1	7.4	1.44	1.44	0.768	4	4	4	3.2	2.9	2	2	116	147	0.0048

2.2.3 Peak Hour Flows

Peak hour flows were determined consideration of the operating characteristics of the plant and service area. Based on this, the peak hour factor is estimated to be 3 times the average daily flow.

2.3 Effluent Quality

The treated wastewater leaving the plant must meet specific limitations established by the FDEP in the current permit. Table 2.3 shows the current plant performance for the period studied versus the permitted requirements for effluent quality.

Table 2.3 Rivers Edge Wastewater Treatment Plant Effluent Quality Analysis

<u>Criteria</u>	Plant Performance	Permitted Limit
Annual ADF	0.005 MGD	0.015MGD
Highest 3 months rolling ADF	0.008 MGD	
Maximum monthly flow	0.0088 MGD	
Average Annual BOD conc.	3.1 mg/L	20 mg/L
Maximum monthly BOD conc.	7.8 mg/L	30 mg/L
Average annual TSS conc.	7.1 mg/L	20 mg/L
Maximum monthly TSS conc.	60mg/L	30 mg/L
pH range	6.2-8.1	6.00-8.50
Min. Cl_2 residual conc.	0.5mg/L	0.5 mg/L
Nitrate, maximum	5.94	12 mg/L
Coliforms, maximum	200	800 #/100 ml

2.4 Design and Current Loadings

The Rivers Edge Wastewater Treatment Plant is an activated sludge wastewater treatment plant operating in the extended aeration mode.

Figure 1.3 at the beginning of this report provides a graphical illustration of the unit process flow scheme.

Table 2.4 lists each unit process along with the associated loading rate with pertinent dimensional or volumetric data. (Volumetric, areas and dimensional data is estimated from information in the previous permit, manufacturer catalog data, and comparison with other facilities using the same manufactured tankage). Process design data is also incorporated into table 2.4.

Table 2.4 - Process Data

•

Influent Characteristics:			Current Flow	Design Flow
	BOD TSS TKN M3MADF	mg/L mg/L mg/L MGD	159 331 40 0.0050	200 350 40 0.0150
Effluent Targets				
	BOD TSS Nitrate Disinfection	mg/L mg/L mg/L	<20 <20 12 basic	<20 <20 12 basic
Process Design:				
	Process Mode Temp MLSS mg/L SRT days Yeild Coefficient anoxic aeration Total Volume MGAL V/Q, hrs. BOD Loading, #/1 Solids, Oxic, Lbs Solids, Anoxic, Lbs MLSS Recirculation, % RAS mg/L WAS, lb/day WAS, gpd Tank Configuration	000 cf	Ext Aer 20 3296 120 0.52 0 0 015 72.0 3.3 412 0 300 100 6593 3 63 \$ettics	Ext Aer 20 3357 25 0.68 0 0.015 24.0 12.5 420 0 300 100 6715 17 300 series
Aeration System:				
	Process O2, lb/day Diffuser Efficiency, % Air Rqd., SCFM lb O2/#BOD Air supply, CF/# BOD Type Aeration Number of Eductors		24 7 14 3.6 2991 Diffused 1	73 7 42 2.9 2425 Diffused 1

	Current Flow	Design Flow
Return Rate/Eductor, GPM	3.5	10.4
Air Eductors	11.0	11.0
Skimmer Air	3.7	3.7
Air Rqd. RAS:	15	15
Estimated RAS compressor Hp	1	1
Air Rqd. Process:	14	42
Air Rqd.Digester	5	5
Volume Surge	15000	3600
Air Rqd.Surge	60	14
Total Air Rqd.:	93	76
HP Required	3.7	3.0
Provided, single blower Hp	5	5

Final Settling:

ų

•

.

No. of Clarifiers	1	1
Surface Area, EA., sf	78	78
Est Side Depth	4.5	4.5
Est Total Depth to Hopper Bottom	13	13
Volume	5232	5232
V/Q, hrs.	25.1	8.4
Design Peak Factor	3	3
Hydraulic Overflow:		
Avg., gpd/sf	64	64
Peak, gpd/sf	192	192
Solids Loading Rate:		
Avg., lb/d-sf	4	11
Peak, lb/d-sf	7	22

Disinfection:

Method	Hypochlorination H	Hypochlorinatio
No. of CCCs	1	n I
Volume EA, gallons	600	600
Total CCC volume est	600	600
Cl2 Residual, mg/L	0.5	0.5
Cl2 Dose, mg/L	8	8
Consumption, lb/day	0.33	1.00
If Hypochlorination SystemUsed		
Est. Sodium Hypochlorite strength, %	15	15
Dose required, mg/L	8	8
Available Chlorine, lb/gal	1.25	1.25
dose, #/gal	6.68E-05	6.68E-05
Avg dose, #/day	0.33	1.00
Avg dose, gal/day	0.3	0.8
Peak Hour Capacity, gal/day	1	2
CCC Retention Time		

		Current Flow	Design Flow
	@ ADF, minutes	173	58
	@ PHF, minutes	58	19
	Residual * Detention	29	10
	Disinfection Level	Basic	Basic
Aerobic Sludge Digestion:			
	WAS Flow, gpd	63	300
	Total Solids,#/day	3.44	16.80
	WAS, mg/L	6593	6715
	% Volatile	75	75
	WASv, mg/L	4945	5036
	Total VSS,#/d	3	13
	VSS, #/Digester cf/day	0.02	0.08
	Thick Solids,%	1	1
	Digester Vol, gal	1200	1200
	Initial Est.SRT, days	25	5
	Temp, Degrees C	20	20
	VSS Destroyed, %	31.19	14.60
	Avg. Solids, mg/L	7000	7000
	Supernatant Solids,mg/L	300	300
	WAS Fraction Not Destroyed	0.77	0.89
	WAS Fraction in Digester	0.51	0.60
	Supernatant, gpd	31	121
	TSS in Digester, #	70	70
	Total SS Removed, #/d	3	15
	Supernatant TSS,#/d	0.1	0.3
	Sludge Discharge,#/d	3	15
	Sludge Rem/year, DTR	0.5	2.7
	Sludge Discharge,gpd	32 .	179
	Digester SRT, days	25.9	4.6
	Sludge Stabiliz. Class	<b< th=""><th><b< th=""></b<></th></b<>	<b< th=""></b<>
	Digester HRT, days	19.2	4.0
	O2 Rqd, VSS, #/d	2	4
	Air, SCFM	1	3
	Diffuser Effic.,%	5	5
	Air Rqd. Mixing, SCFM Design SCFM	5	5
	Design Serviv	5	5
Land Application System			
	Land Application Area, sf	94752.00	94752
	Land Application Area, ac	2.1752	2.1752
	Type System	Percolation Pond	Percolation
			Pond
	# SubCells	2	2
	Load Rate, gpd/sf	0.05	0.16
	Load Rate, in/wk	0.59	1.78

•

2.5 Effluent Disposal / Reuse

Effluent from the treatment plant is disposed or reused by dual percolation-evaporation ponds.

The relationship of the effluent disposal system to the treatment facility is shown in the site plan in figure 1.4

The associated loading rates of this system at current and design flows is as follows:

TABLE 2.5 Effluent Disposal\Reuse System

System Type	Application Area (acres)	Flow (MGD)	Loading Rate (in/wk)
dual percolation-e	vaporation		
ponds	0.216	0.015	17.9
		0.005	5.97

Note: 1.9 gpd/sf equals 21.3 in/wk; 5.6 gpd/sf equals 62.9 in/wk.

Based on site observation, the system appears to be functioning properly. It is recommended that the operator and Owner continue to monitor the performance of the system regularly, particularly if flows should increase.

Note, the surface area of the existing dual ponds is based on approximate field measure.

The current permit allows for the construction of an additional two ponds and increased capacity, but these have not been constructed.

2.6 Waste Sludge Disposal or Reuse System

2.6.1 General Information About Rule 62-640, EPA Rule 503

The disposal of waste sludge from domestic wastewater plants in Florida is regulated by the FDEP under their rule 62-640, by the Federal Government under EPA rule 503, and often by local regulation which varies.

The relationship of the rules to each other is complex, but generally, WWTP owners have two ways to comply with rule 62-640 and rule 503. First, if the Owner elects to use a sludge hauler solely to haul his waste sludge to a land application site, the Owner will usually have to have on file with FDEP an Agricultural Use Plan (AUP). In many cases, the Owner will also need to obtain approval from the USEPA for the same site. In the second case, the Owner can enter into a contract with a sludge hauler who holds a permit from the FDEP to haul, treat and dispose of sludge himself. The hauler will have a type of permit known as a Regional Residuals Treatment Facility or Regional residuals Management Facility permit.

The primary difference between the first and second case is that in the first case, the sludge hauler is not permitted by FDEP to treat sludge, and so the Owner will hold the State FDEP AUP and the Federal permit, whereas in the second case, the hauler will usually hold those responsibilities.

In March of 1998, FDEP rule 62-640 was updated to conform better with EPA rule 503 requirements.

2.6.2 <u>General Information about Meeting EPA Rule 503 Requirements and 62-640 for Owners who</u> Hold their Own Agriculatural Use Plans

The rules are fairly complex, and no attempt is made here to give a complete synopsis.

Stabilization Requirements

Usually, most WWTPs with their own AUP will need to stabilize their sludge to what is called class B standards when the sludge is hauled to a site such as a hayfield (non human edible crops) and with restricted site access.

To meet class B stabilization standards using aerobic digestion, rule 62-640 F.A.C. requires that the aerobic digester provide a minimum of 40 days solids retention time in accordance with the standards of a Process to Significantly Reduce Pathogens (PSRP), presently contained in CFR 503. Alternatives are discussed below.

Vector Attractor Reduction

Several methods to meet CFR 503 standards for Vector Attractor Reduction (VAR), defined as 38% Volatile Suspended Solids reduction, are available. Referring to the USEPA technical manual, Sludge Treatment and Disposal, a design graph is available for predicting VSS destruction in aerobic digesters based on the multiplier of temperature times solids retention time. Generally, 38%

VSS destruction is expected at a temperature of 20 degrees C when the digester solids retention time is in excess of 40 days. It is suggested that facilility operators relying on aerobic digesters to meet CFR 503 strandards for VAR, confirm 38% VSS destruction by having the digested sludge periodically given a Specific Oxygen Uptake Rate (SOUR) test. (Standards for this test are contained in CFR 503).

Alternatives

There are several alternatives to meeting Class B stabilization and VAR. The most commonly used method is lime stabilization. This consists of bringing the pH of the sludge to be disposed up to 12 for a period of two hours, followed by maintaining the sludge at pH 11.5 for an additional 22 hours.

Record Keeping

Both rule 62-640 and Rule 503 have extensive record keeping requirements. Basically records include keeping a running total of when sludge is hauled, where, and keeping a running tally on the accumulation of the amount of heavy metals disposed of at the land application site.

2.6.3 Disposal and Reuse of Waste Sludge From Rivers Edge WWTP.

Please refer to the process calculations in table 2.4 for information on the SRT and predicted VSS destruction from this facility from the aerobic process alone. Waste sludge from this facility is classified as Class B.

The facility uses lime stabilization to achieve or demonstrate compliance with the required minimum Class B standard.

Estimated sludge removal quantities (dry annual tonnage) is shown below.

The disposition of the sludge is as follows:

Table 2.6Sludge (Residuals) Disposal

Direct Land Application

Regional Residual Treatment Facility

Quantity 0.5 dry-tons/yr Site/Facility

Name

0d ry-tons/yr

American Water, Hauler Sites noted: Prairie Grove Boran Ranch, VC Hollingsworth

3.0 FUTURE CONDITIONS - WASTEWATER FLOW PROJECTION

3.1 Unit Waste Generation Rates

The current ADF unit waste generation rate(s) applicable to this facility is gpd per modular home. From section 3.1, the maximum three month average daily flow is 0.008 MGD. There are 45 modular homes served by this facility at the present. From this, it is concluded that the unit waste generation rate is 110 gpd per modular home.

3.2 Future Possible Average Flow


The future possible average flow to this facility is calculated in table 3.2 under the premise that the maximum future or build out flow is equal to the maximum number of units that contribute wastewater times their unit waste generation rate.

Table 3.2Future Possible Average Flow

Type of Unit	#of	Units	Unit Waste Generation Rate	Future Flow
modular homes	295	110 g	pd per modular home	0.033MGD

3.3 Growth Rate

Future growth rates can be predicted from several methods. In general, the major methods are: linear regression of historical flow, local municipal comprehensive plan projections, and site specific knowledge. In this case, a linear projection based on a review of the last few years of flow was performed. The result is as shown below (see next section, discussion):



4.0 SUMMARY AND RECOMMENDATIONS

Based on the analysis of the wastewater treatment plant, effluent disposal or reuse system and sludge handling stream, the maximum ratable capacity of the system as a whole is 0.015 MGD, as noted in the foregoing sections.

Future maximum capacity anticipated is 0.033 MGD.

This facility has been around since it appears 1984. The historical record of flows (see appendix) indicates low flow and little increase in flow until the last few years.

With new owners, it is difficult to make a reliable forecast of the future, however, it seems likely that facility capacity could be reached within 10 years.

Within 5 years, annual average flow, based on a linear projection, should increase from the present 0.005 MGD to 0.011 MGD.

It is recommended that the owner begin planning for a plant expansion as required by the FDEP. Since the facility has been previously permitted for an expansion, these plans should be reviewed for appropriateness.

This capacity analysis report should be updated within 2 years.

APPENDIX

• (

.

Note: all data shown obtained electronically from FDEP Tallahassee information services

	Flow	3MADF
Mo/Yr	Mo Avg	
1/1/1992	0.0027	
6/29/1992	0.005	
7/29/1992	0.003	
8/28/1992	0.003	
9/27/1992	0.003	
3/1/1994	0.003	
3/31/1994	0.0044	
4/30/1994	0.005	
9/1/1994	0.004	
10/1/1994	0.003	
11/1/1994	0.004	
12/1/1994	0.005	
1/15/1995	0.005	
2/14/1995	0.006	
3/16/1995	0.006	
4/15/1995	0.0022	
5/15/1995	0.0018	
6/14/1995	0.0019	
7/14/1995	0.0027	
8/13/1995	0.0025	
9/12/1995	0.0034	
10/12/1995	0.003	
11/11/1995	0.0023	
1/15/1996	0.0023	
2/14/1996	0.0022	
4/15/1996	0.0026	
5/15/1996	0.0021	
6/14/1996	0.002	
7/14/1996	0.002	
8/13/1996	0.0025	
9/12/1996	0.0022	
10/12/1996	0.005	
11/11/1996	0.0021	
12/11/1996	0.0021	
6/15/1997	0.001	
7/15/1997	0.002	
8/14/1997	0.002	
9/13/1997	0.002	
10/13/1997	0.002	
11/12/1997	0.002	
12/12/1997	0.002	

1/11/1998 2/10/1998 3/12/1998 4/11/1998 5/11/1998 6/10/1998 7/10/1998 9/8/1998 10/8/1998 10/8/1998 12/7/1998 12/7/1998 1/6/1999 2/28/1999 3/31/1999 4/30/1999	0.002 0.003 0.002 0.002 0.002 0.002 0.002 0.002 0.002 0.002 0.002 0.002 0.002 0.002 0.002 0.001 0.001	
6/30/1999	0.001	0.001
7/31/1999	0.001	0.001
8/31/1999	0.001	0.001
9/30/1999	0.001	0.001
10/31/1999	0.001	0.001
11/30/1999	0.001	0.001
12/31/1999	0.001	0.001
1/31/2000	0.001	0.001
2/29/2000	0.001	0.001
3/31/2000	0.001	0.001
4/30/2000	0.001	0.001
5/31/2000	0.001	0.001
6/30/2000	0.001	0.001
7/31/2000	0.001	0.0011
8/31/2000	0.002	0.0014
8/31/2000	0.002	0.0014
9/30/2000	0.002	0.002
9/30/2000	0.002	0.002
10/31/2000	0.002	0.002

,

•

1/31/2001	0.002	0.002
2/28/2001	0.002	0.002
3/31/2001	0.001	0.002
4/30/2001	0.001	0.002
5/31/2001	0.001	0.001
6/30/2001	0.001	0.001
7/31/2001	0.002	0.001
8/31/2001	0.002	0.002
9/30/2001	0.002	0.002
10/31/2001	0.002	0.002
11/30/2001	0.002	0.002
12/31/2001	0.002	0.002
1/31/2002	0.002	0.002
2/28/2002	0.002	0.002
3/31/2002	0.002	0.002
4/30/2002	0.002	0.002
5/31/2002	0.005	0.003
6/30/2002	0.005	0.004
7/31/2002	0.008	0.006
8/31/2002	0.006	0.006
9/30/2002	0.001	0.005
10/31/2002	0.001	0.002
11/30/2002	0.002	0.002
12/31/2002	0.0088	0.004
1/31/2003	0.0079	0.006
2/28/2003	0.0058	0.008
3/31/2003	0.0064	0.001
4/30/2003	0.0084	0.007
5/31/2003	0.0036	0.006

x ::

6/30/2003	0.0049	0.006
7/31/2003	0.0045	0.004
8/31/2003	0.0054	0.005
9/30/2003	0.0048	0.005

• .

.

.

27

MSM UTILITIES, LLC

DOCKECT NO. 050587-WS

ATTACHMENT TO RESPONSE NO. 12 to STAFF'S FIRST DATA REQUEST

SERVICE AVAILABILITY CHARGES and PLANT EXPANSION COSTS MSM does not currently have any approved Service Availability Charges (SACs) nor does it have an approved Meter Installation Fee. It is MSM's intent that such charges be proposed and approved as a part of this SARC. MSM had not specifically requested that SACs be set as a part of the SARC. But, based on prior experience, MSM anticipated that Staff would analyze the SAC situation as a part of its SARC analysis. Without knowledge of the outcome of the SARC, MSM did not have a base from which to determine said charges. MSM has reviewed the Staff Audit and now has a sufficient base from which SACs can be developed.

MSM intends to expand its water supply and treatment and wastewater treatment facilities in 2007. The current capacity of the water supply and reverse osmosis (R/O) treatment facilities is 90,000 GPD. The utility plans to expand the facility to 150,000 GPD capacity in 2007. Based on design flows of 250 GPD/ERC the plant should be able to serve 600 ERCs. At the anticipated rate of development, the expanded facilities should reach buildout in 2011 or five years from the year the facilities are placed in service. The estimated cost of expanding the water supply and treatment facilities is \$800,000 (See Table 8). The current capacity of the wastewater treatment plant is 15,000 GPD. This facility cannot be expanded at the present location. The existing facility will be removed from service and replaced in 2007 with a 90,000 GPD facility. Based on design flows of 200 GPD/ERC the plant should be able to serve 450 ERCs. At the anticipated rate of development, the expanded facilities should reach buildout in 2010 or four years from the year the facilities are placed in service. The estimated cost of the new wastewater treatment facility is \$1,320,000 (See Table 9).

In the tables that follow, MSM has projected plant in service, accumulated depreciation, CIAC and accumulated amortization through the year 2011. Based on those projections, MSM has calculated a System Capacity Charge that will result in a ration of net CIAC to net Plant of 75% at buildout for the water and wastewater systems. As indicated in Tables 1 and 2, MSM believes that the appropriate SAC charges are a System Capacity Charge per ERC of \$638.10 for water and \$1,762.40 for wastewater. MSM requests the approval of those charges.

In reaching its conclusions, MSM took into consideration the following:

1. The existing plant and CIAC balances and the related depreciation and amortization.

2. The existing number of ERCs served.

3. The estimated rate of development.

4. The policy that all future distribution and collection infrastructure will be contributed by the developer. An estimate of the per lot cost for this infrastructure and the offsetting contributions are accounted for in the calculations. The per lot estimates are based on recent bids for a similar size system (See Tables 6 and 7).

5. A Meter Installation Fee of \$183.00 is being requested in this SARC, the support for which is contained in response to Staff First Data Request No. 11. The meter costs and offsetting fees are accounted for in the calculations (See Tables 6 and 7).

6. The existing wastewater treatment facility will be removed from service. The removal of the associated original cost and accumulated depreciation are reflected in the calculations (See Table 4).

It will be necessary for MSM to revise its tariffs to reflect any approved fees and policy changes. The tariff sheets that will need revising are Water Tariff Sheet Nos. 17.0, 21.0 and 24.0 and Wastewater Tariff Sheet Nos. 16.0 and 22.0.

MSM UTILITIES, LLC DOCKET NO. 050587-WS CALCULATION AND SUPPORT FOR SYSTEM CAPACITY CHARGES

INDEX OF TABLES

Table Description

- 1 Water System Projected Account Balances by Year and Calculation of System Capacity Charge Buildout Year - 2011
- 2 Wastewater System Projected Account Balances by Year and Calculation of System Capacity Charge Buildout Year - 2010
- 3 System Design Flows
- 4 Depreciable Asset as of 12/31/05
- 5 CIAC as of 12/31/05
- 6 Assets Associated with Planned Expansion in 2007
- 7 Distribution & Collection CIAC Associated with Planned Expansion Beginning in 2007
- 8 Engineer's Preliminary Opinion of Costs Water Plant Expansion
- 9 Engineer's Preliminary Opinion of Costs Wastewater Treatment Plant Expansion

MSM UTILITIES, LLC DOCKET NO. 050587-WS WATER SYSTEM PROJECTED ACCOUNT BALANCES BY YEAR AND CALCULATION OF SYSTEM CAPACITY CHARGE WATER PLANT BUILDOUT YEAR - 2011

	12/31/04	12/31/05	12/31/06	12/31/07	12/31/08	12/31/09	12/31/10	12/31/11
Plant in Service Balances Existing Plant	377,986.88	377,986.88	377,986.88	377,986.88	377,986.88	377,986.88	377,986.88	377,986.88
Planned Additions Total	377,986.88	377,986.88	377,986.88	926,840.00 1,304,826.88	1,053,680.00 1,431,666.88	1,180,520.00 1,558,506.88	1,307,360.00 1,685,346.88	1,376,065.00 1,754,051.88
		·						
Accumulated Depreciation Existing Plant	251,503.00	266,916.42	280,189.84	293,463.27	306,736.69	319,280.81	328,184.52	335,903.61
Planned Additions Total	251,503.00	266,916.42	280,189.84	21,031.41 314,494.67	65,136.71 371,873.39	113,326.97 432,607.79	165,602.21 493,786.73	221,026.27 556,929.89
			,	- · · , · - · ·		,		
CIAC Existing CIAC	89,840.00	89,840.00	89,840.00	89,840.00	89,840.00	89,840.00	89,840.00	89,840.00
Planned Additions - Distribution System Charge				126,840.00 76,572.00	253,680.00 153,144.00	380,520.00 229,716.00	507,360.00 306,288.00	576,065.00 347,764.50
Total	89,840.00	89,840.00	89,840.00	293,252.00	496,664.00	700,076.00	903,488.00	1,013,669.50
Accumulated Amortization Existing CIAC	36,566.00	40,269.12	43,972.24	47,675.36	51,378.48	55,081,60	58,784.72	62,487.84
Planned Additions - Distribution	00,000.00	40,200.72	-10,012.24	2,042.48	8,169.94	18,382.35	32,679.74	50,125.96
System Charge Total	36,566.00	40,269.12	43,972.24	37.50 49,755.34	224.99 59,773.40	712.45 74,176.41	1,649.89 93,114.36	3,170.10 115,783.90
	,							
Net Plant Net CIAC	126,483.88 53,274.00	111,070.46 49,570.88	97,797.04 45,867.76	990,332.21 243,496.66	1,059,793.49 436.890.60	1,125,899.09 625,899.59	1,191,560.15 810,373.64	1,197,121.99 897,885.60
Ratio- Net CIAC/Net Plant	42.12%	44.63%	46.90%	24.59%	41.22%	55.59%	68.01%	75.00%
Added ERCs	¢ 000.40			120	120	120	120	65
Proposed System Charge per ERC Average Amort. Rate in Buildout Year	\$ 638.10 3.67%					*		

TABLE 1

MSM UTILITIES, LLC DOCKET NO. 050587-WS WATER SYSTEM PROJECTED ACCOUNT BALANCES BY YEAR AND CALCULATION OF SYSTEM CAPACITY CHARGE WASTEWATER PLANT BUILDOUT YEAR - 2010

Plant in Service Balances	12/31/04	12/31/05	12/31/06	12/31/07	12/31/08	12/31/09	12/31/10	12/31/11
Existing Plant	158,366.00	158,366.00	158,366.00	158,366.00	158,366.00	158,366.00	158,366.00	158,366.00
Planned Additions Total	158,366.00	158,366.00	158,366.00	1,427,520.00 1,585,886.00	1,535,040.00 1,693,406.00	1,642,560.00 1,800,926.00	1,673,920.00 1,832,286.00	1,673,920.00 1,832,286.00
Accumulated Depreciation Existing Plant Planned Additions	98,230.00	101,898.51	105,567. 01	109,235.52 45,160.82	112,904.03 138,065.52	116,270.13 236,136.30	119,312.15 337,543.52	122,354.18 439,704.13
Total	98,230.00	101,898.51	105,567.01	154,396.34	250,969.54	352,406.43	456,855.67	562,058.31
CIAC Balances Existing CIAC Planned Additions - Distribution	96,166.00	96,166.00	96,166.00	96,166.00 107,520.00	96,166.00 215,040.00	96,166.00 322,560.00	96,166.00 353,920.00	96,166.00 353,920.00
System Charge	00 400 00	00 400 00	00 400 00	211,488.00	422,976.00	634,464.00	696,148.00	696,148.00
Total	96,166.00	96,166.00	96,166.00	415,174.00	734,182.00	1,053,190.00	1,146,234.00	1,146,234.00
Accumulated Amortization Existing CIAC	<u></u>	CO CON E1	05 007 04	68.035.52	70 704 00	72.070.10	75 440 45	77.154.18
Planned Additions - Distribution	60,030.00	62,698.51	65,367.01	2,583.05	70,704.03 10,332.18	73,070.13 23,247.41	75,112.15 39,499.08	56,504.13
System Charge Total	60.020.00	00 000 E1	05 007 01	74.26	445.55	1,410.91	3,214.78	5,974.72
i otal	60,030.00	62,698.51	65,367.01	70,618.57	81,036.21	96,317.54	114,611.23	133,658.31
· ·								
Net Plant Net CIAC Ratio- Net CIAC/Net Plant	60,136.00 36,136.00 60.09%	56,467.49 33,467.49 59.27%	52,798.99 30,798.99 58.33%	1,431,489.66 344,555.43 24.07%	1,442,436.46 653,145.79 45.28%	1,448,519.57 956,872.46 66.06%	1,375,430.33 1,031,622.77 75.00%	1,270,227.69 1,012,575.69 79.72%
Added ERCs Proposed System Charge per ERC Average Amort. Rate in Buildout Year	\$ 1,762.40 5.75%			120	120	120	35	0

TABLE 2

MSM UTILITIES, LLC SYSTEM DESIGN FLOWS SOURCE: AM ENGINEERING, INC.

Water System

•

Capacity	150,000	gpd
gpd/ERC	250	peak flow
Capacity	600	ERCs
Existing ERCs	55	
New ERCs	545	

Wastewater	System		
Capacity		90,000	gpd
gpd/ERC		200	3 mo avg
Capacity		450	ERCs
		55	
New ERCs		395	

Projected Growth 120 per year per MSM

TABLE 3

MSM UTILITIES, LLC DEPRECIABLE ASSETS AS OF 12/31/05 SOURCE: PSC STAFF AUDIT REPORT, DOCKET NO. 050587-WS

	Water System			A			A	A	A	Assum	Appual
			Accum.	Annual							
Naruc		Plant	Depr.	Depr./Amort.							
Acct.		10/31/05	12/31/04	12/31/05	12/31/06	12/31/07	12/31/08	12/31/09	12/31/10	12/31/11	Rate
304.0	Structures, Bldg	108,920.00	87,593.00	91,627.07	95,661.15	99,695.22	103,729.30	107,763.37	108,920.00	108,920.00	3.70%
304.0	Structures, Electrical	26,600.00	22,163.00	23,148.19	24,133.37	25,118.56	26,103.74	26,600.00	26,600.00	26,600.00	3.70%
307.0	Wells	13,070.00	10,890.00	11,374.07	11,858.15	12,342.22	12,826.30	13,070.00	13,070.00	13,070.00	3.70%
309.0	Supply Mains	10,025.00	7,043.00	7,356.28	7,669.56	7,982.84	8,296.13	8,609.41	8,922.69	9,235.97	3.13%
334.0	Flow Meters	1,550.00	1,550.00	1,550.00	1,550.00	1,550.00	1,550.00	1,550.00	1,550.00	1,550.00	5.88%
311.0	Pumping Equipment	4,000.00	4,000.00	4,000.00	4,000.00	4,000.00	4,000.00	4,000.00	4,000.00	4,000.00	5.88%
320.0	WTP, Original	48,658.00	46,518.00	48,658.00	48,658.00	48,658.00	48,658.00	48,658.00	48,658.00	48,658.00	5.88%
320.0	WTP Replace	85,683.00	22,680.00	27,720.18	32,760.35	37,800.53	42,840.71	47,880.88	52,921.06	57,961.24	5.88%
330.0	Dist. Reservoirs	23,500.00	16,020.00	16,732.12	17,444.24	18,156.36	18,868.48	19,580.61	20,292.73	21,004.85	3.03%
331.0	Dist. Lines	35,107.00	20,790.00	21,713.87	22,637.74	23,561.61	24,485.47	25,409.34	26,333.21	27,257.08	2.63%
333.0	Services	11,425.00	7,335.00	7,661.43	7,987.86	8,314.29	8,640.71	8,967.14	9,293.57	9,620.00	2.86%
334.0	Meters, installed	5,360.91	2,609.00	2,924.35	3,239.70	3,555.04	3,870.39	4,185.74	4,501.09	4,816.43	5.88%
335.0	Hydrants	2,800.00	1,575.00	1,645.00	1,715.00	1,785.00	1,855.00	1,925.00	1,995.00	2,065.00	2.50%
339.0	Misc. Equip.	1,019.99	737.00	788.00	839.00	890.00	941.00	992.00	1,019.99	1,019.99	5.00%
343.0	Equipment	267.98	-	17.87	35.73	53.60	71.46	89.33	107.19	125.06	6.67%
	Total	377,986.88	251,503.00	266,916.42	280,189.84	293,463.27	306,736.69	319,280.81	328,184.52	335,903.61	

	Wastewater System										
		1	Accum.	Annual							
Naruc		Plant	Depr.	Depr./Amort.							
Acct.	Wastewater	10/31/05	12/31/04	12/31/05	12/31/06	12/31/07	12/31/08	12/31/09	12/31/10	12/31/11	Rate
361.0	Collection - Gravity	62,241.00	35,010.00	36,566.03	38,122.05	39,678.08	41,234.10	42,790.13	44,346.15	45,902.18	2.50%
361.0	Collection - Manholes	16,915.00	14,085.00	14,711.48	15,337.96	15,964.44	16,590.93	16,915.00	16,915.00	16,915.00	3.70%
363.0	Service Laterals	17,010,00	10,935.00	11,421.00	11,907.00	12,393.00	12,879.00	13,365.00	13,851.00	14,337.00	2.86%
370.0	Receiving Wells	25,000.00	1,000.00	2,000.00	3,000.00	4,000.00	5,000.00	6,000.00	7,000.00	8,000.00	4.00%
380.0	WWTP	30,000.00	30,000.00	30,000.00	30,000.00	30,000.00	30,000.00	30,000.00	30,000.00	30,000.00	6.67%
380.0	Remove WWTP	(30,000.00)	(30,000.00)	(30,000.00)	(30,000.00)	(30,000.00)	(30,000.00)	(30,000.00)	(30,000.00)	(30,000.00)	
380.0	Ponds	37,200.00	37,200.00	37,200.00	37,200.00	37,200.00	37,200.00	37,200.00	37,200.00	37,200.00	6.67%
	Total	158,366.00	98,230.00	101,898.51	105,567.01	109,235.52	112,904.03	116,270.13	119,312.15	122,354.18	

MSM UTILITIES, LLC CIAC AS OF 12/31/05 SOURCE: PSC STAFF AUDIT REPORT, DOCKET NO. 050587-WS

Naruc Acct. 304.0 304.0 307.0 309.0 334.0	Water System Structures, Bldg Structures, Electrical Wells Supply Mains Flow Meters	CIAC 10/31/05	Water System Accum. Amort. 12/31/04	Accum. Amort. 12/31/05	Accum. Amort. 12/31/06	Accum. Amort. 12/31/07	Accum. Amort. 12/31/08	Accum. Amort. 12/31/09	Accum. Amort. 12/31/10	Accum. Amort. 12/31/11	Annual Depr./Amort. Rate 3.70% 3.70% 3.13% 5.88% 5.88%
311.0 320.0 320.0 330.0	Pumping Equipment WTP, Original WTP Replace Dist, Reservoirs	35,895.00	4,257.00	6,368.47	8,479.94	10,591.41	12,702.88	14,814.35	16,925.82	19,037.29	5.88% 5.88% 3.03%
331.0 333.0 334.0 335.0 339.0 343.0	Dist. Lines Services Meters, Installed Hydrants Misc. Equip. Equipment	35,107.00 11,425.00 4,613.00 2,800.00	20,790.00 7,335.00 2,609.00 1,575.00	21,713.87 7,661.43 2,880.35 1,645.00	22,637.74 7,987.86 3,151.71 1,715.00	23,561.61 8,314.29 3,423.06 1,785.00	24,485.47 8,640.71 3,694.41 1,855.00	25,409.34 8,967.14 3,965.76 1,925.00	26,333.21 9,293.57 4,237.12 1,995.00	27,257.08 9,620.00 4,508.47 2,065.00	2.63% 2.86% 5.88% 2.50% 5.00% 6.67%
	Total	89,840.00	36,566.00	40,269.12	43,972.24	47,675.36	51,378.48	55,081.60	58,784.72	62,487.84	
Naruc Acct. 361.0 361.0 363.0 370.0 380.0	Wastewater System Wastewater Collection - Gravity Collection - Manholes Service Laterals Receiving Wells WWTP	CIAC 10/31/05 62,241.00 16,915.00 17,010.00	Accum. Amort. 12/31/04 35,010.00 14,085.00 10,935.00	36,566.03 14,711.48 11,421.00	38,122.05 15,337.96 11,907.00	39,678.08 15,964.44 12,393.00	41,234.10 16,590.93 12,879.00	42,790.13 16,915.00 13,365.00	44,346.15 16,915.00 13,851.00	45,902.18 16,915.00 14,337.00	Annual Depr./Amort. Rate 2.50% 3.70% 2.86% 4.00% 6.67%
380.0	Ponds Total	96,166.00	60,030.00	62,698.51	65,367.01	68,035.52	70,704.03	73,070.13	75,112.15	77,154.18	6.67%

TABLE 5

.

٠

.

MSM UTILITIES, LLC ASSETS ASSOCIATED WITH PLANNED EXPANSION IN 2007 SOURCE FOR PLANT EXPANSION: AM ENGINEERING, INC. SOURCE FOR DISTRIBUTION & COLLECTION: AM ENGINEERING RECENT BID

	Water System					Accum.	Accum.	Accum.	Accum.	Accum,
Naruc Acct.		Year Installed	Plant	E&OH	Total	Depr. 12/31/07	Depr. 12/31/08	Depr. 12/31/09	Depr. 12/31/10	Depr. 12/31/11
304.0	Structures, Bldg	2007	100,000.00	23,076.92	123,076.92	2,279.20	6,837.61	11,396.01	15,954.42	20,512.82
307.0	Wells	2007	18,000.00	4,153.85 5,076.92	22,153.85	410.26	1,230.77	2,051.28	2,871.79	3,692.31
311.0 320.0	Pumping Equipment WTP, Original	2007 2007	22,000.00 300,000.00	69,230.77	27,076.92 369,230.77	796.38 10,859.73	2,389.14 32,579.19	3,981.90 54,298.64	5,574.66 76,018.10	7,167.42 97,737.56
330.0	Dist. Reservoirs	2007	150,000.00	34,615.38	184,615.38	2,797.20	8,391.61	13,986.01	19,580.42	25,174.83
331.0	Dist. Lines - 120 lots @ \$517/lot	2007			62,040.00	816.32	2,448.95	4,081.58	5,714.21	7,346.84
	Dist. Lines - 120 lots @ \$517/lot Dist. Lines - 120 lots @ \$517/lot	2008 2009			62,040.00 62,040.00		816.32	2,448.95 816.32	4,081.58 2,448.95	5,714.21 4,081.58
	Dist. Lines - 120 lots @ \$517/lot	2010			62,040.00			010.02	816.32	2,448.95
	Dist. Lines - 65 lots @ \$517/lot	2011			33,605.00		4 47 4 49	1 704 40		442.17
333.0	Services - 120 lots @ \$209/lot Services - 120 lots @ \$209/lot	2007 2008			25,080.00 25,080.00	358.29	1,074.86 358.29	1,791.43 1,074.86	2,508.00 1,791.43	3,224.57 2,508.00
	Services - 120 lots @ \$209/lot	2009			25,080.00		000.20	358.29	1,074.86	1,791.43
	Services - 120 lots @ \$209/lot	2010			25,080.00				358.29	1,074.86
334.0	Services - 65 lots @ \$209/lot Meters, Installed - 120 lots @ \$183/lot	2011 2007			13,585.00 21,960.00	645.88	1,937.65	3,229.41	4,521.18	194.07 5,812.94
334.0	Meters, Installed - 120 lots @ \$183/lot	2008			21,960.00		645.88	1,937.65	3,229.41	4,521.18
	Meters, installed - 120 lots @ \$183/lot	2009			21,960.00			645.88	1,937.65	3,229.41
	Meters, Installed - 120 lots @ \$183/lot Meters, Installed - 65 lots @ \$183/lot	2010 2011			21,960.00 11,895.00				645.88	1,937.65 349.85
335.0	Hydrants - 120 lots @ \$148/lot	2007			17,760.00	222.00	666.00	1,110.00	1,554.00	1,998.00
	Hydrants - 120 lots @ \$148/lot	2008			17,760.00		222.00	666.00	1,110.00	1,554.00
	Hydrants - 120 lots @ \$148/lot Hydrants - 120 lots @ \$148/lot	2009 2010			17,760.00 17,760.00			222.00	666.00 222.00	1,110.00 666.00
	Hydrants - 65 lots @ \$148/lot	2010			9,620.00				222.00	120.25
339.0	Mise, Equip.	2007	60,000.00	13,846.15	73,846.15	1,846.15	5,538.46	9,230.77	12,923.08	16,615.38
	Total Water		650,000.00	150,000.00	1,376,065.00	21,031.41	65,136.71	113,326.97	165,602.21	221,026.27
	Wastewater System					Accum.	Accum.	Accum.	Accum.	Accum.
Naruc			Plant	5 8 00	Tabal	Depr.	Depr.	Depr.	Depr.	Depr.
Acct. 360.0	Piping between plant & drainfields	2007	10/31/05 80,000.00	E & OH 16,000.00	Total 96,000.00	12/31/07 1,777.78	12/31/08 5,333.33	12/31/09 8,888.89	12/31/10 12,444.44	12/31/11 16,000.00
360.0	Collection, F.M 120 lots @ \$148	2007			17,760.00	328.89	986.67	1,644.44	2,302.22	2,960.00
	Collection, F.M 120 lots @ \$148	2008			17,760.00 17,760.00		328.89	986.67	1,644.44	2,302.22
	Collection, F.M 120 lots @ \$148 Collection, F.M 35 lots @ \$148	2009 2010			5,180.00			328.89	986,67 95,93	1,644.44 287.78
		2011								•
361.0	Collection - Gravity - 120 lots @ \$583	2007 2008			69,960.00 69,960.00	874.50	2,623.50 874.50	4,372.50 2,623.50	6,121.50 4,372.50	7,870.50 6,121.50
	Collection - Gravity - 120 lots @ \$583 Collection - Gravity - 120 lots @ \$583	2008			69,960.00		074.00	874.50	2,623.50	4,372.50
	Collection - Gravity - 35 lots @ \$583	2010			20,405.00				255.06	765.19
000.0	Creation Laterala, 100 lata @ \$165	2011 2007			19,800.00	282.86	848.57	1,414.29	1,980.00	2,545.71
363.0	Service Laterals - 120 lots @ \$165 Service Laterals - 120 lots @ \$165	2007			19,800.00	202.00	282.86	848.57	1,414.29	1,980.00
	Service Laterals - 120 lots @ \$165	2009			19,800.00			282.86	848.57	1,414.29
	Service Laterals - 35 lots @ \$165	2010 2011			5,775.00				82.50	247.50
370.0	Receiving Wells	2011								
	Lift Stations - 120 lots @ \$237	2007			28,440.00	568.80	1,706.40	2,844.00	3,981.60	5,119.20
	Lift Stations - 120 lots @ \$237 Lift Stations - 120 lots @ \$237	2008 2009			28,440.00 28,440.00		568.80	1,706.40 568.80	2,844.00 1,706.40	3,981.60 2,844.00
	Lift Stations - 35 lots @ \$237	2010			8,295.00				165.90	497.70
		2011								
370.0	Pumping Equipment Lift Stations - 120 lots @ \$132	2007			15,840.00	528.00	1,584.00	2,640.00	3,696.00	4,752.00
	Lift Stations - 120 lots @ \$132	2008			15,840.00		528.00	1,584.00	2,640.00	3,696.00
	Lift Stations - 120 lots @ \$132	2009 2010			15,840.00 4,620.00			528.00	1,584.00 154.00	2,640.00 462.00
	Lift Stations - 35 lots @ \$132	2010			4,020.00				104.00	402.00
				~~ ~~~ ~~		40.000.00	00.000.00	~~~~~~	04.000.00	400 000 00
380.0	WWTP Drainfields	2007 2007	300,000.00 720,000.00	60,000.00 144,000.00	360,000.00 864,000.00	12,000.00 28,800.00	36,000.00 86,400.00	60,000.00 144,000.00	84,000.00 201,600.00	108,000.00 259,200.00
380.0	Total Wastewater	2007	1,100,000.00		1,819,675.00	45,160.82	138,065.52	236,136.30	337,543.52	439,704.13
			2007	2008	2009	2010	2011			
	Plant Additions By Year		2007	2000	2000	2010				
	Water System		926,840.00	126,840.00	126,840.00	126,840.00	68,705.00			
	Wastewater System		1,427,520.00	107,520.00	107,520.00	31,360.00	•			
	Plant Additions - Cumulative									
	Water System			1,053,680.00		1,307,360.00	1,376,065.00			
	Wastewater System		1,427,520.00	1,535,040.00	1,042,000.00	1,673,920.00	1,673,920.00			

TABLE 6

MSM UTILITIES, LLC

DISTRIBUTION & COLLECTION CIAC ASSOCIATED WITH PLANNED EXPANSION BEGINNING IN 2007 SOURCE FOR DISTRIBUTION & COLLECTION: AM ENGINEERING RECENT BID

Water System Accum Accum. Accum. Accum. Accum Annual Naruc Year Dist Amort. Amort Amort Amort Amort. Depr./Amort. Installed CIAC 12/31/07 12/31/08 12/31/09 12/31/10 12/31/11 Acct Rate 2007 Structures, Bida 3.70% 304.0 2007 3,70% 307.0 Wells 2007 Pumping Equipment 5.88% 311.0 WTP, Original 2007 5.88% 320.0 Dist. Reservoirs 2007 330.0 3.03% 2007 62,040.00 816.32 2,448.95 4,081.58 Dist. Lines - 120 lots @ \$517/lot 5.714.21 7.346.84 2.63% 331.0 Dist. Lines - 120 lots @ \$517/lot 2008 62,040.00 816.32 2,448.95 4,081.58 5,714.21 2.63% Dist. Lines - 120 lots @ \$517/lot 2009 62,040.00 816.32 2,448.95 4.081.58 2.63% Dist. Lines - 120 lots @ \$517/lot 2010 62,040.00 2,448.95 816.32 2.63% 33,605.00 Dist. Lines - 65 lots @ \$517/lot 2011 442.17 2.63% Services - 120 lots @ \$209/lot 25,080.00 333.0 2007 358.29 1,074.86 1,791.43 2,508.00 3.224.57 2.86% Services - 120 lots @ \$209/lot 2008 25,080.00 358.29 1.074.86 1,791.43 2,508.00 2.86% 25,080.00 Services - 120 lots @ \$209/lot 2009 358.29 1,074.86 1,791.43 2.86% Services - 120 lots @ \$209/lot 2010 25,080.00 358.29 1,074.86 2.86% Services - 65 lots @ \$209/lot 2011 13,585.00 194.07 2.86% 334.0 Meters, Installed - 120 lots @ \$181/lot 2007 21,960.00 645.88 1,937.65 3,229.41 4,521.18 5,812.94 5.88% Meters, installed - 120 lots @ \$181/lot 2008 21,960.00 645.88 1,937.65 3,229.41 4,521.18 5.88% Meters, installed - 120 lots @ \$181/lot 2009 21,960.00 645.88 1,937.65 3,229.41 5.88% 2010 21,960.00 Meters, Installed - 120 lots @ \$181/lot 645.88 1,937.65 5.88% 11.895.00 Meters, Installed - 65 lots @ \$181/lot 2011 349.85 5.88% 17,760.00 335.0 Hydrants - 120 lots @ \$148/lot 2007 222.00 666.00 1.110.00 1.554.00 1,998.00 2.50% 2008 17 760 00 Hydrants - 120 lots @ \$148/lot 222.00 666.00 1,110.00 1.554.00 2.50% Hydrants - 120 lots @ \$148/lot 2009 17 760.00 222.00 666.00 1,110.00 2.50% 2010 Hydrants - 120 lots @ \$148/lot 17.760.00 222 00 666.00 2.50% 2011 9,620.00 Hydrants - 65 lots @ \$148/lot 120.25 2 50% 339.0 2007 Misc. Equip. 5.00% Total Water 576,065.00 2,042.48 8,169.94 18,382.35 32,679,74 50.125.96 Wastewater System Accum. Accum. Accum. Accum. Accum. Annual Naruc Collection Amort. Amort. Amort. Depr./Amort. Amort. Amort. CIAC 12/31/07 12/31/08 12/31/09 12/31/10 12/31/11 Rate Acct Piping between plant & drainfields 2007 3.70% 360.0 2007 Collection, F.M. - 120 lots @ \$148 17,760.00 328 89 986.67 1,644.44 2,302.22 360.0 2,960.00 3.70% Collection, F.M. - 120 lots @ \$148 2008 17,760.00 328.89 986.67 1.644.44 2.302.22 3.70% Collection, F.M. - 120 lots @ \$148 17,760.00 2009 328.89 986.67 1,644,44 3.70% Collection, F.M. - 35 lots @ \$148 2010 5,180.00 95.93 287.78 3.70% 2011 3.70% 2007 69,960.00 2,623,50 7.870.50 361.0 Collection - Gravity - 120 lots @ \$583 874 50 4,372.50 6,121.50 2.50% Collection - Gravity - 120 lots @ \$583 2008 69,960.00 874.50 2.50% 2,623.50 4,372.50 6,121.50 Collection - Gravity - 120 lots @ \$583 2009 69,960.00 874.50 2,623.50 4,372.50 2.50% Collection - Gravity - 35 lots @ \$583 2010 20,405.00 2.50% 255.06 765.19 2011 2.50% 363.0 Service Laterals - 120 lots @ \$165 2007 19,800.00 282.86 848.57 1,414.29 1,980.00 2,545.71 2.86% Service Laterals - 120 lots @ \$165 2008 19,800.00 282.86 848.57 1,414.29 1,980.00 2.86% Service Laterals - 120 lots @ \$165 2009 19,800.00 282.86 848.57 1,414.29 2.86% Service Laterals - 35 lots @ \$165 2010 5,775.00 82.50 247.50 2.86% 2011 2.86% 370.0 **Receiving Wells** 2007 28,440,00 Lift Stations - 120 lots @ \$237 568 80 1 706 40 2 844 00 3 981 60 5 119 20 4 00% 28,440.00 2008 568.80 1,706.40 2,844.00 Lift Stations - 120 lots @ \$237 3.981.60 4 00% 2009 28,440.00 Lift Stations - 120 lots @ \$237 568.80 1,706.40 2,844.00 4.00% 2010 8,295.00 165.90 497.70 4.00% Lift Stations - 35 lots @ \$237 2011 4.00% Pumping Equipment Lift Stations - 120 lots @ \$132 2007 15,840.00 528.00 1,584.00 2,640.00 3,696.00 4,752.00 6.67% Lift Stations - 120 lots @ \$132 2008 15,840.00 528.00 1,584.00 2,640.00 3,696.00 6.67% Lift Stations - 120 lots @ \$132 Lift Stations - 35 lots @ \$132 2009 15,840.00 528.00 1,584.00 2,640.00 6.67% 4,620.00 2010 154.00 462.00 6.67% 2011 6.67% 2007 6.67% 380.0 WWTP 2007 6.67% Drainfields 380.0 499,675.00 2,583.05 10,332.18 23,247.41 39,499.08 56,504.13 Total Wastewater 2007 2008 2009 2010 2011 CIAC Additions By Year 126.840.00 126,840,00 126.840.00 126,840.00 68.705.00 Water System 107,520,00 107,520.00 31,360.00 107.520.00 Wastewater System CIAC Additions - Cumulative 126,840.00 253 680 00 380 520 00 507 360 00 576 065 00 Water System 215,040.00 322 560 00 107.520.00 353,920,00 353,920,00 Wastewater System

TABLE 7

TABLE 8



Consulting Engineers - Surveyors 6320 Tower Lane, Sarasota, FL 34240-8809 Telephone (941) 377-9178 Facsimile (941) 378-3786

ENGINEER'S PRELIMINARY OPINION OF COSTS FOR RIVERS EDGE UTILITY 150,000 WATER PLANT EXPANSION*

<u>ITEM</u>	DESCRIPTION	ESTIMATED COST
1.	Construct two 150 GPM wells with pump and controls	\$18,000
2.	Construct 150,000 GPD water plant with controls and generator	300,000
3.	Construct 150,000 gallon storage tank	150,000
4.	Construct building for water plant and pumps	100,000
5.	High service pumps and controls	22,000
6.	Sitework and piping	<u>60.000</u>
	Total Estimated Construction Costs	\$650,000
-	Engineering, Contingencies, Administration & Permits	<u>150,000</u>
	Total Estimated Project Cost	<u>\$800,000</u>

*Not Including Concentrate Disposal

MLTS-0001

09/30/05

TABLE 9

Consulting Engineers - Surveyors

6320 Tower Lane, Sarasota, FL 34240-8809 Telephone (941) 377-9178 Facsimile (941) 378-3786

ENGINEER'S PRELIMINARY OPINION OF COSTS FOR RIVERS EDGE UTILITY 90,000 WASTEWATER TREATMENT PLANT EXPANSION

ITEM	DESCRIPTION	ESTIMATED COST
1.	90,000 GPD Wastewater treatment plant with filters and generator	\$300,000
2.	Four acre drainfields including sitework, piping and miscellaneous	720,000
3.	Piping to site and from plant to drainfields	80.000
	Total Estimated Construction Costs	\$1,100,000
	Engineering, Contingencies, Administration & Permits	<u>220,000</u>
	Total Estimated Project Cost	<u>\$1,320,000</u>

MLTS-0001

09/30/05

