

**Report to the Florida Public Service Commission Pursuant to
Rule 25-6.0343, F.A.C.
Calendar Year 2019**

1) Introduction

- a) Florida Keys Electric Cooperative Association, Inc.
- b) 91630 Overseas Highway
Tavernier, Florida 33070
- c) Scott Newberry
Chief Executive Officer
Phone – (305) 852-2431
Fax – (305) 852-4794
Email – scott.newberry@fkec.com

2) Number of meters served in calendar year 2019

32,926

3) Standards of Construction

- a) National Electric Safety Code Compliance

Construction standards, policies, guidelines, practices, and procedures at Florida Keys Electric Cooperative Association, Inc., comply with the National Electrical Safety Code (ANSI C-2) [NESC]. For electrical facilities constructed on or after February 1, 2007, the 2007 NESC applies. Electrical facilities constructed prior to February 1, 2007, are governed by the edition of the NESC in effect at the time of the facilities initial construction.

- b) Extreme Wind Loading Standards

Florida Keys Electric Association, Inc., facilities were not originally designed to the extreme loading standards on a system wide basis. However, Florida Keys Electric Cooperative Association, Inc. adopted the extreme wind loading standard on April 24, 2006 for:

- a) New construction
- b) Major planned work, including expansion, reconstruction or relocation of existing facilities

c) Flooding or Storm Surges

Florida Keys Electric Cooperative Association, Inc. continues to evaluate and modify our standards, policies, guidelines, practices and procedures that address the effects of flooding and storm surges on underground facilities and supporting overhead facilities. FKEC participated in the Public Utility Research Center's (PURC) study on the conversion of overhead electric facilities to underground and the effectiveness of undergrounding facilities in preventing storm damage and outages through the Florida Electric Cooperative Association. Existing water levels, as well as potential storm surges, are factors that are taken into account when siting and route selection is determined for new facilities or upgrades.

d) Safe and Efficient Access of New and Replacement Distribution Poles

Electrical construction standards, policies, practices and procedures at Florida Keys Electric Cooperative Association, Inc., provide for placement of new and replacement distribution facilities so as to facilitate safe and efficient access for installation and maintenance. Wherever new facilities are placed, all facilities are installed so that FKEC facilities are accessible by its crews and vehicles to ensure proper maintenance/repair is performed as expeditiously and safely as possible. FKEC decides on a case-by-case basis whether existing facilities need to be relocated. If it is determined that facilities need to be relocated, they will be placed in the safest, most accessible area available.

e) Attachments by Others

Electrical construction standards, policies, guidelines, practices and procedures at Florida Keys Electric Cooperative Association, Inc., include written safety, pole reliability, pole loading capacity and engineering standards and procedures for attachments by others to the utility's electric transmission and distribution poles. FKEC included inspection of third party contacts in the formal distribution pole inspection which began in 2007 and was completed in 2010. Our second cycle of inspections resumed in 2015 and was completed in 2018. The company GIS system is continuously updated with field data collected and modified due to new construction and relocations.

FKEC is presently in negotiations with Comcast regarding a new joint use agreement. The previous agreement has expired.

4. Facility Inspections

a) Describe the utility's policies, guidelines, practices, and procedures for inspecting transmission and distribution lines, poles, and structures including, but not limited to, pole inspection cycles and pole selection process.

Florida Keys Electric Cooperative Association Inc. conducts aerial (helicopter patrol) and ground-based infrared inspections on all transmission/mainline distribution structures, and substation facilities annually. Any abnormal condition is documented and prioritized for remediation. FKEC also has started using supplemental aerial drone-based technology to collect information on individual structures for reliability and safety purposes.

Distribution poles are tested, inspected and treated on an eight-year cycle. FKEC began a formal distribution pole inspection and treatment program in 2007. All distribution wood poles (10,698) in the system were tested and treated between 2007 and 2010. All rejects (1003) were replaced. The wood pole reject rate for the 2007-2010 cycle was 9%.

The second cycle of inspections, treatments and replacements resumed in 2015 and was completed in 2018. During this current cycle, FKEC visually inspected all distribution structures including steel, concrete, ductal iron, and wood (14,179). The 11,808 wood poles were also tested and treated with a reject rate of 3.85%.

Routine distribution pole replacement continues as new construction, upgrades and relocation efforts require. The next full cycle-inspection routine will start no later than 2023.

b) Describe the number and percentage of transmission and distribution inspections planned and completed for 2019.

FKEC annually performs aerial helicopter patrol and infrared inspections on all (100%) of its transmission/mainline distribution structures, and substation facilities.

Routine distribution pole replacement continues as new construction, upgrades and relocation efforts require.

c) Describe the number and percentage of transmission poles and structures and distribution poles failing inspection in 2019 and the reason for the failure.

No transmission structures failed inspection during the 2019 inspection cycle.

114 transmission water structures were inspected in 2017 and the foundations were determined to be nearing the end of their life. Foundation repairs on these structures is scheduled to begin in 2020.

Routine distribution pole replacement continues as new construction, upgrades and relocation efforts require.

d) Describe the number and percentage of transmission poles and structures and distribution poles, by pole type and class of structure, replaced or for which remediation was taken after inspection in 2019, including a description of the remediation taken.

One transmission structure was replaced in 2019. It was a heavily guyed structure and it was replaced with a self-supporting structure.

There were 158 wood distribution reject poles identified in 2018. All 158 poles are scheduled to be replaced in 2019. All rejected poles were replaced in 2019 prior to the start of Hurricane season.

5. Vegetation Management

a) Describe the utility's policies, guidelines, practices, and procedures for vegetation management, including programs addressing appropriate planting, landscaping, and problem tree removal practices for vegetation management outside of road right-of-ways or easements, and an explanation as to why the utility believes its vegetation management practices are sufficient.

Florida Keys Electric Cooperative Association, Inc. inspects and trims, where necessary, the entire transmission system on an annual basis. Substations are inspected annually and trimmed when vegetation encroaches. The remainder of FKEC's distribution system is trimmed on a three-year cycle. FKEC has a formal trade-a-tree program that was implemented in 2007 to support the removal of problem trees located along/near the right of way. Proper planting information (species and guidelines on locations...) is readily available on the company website as well as the main office lobby areas. Vegetation related outages and power quality issues are monitored on a daily basis and any areas needing additional maintenance are completed by our in-house vegetation management resources.

b) Describe the quantity, level, and scope of vegetation management planned and completed for transmission and distribution facilities in 2019.

100% of the transmission facilities are inspected annually and vegetation management tasks are performed as needed. Also, all substation properties are inspected annually and vegetation management tasks are performed as needed.

Vegetation management tasks were performed on approximately 528 miles of overhead distribution facilities (primary, secondary and service) during 2019. Vegetation related outages and power quality issues are monitored on a daily basis and any areas needing additional maintenance are completed by our in-house vegetation management resources.

Report on Collaborative Research for Hurricane Hardening

Provided by

The Public Utility Research Center
University of Florida

To the

Utility Sponsor Steering Committee

Final Report dated February 2018

I. Introduction

The Florida Public Service Commission (FPSC) issued Order No. PSC-06-00351-PAA-EI on April 25, 2006 (Order 06-0351) directing each investor-owned electric utility (IOU) to establish a plan that increases collaborative research to further the development of storm resilient electric utility infrastructure and technologies that reduce storm restoration costs and outages to customers. This order directed IOUs to solicit participation from municipal electric utilities and rural electric cooperatives in addition to available educational and research organizations. As a means of accomplishing this task, the IOUs joined with the municipal electric utilities and rural electric cooperatives in the state (collectively referred to as the Project Sponsors) to form a Steering Committee of representatives from each utility and entered into a Memorandum of Understanding (MOU) with the University of Florida's Public Utility Research Center (PURC). The third extension of this MOU was approved last year by the Research Collaboration Partners and now extends through December 31, 2018.

PURC manages the work flow and communications, develops work plans, serves as a subject matter expert, conducts research, facilitates the hiring of experts, coordinates with research vendors, advises the Project Sponsors, and provides reports for Project activities. The collaborative research has focused on undergrounding, vegetation management, hurricane-wind speeds at granular levels, and improved materials for distribution facilities.

This report provides an update on the activities of the Steering Committee since the previous report dated February 2017.

II. Steering Committee Workshop

On December 5, the Steering Committee organized a web-based workshop for over 40 participants from the Project Sponsors hosted by the University of Florida. The workshop was held to orient new members on the model of the costs and benefits of storm hardening strategies and to discuss the integration of data from recent storm activities.

The presenter for the workshop was Ted Kury. He first described the model and the overall flow of the simulation element. He then described the 115 different inputs to the model and demonstrated where to find them. Next, he demonstrated a test run of 50 hurricane years for the state and demonstrated how the model illustrates the shift in the probability distribution of the outcome variables. Finally, he demonstrated the model's ability to simulate single hurricanes, both historical and hypothetical.

Following the demonstration, the members discussed strategies for adding data from recent storm experiences to the model.

III. Undergrounding

The collaborative research on undergrounding has been focused on understanding the existing research on the economics and effects of hardening strategies, including undergrounding, so that informed decisions can be made about undergrounding policies and specific undergrounding projects.

The collaborative has refined the computer model developed by Quanta Technologies and there has been a collective effort to learn more about the function and functionality of the computer code. PURC and the Project Sponsors have worked to fill information gaps for model inputs and significant efforts have been invested in the area of forensics data collection.

In addition, PURC has worked with doctoral and master's candidates in the University of Florida Department of Civil and Coastal Engineering to assess some of the inter-relationships between wind speed and other environmental factors on utility equipment damage. PURC has also been contacted by engineering researchers at the University of Wisconsin and North Carolina State University with an interest in the model, though no additional relationships have been established. In addition to universities, PURC was again contacted by researchers at the Argonne National Laboratory who expressed interest in modeling the effects of storm damage. The researchers developed a deterministic model, rather than a probabilistic one, but did use many of the factors that the Collaborative have attempted to quantify. They are currently working to incorporate stochastic elements into their model and have consulted PURC for guidance. Every researcher that contacts PURC cites the model as the only non-proprietary model of its kind.

The research discussed in previous years' reports on the relationship between wind speed and rainfall is still under review by the engineering press. Further results of this and related research can likely be used to further refine the model.

IV. Wind Data Collection

The Project Sponsors entered into a wind monitoring agreement with WeatherFlow, Inc., in 2007. Under the agreement, Florida Sponsors agreed to provide WeatherFlow with access to their properties and to allow WeatherFlow to install, maintain and operate portions of their wind monitoring network facilities on utility-owned properties under certain conditions in exchange for access to wind monitoring data generated by WeatherFlow's wind monitoring network in Florida. WeatherFlow's Florida wind monitoring network includes 50 permanent wind monitoring stations around the coast of Florida, including one or more stations located on utility-owned property. The wind monitoring agreement expired in early 2012; however, it was renewed in April 2017 and will renew automatically annually on the effective date for an additional one year period, unless terminated by the parties to the agreement.

V. Public Outreach

In last year's report we discussed the impact of increasingly severe storms on greater interest in storm preparedness. PURC researchers continue to discuss the collaborative effort in Florida with the engineering departments of the state regulators in Connecticut, New York, and New Jersey, Pennsylvania, and regulators in Jamaica, Grenada, Curacao, Samoa, and the Philippines. While all of the regulators and policymakers showed great interest in the genesis of the collaborative effort, and the results of that effort, they have not, at this point, shown further interest in participating in the research effort. PURC researchers also engaged with the popular media in preparation for, and in the wake of, Hurricane Irma.

VI. Conclusion

In response to the FPSC's Order 06-0351, IOUs, municipal electric utilities, and rural electric cooperatives joined together and retained PURC to coordinate research on electric infrastructure hardening. The steering committee has taken steps to extend the research collaboration MOU so that the industry will be in a position to focus its research efforts on undergrounding research, granular wind research and vegetation management when significant storm activity affects the state.

Report on Collaborative Research for Hurricane Hardening

Provided by

The Public Utility Research Center
University of Florida

To the

Utility Sponsor Steering Committee

Final Report dated February 2020

I. Introduction

The Florida Public Service Commission (FPSC) issued Order No. PSC-06-00351-PAA-EI on April 25, 2006 (Order 06-0351) directing each investor-owned electric utility (IOU) to establish a plan that increases collaborative research to further the development of storm resilient electric utility infrastructure and technologies that reduce storm restoration costs and outages to customers. This order directed IOUs to solicit participation from municipal electric utilities and rural electric cooperatives in addition to available educational and research organizations. As a means of accomplishing this task, the IOUs joined with the municipal electric utilities and rural electric cooperatives in the state (collectively referred to as the Research Collaboration Partners) to form a Steering Committee of representatives from each utility and entered into a Memorandum of Understanding (MOU) with the University of Florida's Public Utility Research Center (PURC). In 2018 the Research Collaboration MOU was renewed for an initial term of two years, effective January 1, 2019, and will be automatically extended for successive two-year terms.

PURC performs the administration function for research collaboration, including financial management, logistics, production and distribution of documents, and preparation of reports. PURC also coordinates and performs research as agreed upon with the Steering Committee by facilitating the exchange of information from the Research Collaboration Partners with individuals conducting research projects and facilitating the progress of each research project. The collaborative research has focused on undergrounding, vegetation management, hurricane-wind speeds at granular levels, and improved materials for distribution facilities.

This report provides an update on the activities of the Steering Committee since the previous report dated February 2019.

II. Undergrounding

The collaborative research on undergrounding has been focused on understanding the existing research on the economics and effects of hardening strategies, including undergrounding, so that informed decisions can be made about undergrounding policies and specific undergrounding projects.

The collaborative has refined the computer model developed by Quanta Technologies and there has been a collective effort to learn more about the function and functionality of the computer code. PURC and the Project Sponsors have worked to fill information gaps for model inputs and significant efforts have been invested in the area of forensics data collection.

In addition, PURC has worked with doctoral and master's candidates in the University of Florida Department of Civil and Coastal Engineering to assess some of the inter-relationships between wind speed and other environmental factors on utility equipment damage. PURC has also been contacted by engineering researchers at the University of Wisconsin and North Carolina State University with an interest in the model, though no additional relationships have been established. In addition to universities, PURC has been in contact with stakeholders in Puerto Rico in light of PURC Director Mark Jamison's appointment to the Southern States Energy Board Blue Ribbon Task Force on the future of Puerto Rico's energy system. The stakeholders, government and task force are concerned with strategies to make Puerto Rico's system more resilient and are interested in the role that the model could play. Finally, PURC has been contacted by California stakeholders interested in applying the principles of the model to the mitigation of the interactions between the electricity grid and the surrounding vegetation, potentially reducing the risk of wildfires. Despite the outside interest, there are no concrete plans to expand the scope of the model at this time. Every researcher that contacts PURC cites the model as the only non-proprietary model of its kind.

III. Wind Data Collection

The Project Sponsors entered into a wind monitoring agreement with WeatherFlow, Inc., in 2007. Under the agreement, Florida Sponsors agreed to provide WeatherFlow with access to their properties and to allow WeatherFlow to install, maintain and operate portions of their wind monitoring network facilities on utility-owned properties under certain conditions in exchange for access to wind monitoring data generated by WeatherFlow's wind monitoring network in Florida. WeatherFlow's Florida wind monitoring network includes 50 permanent wind monitoring stations around the coast of Florida, including one or more stations located on utility-owned property. The wind monitoring agreement expired in early 2012; however, it was renewed in April 2017 and will renew automatically annually on the effective date for an additional one year period, unless terminated by the parties to the agreement.

IV. Public Outreach

We have previously discussed the impact of increasingly severe storms and the increased

population and utility infrastructure along the coast on greater interest in storm preparedness. PURC researchers continue to discuss the collaborative effort in Florida with the engineering departments of the state regulators in New York, New Jersey, and Pennsylvania, and regulators in Jamaica, Grenada, Curacao, St. Lucia, the Bahamas, Samoa, and the Philippines. In 2019, stakeholders in Puerto Rico and California also showed interest in the collaborative's efforts. While all of the regulators and policymakers showed great interest in the genesis of the collaborative effort, and the results of that effort, they have not, at this point, shown further interest in participating in the research effort. In 2019, there continued to be considerable interest in Florida's hardening efforts from the popular media in California, in light of continued wildfire problems in the state and their aftermath.

VI. Conclusion

In response to the FPSC's Order 06-0351, IOUs, municipal electric utilities, and rural electric cooperatives joined together and retained PURC to coordinate research on electric infrastructure hardening. The steering committee has taken steps to extend the research collaboration MOU so that the industry will be in a position to focus its research efforts on undergrounding research, granular wind research and vegetation management when significant storm activity affects the state.