FILED 8/10/2021 DOCUMENT NO. 09037-2021 FPSC - COMMISSION CLERK

## Ausley McMullen

ATTORNEYS AND COUNSELORS AT LAW

123 SOUTH CALHOUN STREET
P.O. BOX 391 (ZIP 32302)
TALLAHASSEE, FLORIDA 32301
(850) 224-9115 FAX (850) 222-7560

August 10, 2021

### **VIA: ELECTRONIC FILING**

Mr. Adam J. Teitzman Commission Clerk Florida Public Service Commission 2540 Shumard Oak Boulevard Tallahassee, Florida 32399-0850

Re: Petition of Tampa Electric Company for Approval of Revised Underground

Residential Distribution Tariff

Dkt.: 20210064-EI

Dear Mr. Teitzman:

Attached for filing in the above docket is Tampa Electric Company's update to item 3(b) in response to Staff's Third Data Request (Nos. 1-3), propounded on July 26, 2021.

Thank you for your assistance in connection with this matter.

Sincerely,

James D. Beasley

JDB/bmp Attachment

cc: All Parties of Record (w/attachment)

Holly Forrest, FPSC (w/attachment)

### **CERTIFICATE OF SERVICE**

I HEREBY CERTIFY that a true and correct copy of the foregoing updated responses of Tampa Electric Company to Staff's Third Data Request (Nos. 1-3), have been furnished by electronic mail on this 10th day of August 2021 to the following:

Shaw Stiller
Office of General Counsel
Florida Public Service Commission
Room 390L – Gerald L. Gunter Building
2540 Shumard Oak Boulevard
Tallahassee, FL 32399-0850
sstiller@psc.state.fl.us

Richard Gentry
Charles Rehwinkel
Anastacia Pirrello
Stephanie Morse
Mary Wessling
Office of Public Counsel
c/o The Florida Legislature
111 West Madison Street, Room 812
Tallahassee, FL 32399-1400
gentry.richard@leg.state.fl.us
rehwinkel.charles@leg.state.fl.us
pirrello.anastacia@leg.state.fl.us
morse.stephanie@leg.state.fl.us
wessling.mary@leg.state.fl.us

ATTORNEY

FILED: AUGUST 2, 2021 REVISED: AUGUST 4, 2021

**SUPPLEMENTED: AUGUST 10, 2021** 

- 3. Please provide the Net Present Value of operational costs, including storm restoration costs, calculation, and resulting URD differential for the low- and high-density subdivisions.
  - a. Using calculations based on the historical methodology used by TECO for an average of three years for 2018, 2019, and 2020. Provide all supporting workpapers to show the calculations.
  - b. Using calculations based on an average of five years for the years 2016, 2017, 2018, 2019, and 2020. Please provide all workpapers to show the calculations.
- **A.** a. Please see attached calculations based on the historical methodology for an average of three years for 2018, 2019, and 2020.
  - b. Please see attached calculations based on the historical methodology for an average of five years for 2016, 2017, 2018, 2019, and 2020.

### OVERHEAD VS UNDERGROUND SUMMARY SHEET

Single Occupancy Low Density 210 Lot Subdivision Cost per Lot

ITEM	OVERHEAD	UNDERGROUND	DIFFERENTIAL
Labor	\$719.59	\$1,213.14	\$493.55
Material	\$708.94	\$1,227.97	\$519.03
TOTAL	\$1,428.53	\$2,441.11	\$1,012.58
NPV Operational Cost Including Storm Restoration and Lost Pole Attachment Revenue	\$1,868.48	\$1,129.27	-\$739.21
TOTAL Including NPV Operational Cost	\$3,297.01	\$3,570.38	\$273.37

### COST PER SERVICE LATERAL OVERHEAD MATERIAL AND LABOR

### Single Occupancy Low Density 210 Lot Subdivision Cost per Lot

ITEM	MATERIAL	LABOR <sup>1</sup>	TOTAL
Service <sup>2</sup>	\$134.88	\$79.94	\$214.82
Primary	\$16.04	\$47.12	\$63.16
Secondary	\$121.20	\$160.21	\$281.41
Initial Tree Trim	\$0.00	\$0.00	\$0.00
Poles	\$150.71	\$278.42	\$429.13
Transformers	\$208.91	\$88.24	\$297.15
Subtotal	\$631.74	\$653.93	\$1,285.67
Stores Handling <sup>3</sup>	\$77.20	\$0.00	\$77.20
Subtotal	\$708.94	\$653.93	\$1,362.87
Engineering		\$65.66	\$65.66
TOTAL	\$708.94	\$719.59	\$1,428.53

<sup>&</sup>lt;sup>1</sup> Includes Administration, General, Energy Delivery Supervison, & Transportation

<sup>&</sup>lt;sup>2</sup> Includes Meter

<sup>&</sup>lt;sup>3</sup> 12.22% of all Material

### COST PER SERVICE LATERAL UNDERGROUND MATERIAL AND LABOR

### Single Occupancy Low Density 210 Lot Subdivision Cost per Lot

ITEM	MATERIAL	LABOR <sup>1</sup>	TOTAL
Service <sup>2</sup>	\$331.03	\$248.42	\$579.45
Primary	\$304.40	\$109.34	\$413.74
Secondary	\$79.99	\$64.92	\$144.91
Transformers	\$378.83	\$86.18	\$465.01
Pri. and Sec. Trenching	\$0.00	\$319.74	\$319.74
Service Trenching	\$0.00	\$318.88	\$318.88
Subtotal	\$1,094.25	\$1,147.48	\$2,241.73
Stores Handling <sup>3</sup>	\$133.72	\$0.00	\$133.72
Subtotal	\$1,227.97	\$1,147.48	\$2,375.45
Engineering		\$65.66	\$65.66
TOTAL	\$1,227.97	\$1,213.14	\$2,441.11


<sup>&</sup>lt;sup>1</sup> Includes Administration, General, Energy Delivery Supervison, & Transportation

Includes Meter

 $<sup>^3</sup>$  12.22% of all Material

TYPICAL SINGLE OCCUPANCY LOW DENSITY 210 LOT SUBDIVISION LAYOUT





### OVERHEAD VS UNDERGROUND SUMMARY SHEET

Single Occupancy High Density 176 Lot Subdivision Individually Metered Cost per Lot

ITEM	OVERHEAD	UNDERGROUND	DIFFERENTIAL
Labor	\$570.46	\$1,015.10	\$444.64
Material	\$551.19	\$866.33	\$315.14
TOTAL	\$1,121.65	\$1,881.43	\$759.78
NPV Operational Cost Including Storm Restoration and Lost Pole Attachment Revenue	\$1,387.02	\$528.93	-\$858.09
TOTAL Including NPV Operational Cost	\$2,508.67	\$2,410.36	-\$98.31

### COST PER SERVICE LATERAL OVERHEAD MATERIAL AND LABOR

### Single Occupancy High Density 176 Lot Subdivision Individually Metered Cost per Lot

ITEM	MATERIAL	LABOR <sup>1</sup>	TOTAL
Service <sup>2</sup>	\$142.24	\$91.83	\$234.07
Primary	\$12.88	\$35.17	\$48.05
Secondary	\$64.40	\$106.36	\$170.76
Initial Tree Trim			\$0.00
Poles	\$113.97	\$205.55	\$319.52
Transformers	\$157.68	\$70.27	\$227.95
Subtotal	\$491.17	\$509.18	\$1,000.35
Stores Handling <sup>3</sup>	\$60.02	\$0.00	\$60.02
Subtotal	\$551.19	\$509.18	\$1,060.37
Engineering		\$61.28	\$61.28
TOTAL	\$551.19	\$570.46	\$1,121.65

 $<sup>\</sup>frac{1}{2}$  Includes Administration, General, Energy Delivery Supervison, & Transportation Includes Meter

<sup>&</sup>lt;sup>3</sup> 12.22% of all Material

### COST PER SERVICE LATERAL UNDERGROUND MATERIAL AND LABOR

### Single Occupancy High Density 176 Lot Subdivision Individually Metered Cost per Lot

ITEM	MATERIAL	LABOR <sup>1</sup>	TOTAL
Service <sup>2</sup>	\$288.33	\$260.66	\$548.99
Primary	\$138.27	\$61.14	\$199.41
Secondary	\$78.14	\$70.32	\$148.46
Transformers	\$267.25	\$68.77	\$336.02
Pri. and Sec. Trenching		\$175.02	\$175.02
Service Trenching		\$317.91	\$317.91
Subtotal	\$771.99	\$953.82	\$1,725.81
Stores Handling <sup>3</sup>	\$94.34	\$0.00	\$94.34
Subtotal	\$866.33	\$953.82	\$1,820.15
Engineering		\$61.28	\$61.28
TOTAL	\$866.33	\$1,015.10	\$1,881.43

Includes Administration, General, Energy Delivery Supervison, & Transportation
 Includes Meter

<sup>&</sup>lt;sup>3</sup> 12.22% of all Material

### OVERHEAD VS UNDERGROUND SUMMARY SHEET

Single Occupancy High Density 176 Lot Subdivision Multi-Unit Meter Centers Cost per Lot

ITEM	OVERHEAD	UNDERGROUND	DIFFERENTIAL
Labor	NA	NA	NA
Material	NA	NA	NA
TOTAL	NA	NA	NA

Tampa Electric's URD policy does not include "per lot" charges for multi-unit meter centers. These installations are covered in Tariff Section 5 Subsection 3.4.4.

### COST PER SERVICE LATERAL OVERHEAD MATERIAL AND LABOR

### Single Occupancy High Density 176 Lot Subdivision Multi-Unit Meter Centers Cost per Lot

ITEM	MATERIAL	LABOR <sup>1</sup>	TOTAL
Service <sup>2</sup>			\$0.00
Primary			\$0.00
Secondary			\$0.00
Initial Tree Trim			\$0.00
Poles			\$0.00
Transformers			\$0.00
Subtotal	\$0.00	\$0.00	\$0.00
Stores Handling <sup>3</sup>			\$0.00
Subtotal	\$0.00	\$0.00	\$0.00
Engineering			\$0.00
TOTAL	\$0.00	\$0.00	\$0.00

<sup>&</sup>lt;sup>1</sup> Includes Administration, General & Transportation

Tampa Electric's URD policy does not include "per lot" charges for multi-unit meter centers. These installations are covered in Tariff Section 5 Subsection 3.4.4.

<sup>&</sup>lt;sup>2</sup> Includes Meter

<sup>&</sup>lt;sup>3</sup> 12.22% of all Material

### COST PER SERVICE LATERAL UNDERGROUND MATERIAL AND LABOR

### Single Occupancy High Density 176 Lot Subdivision Multi-Unit Meter Centers Cost per Lot

ITEM	MATERIAL	LABOR <sup>1</sup>	TOTAL
Service <sup>2</sup>			\$0.00
Primary			\$0.00
Secondary			\$0.00
Transformers			\$0.00
Pri. and Sec. Trenching			\$0.00
Service Trenching			\$0.00
Subtotal	\$0.00	\$0.00	\$0.00
Stores Handling <sup>3</sup>			\$0.00
Subtotal	\$0.00	\$0.00	\$0.00
Engineering			\$0.00
TOTAL	\$0.00	\$0.00	\$0.00


Includes Administration, General & Transportation

Tampa Electric's URD policy does not include "per lot" charges for multi-unit meter centers. These installations are covered in Tariff Section 5 Subsection 3.4.4.

<sup>&</sup>lt;sup>2</sup> Includes Meter

<sup>3 12.22%</sup> of all Material

TYPICAL SINGLE OCCUPANCY HIGH DENSITY 176 LOT SUBDIVISION LAYOUT



TYPICAL SINGLE OCCUPANCY HIGH DENSITY 176 LOT SUBDIVISION LAYOUT



### AVERAGE UNDERGROUND FEEDER COSTS

Underground \$/Ft	Overhead \$/Ft	Difference
With Favorable Trenching \$/Ft		\$/Ft
Additional Trenching Cost* (Difficult Trenching) \$/Ft		\$/Ft
* Difficult trenching charges include undergr	round cost of cable-in-cor	nduit and rock trench adder.
Note: Above costs reflect adjustment ofunderground estimates.	for overhead estim	nates and \$ for
Feeder cost are not included in Tampa Ele addressed in Tampa Electric's Tariff Sect		

### ACTUAL OPERATIONAL DISTRIBUTION EXPENSES IN 2020

For Overhead and Underground

OVERHEAD UNDERGROUND

Operational Expense - Distribution

\$63,394,096

\$33,194,939

## JOINT TRENCHING WITH OTHER UTILITIES In RESIDENTIAL DISTRIBUTION

2011-2020 ADDITIONS

				Total	Total
				Amount	Amount
		Work		Due From	Due To
Date		Order		Other	Other
Closed	Location	Number	Footage	<u>Utility</u>	<b>Utility</b>

Tampa Electric did not engage in joint trenching during calendar year 2020.

# JOINT TRENCHING WITH OTHER UTILITIES In RESIDENTIAL DISTRIBUTION (continued)

<u>Year</u>	Footage Feet	Amount Due From Other Utility	Amount Due To Other Utility
Total For 2011	0	\$0.00	\$0.00
Total For 2012	0	\$0.00	\$0.00
Total For 2013	0	\$0.00	\$0.00
Total For 2014	0	\$0.00	\$0.00
Total For 2015	0	\$0.00	\$0.00
Total For 2016	0	\$0.00	\$0.00
Total For 2017	0	\$0.00	\$0.00
Total For 2018	0	\$0.00	\$0.00
Total For 2019	0	\$0.00	\$0.00
Total For 2020	0	\$0.00	\$0.00
10-Year Total	0	\$0.00	\$0.00

### LOW DENSITY MODEL 4/2021

Underground Costs (per lot)

## (210 lots) With overheads filed in rate case

	MATE	RIAL	LABO	R	TOTAL			
ITEM	COST	% CHANGE	COST	% CHANGE	COST	% CHANGE	EXPLANATION OF % CHANGE	
SERVICE	331.03	64.92%	248.42	46.79%	579.45	56.63%	Underground material up, contractor rates up	
PRIMARY	304.40	30.81%	109.34	51.40%	413.74	35.68%	Underground material up, Cable labor re-evaluation caused labor increase	
SECONDARY	79.99	84.78%	64.92	28.28%	144.91	54.32%	Underground material up, Cable labor re-evaluation caused labor increase	
TRANSFORMERS	378.83	9.14%	86.18	10.13%	465.01	9.32%	Underground material up, TEC & Contractor overhead down	
TRENCHING								
PRIMARY & SECONDARY			319.74	-12.14%	319.74	-12.14%	Contractor rates down	
SERVICES			318.88	-7.16%	318.88	-7.16%	Contractor rates down	
SUB-TOTAL	1,094.25	32.82%	1,147.48	6.48%	2,241.73	17.89%		
STORES HANDLING	133.72	16.11%			133.72	16.11%	Higher material costs produces higher handling costs	
SUB-TOTAL	1,227.97	30.77%	1,147.48	6.48%	2,375.45	17.79%		
ENGINEERING			65.66	0.00%	65.66	0.00%		
TOTAL	1,227.97	30.77%	1,213.14	6.10%	2,441.11	17.23%		
					1,129.27	1	nt Value of the Life Cycle Operational Cost Including Storm on and Lost Pole Attachment Revenue	
Total with NPV Factor					3,570.38	Total Including NPV of Operational Cost		

### Overhead Costs (per lot)


	MAT	ERIAL	LABO	R	TOTAL		
ITEM	COST	% CHANGE	COST	% CHANGE	COST	% CHANGE	EXPLANATION OF % CHANGE
SERVICE	134.88	70.67%	79.94	6.94%	214.82	39.69%	Material up, Labor up
PRIMARY	16.04	15.73%	47.12	12.78%	63.16	13.52%	Material up, Labor up
SECONDARY	121.20	11.24%	160.21	6.02%	281.41	8.21%	Material up, Labor up
INITIAL TREE TRIM			0.00		0.00		
POLES	150.71	8.41%	278.42	8.73%	429.13	8.62%	Material up, Labor up
TRANSFORMERS	208.91	3.31%	88.24	9.53%	297.15	5.08%	Material up, Labor up
SUB-TOTAL	631.74	16.33%	653.93	8.22%	1,285.67	12.06%	
STORES HANDLING	77.20	1.69%			77.20	1.69%	Higher material costs produces higher handling costs
SUB-TOTAL	708.94	14.53%	653.93	8.22%	1,362.87	11.41%	
ENGINEERING			65.66	0.00%	65.66	0.00%	
TOTAL	708.94	14.53%	719.59	7.41%	1,428.53	10.83%	
					1,868.48		nt Value of the Life Cycle Operational Cost Including Storm on and Lost Pole Attachment Revenue
Total with NPV Factor					3,297.01	Total Including NPV of Operational Cost	

### Differential Costs (per lot)

	MATERIAL		LABO	R	TOTAL	
ITEM	COST	% CHANGE	COST	% CHANGE	COST	% CHANGE
Differential (per lot)	519.03	62.19%	493.55	4.25%	1,012.58	27.62%
NPV amount					-739.21	
Differential (per lot)	0.00		0.00		273.37	-155.68%

1 Includes NPV of Operational Cost

TAMPA ELECTRIC COMPANY DOCKET NO. 20210064-EI STAFF'S THIRD DATA REQUEST REQUEST NO. 3b



### UG Construction Cost Data Summary Low Density (210-Lot) UG Subdivision Costs

	Α	В	C (C + M) Material and	D	E (F + L) Total Labor	F (G + H + I )	G Base	H (G x J x TLF) TEC Labor	(G x K x CLF) Contract Labor	J TEC	K Contractor	L	M (D x MHR) Material	N (C+E)
Line #	Work Type/WR #	Description	Handling	Material	Plus Vehicles	Total Labor	Labor	Overheads	Overheads	Work %	Work %	Vehicle	Handling	Total
1	Transformers													
2	924920	Install & Ground Transformers	89,275.93	\$79,554.38	12,917.76	11,552.89	6,726.81	4,286.32	539.76	60%	40%	\$1,364.87	9,721.55	102,193.69
3	Contractor	Prepare Pad Site		-	5,179.75	5,179.75	4,314.30	-	865.45	0%	100%			5,179.75
4			89,275.93	79,554.38	18,097.51	16,732.64	11,041.11	4,286.32	1,405.21			1,364.87	9,721.55	107,373.44
5 6	Primary													
7	924957	Primary Line - OH-UG Takeoffs	1,615.06	\$1,439,19	1.910.80	1.708.90	995.03	634.03	79.84	60%	40%	\$201.89	175.87	3.525.85
8	925017	Primary Conduit (Material Only)	25,221.49	\$22,475.04	1,510.00	1,700.30	-	-	- 13.04	0070	4070	Ψ201.03	2,746.45	25,221.49
9	925022	Primary Cable	44,899.79	\$40,010.51	21,050.29	18,826.15	10,961.75	6,984.83	879.57	60%	40%	\$2,224.14	4,889.28	65,950.08
10			71,736.34	63,924.74	22,961.08	20,535.05	11,956.78	7,618.86	959.41			2,426.03	7,811.60	94,697.43
11	Secondary													
12	925024	Secondary Cable	11,440.67	\$10,194.86	13,633.22	12,192.76	7,099.38	4,523.72	569.65	60%	40%	\$1,440.46	1,245.81	25,073.90
13	925026	Secondary Conduit (Material Only)	7,409.08	\$6,602.28				-					806.80	7,409.08
14			18,849.75	16,797.14	13,633.22	12,192.76	7,099.38	4,523.72	569.65			1,440.46	2,052.61	32,482.97
15 16	Service 925028	Service Cable	26,226.15	\$23.370.30	48.611.12	48.611.12	40.489.02		8,122.10	0%	100%		2,855.85	74,837.27
17	925028	Set Meters	21.181.30	\$18.874.80	3,556.32	3,180.56	1.851.92	1,180.04	148.60	60%	40%	\$375.75	2,055.05	24,737.62
18	925030	Service Conduit Material	30,604.71	\$27,272.06	5,550.52	5,100.50	1,001.02	1,100.04	140.00	0070	4070	Ψ070.70	3,332.65	30,604.71
19			78.012.16	69,517.16	52.167.43	51.791.68	42.340.94	1.180.04	8,270.70			375.75	8,495.00	130,179.59
20														
21	Trenching													
22	Contractor	Primary Trenching	-	-	45,216.01	45,216.01	37,661.18	-	7,554.83	0%	100%	-	-	45,216.01
23	Contractor	Secondary Trenching	-	-	5,475.70	5,475.70	4,560.80	-	914.90	0%	100%	-	-	5,475.70
24	TEC Inspection	n for Primary			16,452.69	15,594.97	42,221,98		8.469.73	100%	0%	857.72 857.72		16,452.69 67,144.40
25 26			-	-	67,144.40	66,286.68	42,221.98	-	8,469.73			857.72	-	67,144.40
27	Contractor	Svc Trenching Pri. Prop	-	-	39,974.94	39,974.94	33,295.80		6,679.14	0%	100%	-	-	39,974.94
28	Contractor	Svc Trenching Rts-of-Wy	-	-	17,238.59	17,238.59	14,358.31	-	2,880.28	0%	100%	-	-	17,238.59
29	TEC Inspection	for Service			9,750.62	9,242.42		<u> </u>		100%	0%	508.20		9,750.62
30 31			-	-	66,964.14	66,455.94	47,654.11	-	9,559.41			508.20	-	66,964.14
32 33	Engineering	Design/Inspection/Coordination	-	-	13,788.39	13,788.39	-	-	-			-	-	13,788.39
34 35	Totals (Sum of lines Cost per Lot	4, 10, 14, 19, 25, 30, and 32) (line 34 /210 lots)	\$ 257,874.18 \$ 1,227.97	\$ 229,793.42	\$ 254,756.18 \$ 1,213.12	\$ 247,783.15	162,314.30	17,608.95	\$ 29,234.11			\$ 6,973.04	\$ 28,080.76	512,630.36 5 2,441.10

Adjustment Factors			
TEC Operations Labor Overhead Factor	TLF =	1.062	
Contractor Labor Overhead Factor	CLF =	0.2006	
Current year material handling charge rate	MHR =	0.1222	

		UG Contrac	tor Labor E	stimate -	210 lot low	density			
		Prepare pad s	ite (Primary	Contractor	Labor Costs)				
		<u>Total</u>	Cost	Pad sites					
Pad site preparation	Total	\$4,314.30	\$143.81	30					
		Primary Trend	hing & Cond	luit (Primar	y Contractor L	abor Costs)			
		Total	Cost	Feet					
		\$29,126.24	\$2.08 \$0.51	14003 15806			ching Cost Only		
		\$8,061.06 \$0.00	\$0.00	14003			stallation (both trenching and in existing trench) allation (used exact length for labor cost not 5% extra)		
		\$473.88	\$157.96	3			: (30" x 48" x 18"), UG GR&S 6-21		
Primary Trenching	Sub-total	\$37,661.18	,,,,,,,,,,				(40 11.10 11.10 ), 50 0.100 0.00		
		Secondary Tre			nary Contracto	r Labor Costs	<u>s)</u>		
		Total	<u>Cost</u> \$2.08	<u>Feet</u> 1597		Mashina Tana	abina Cast Oak		
		\$3,321.76 \$0.00	\$2.08 \$0.51	0		2" Conduit Ins	ching Cost Only		
		\$176.00	\$0.55	320		3" Conduit Ins			
		\$1,063.04	\$0.64	1661		4" Conduit Ins			
		\$0.00	\$0.00	1597		Pull-tape Insta	allation (used exact length not 5% extra)		
Secondary Trenching	Sub-total	\$4,560.80							
Primary Contractor Labor	Total	\$42,221.98							
		Service Trenc			Contractor L	abor Costs)			
		<u>Total</u> \$7.473.44	<u>Cost</u> \$2.08	<u>Feet</u> 3593		Trenching Co.	st -Trenching feet required for 2" service conduit		
		\$1,196.00	\$2.08	575			st-Trenching feet required for 3" service conduit		
		\$4,415.07	\$0.51	8657		2" Conduit Ins			
		\$1,273.80	\$0.55	2316		3" Conduit Ins	stallation		
Svc Trenching Rts-of-Wy	Sub-total	\$0.00 <b>\$14.358.31</b>	\$0.00	10973		Pull-tape Insta	allation (used exact length not 5% extra)		
,			hing & Cond	uit on Priva	ato Proporty (S	onvice Centra	actor Labor Costs)		
		Total	Cost	Feet	ite Froperty (S	ervice contra	ictor Labor Costs)		
Svc Trenching Pri. Prop	Sub-total	\$33,295.80	\$5.26	6330		Trenching & c	conduit labor cost - Trenching feet = 30 ft x 210 lots		
		Service Cable			bor Costs)				
	0.1.4.4.1	<u>Total</u>	Cost	Feet			4/0.0-11-1		
Service Cable Labor	Sub-total	\$40,489.02	\$2.34	17303		installing 2/0 o	or 4/0 Cable in existing conduit from source to meter		
Service Conractor Labor	Total	\$88,143.13							
Total Contractor L	abor Cost	\$130,365.11							
		Inspection (TE	CO Labor C	ost)	TEC Vohicle	TEC Vehicle			
		Total	Rate	Feet/Qty	Rate	Total	Inspection costs for Primary Contractor (TECO Labor Cost)		
		\$10,953.46	\$88.00	14003	\$4.84	\$602.44	Primary Inspection chg = (mach. trnch ft / 900 ft per day)*(8 hr/day)*Contractor rate		
		\$1,249.21	\$88.00	1597	\$4.84				
		\$3,260.30	\$88.00	4168	\$4.84				
Inspection costs for Primary Contractor	Sub-total	\$132.00 <b>\$15,594.97</b>	\$44.00	3	\$2.42	\$7.26 <b>\$857.72</b>	1ø splice box (30" x 48" x 18"), UG GR&S 6-21		
		TEC Labor	TEC Labor		TEC Vehicle	TEC Vehicle			
		Total	Rate	Feet/Qty	Rate	Total	Inspection costs for Service Contractor (TECO Labor Cost)		
Inspection costs for		\$9,240.00	\$44.00	210	\$2.42	\$508.20	Service Private Property Inspection = .5hr x # of lots x rate		
Service Contractor   Sub-total   \$9,242.42   \$508.20									
Total TEC Inspec	ction Cost	\$24,837.39							
. 5ta. 120opet		+41,001.00							

Please modify the low density construction drawing legend as shown below.


### UG Material List - 1501-2500 sq ft same trench 210 lot low density


- 1250 Total Connected KVA
- 1272.2 Total initial peak demand KVA
  - 6 25 kVA Transformers
  - 8 37.5 kVA Transformers
  - 16 50 kVA Transformers
  - 0 75 kVA Transformers
- 14003 Trench Feet of 1/0 AL Primary Cable
- 1803 Existing trench feet of 1/0 AL Primary Cable
  - 0 Trench Feet of 2/0 AL Secondary Cable
  - 0 Existing trench feet of 2/0 AL Secondary Cable
- 1597 Trench Feet of 4/0 AL Secondary Cable
- 384 Existing trench feet of 4/0 AL Secondary Cable
  - 0 Trench Feet of 500 MCM AL Secondary Cable
  - 0 Existing trench feet of 500 MCM AL Secondary Cable
- 9233 Trench Feet of 2/0 AL Service Cable
- **5064** Existing trench feet of 2/0 AL Service Cable
- 1265 Trench Feet of 4/0 AL Service Cable
- 1741 Existing trench feet of 4/0 AL Service Cable
  - 0 Load Break Cabinet

### Notes:

- 1. 1501-2500 SF Homes
- 2. 3.5 Ton AC Units
- 3. 40' Service run from property corner to meter location
- 4. Voltage drop less than or equal to 12.0 volts
- 5. Voltage flicker less than or equal to 12.0 volts

### UG CU Totals (Material and Labor) - 2000 sq ft - 210 lot low density Links allow this worksheet to summarize the material and CU entries from the ParkhurstPole worksheet through the BentTreePole worksheet. The totals are broken down into material construction units (CUs) for WorkPro work requests and labor inputs for the Contractor Labor worksheet. Station All Stations - This information is used to create Work Requests to obtain costs. === Blue shading indicates fields to be undated. In WorkPro search for each Work Request Number shown in the blue areas. Then copy each work request which will create a new work request number to be entered. Transfer the values from Qty and CU columns highlighted in yellow to the new WorkPro Work Requests to obtain new costs Those costs are then entered into the LDdifferentialMonth-Year.xls workbook to calculate the Low Density Differential cost. **Work Request** Number 924920 Transformers - Cost for: Material only, TEC labor & overhead, vehicle CU Definition **Total Connected KVA** Qty 0 pku51a3n 25 kva, 6 tap 250mcm Ω 6 pku51c3n 25 kva, 8 tap 250mcm 150 150 0 pku51a4n 37.5 kva, 6 tap 250mcm 150 1 pku51b4n 37.5 kva, 6 tap 500mcm 37.5 187.5 0 pku51c4n 37.5 kva, 8 tap 250mcm 0 187.5 7 pku51d4n 37.5 kva. 8 tap 500mcm 262.5 450 0 pku51a5n 50 kva, 6 tap 250mcm 0 450 0 pku51b5n 50 kva,6 tap 500mcm 450 0 pku51c5n 50 kva,8 tap 250mcm 0 450 16 pku51d5n 50 kva.8 tap 500mcm 800 1250 0 pku51a6n 75 kva. 6 tap 250mcm 1250 0 0 pku51b6n 75 kva, 6 tap 500mcm 0 pku51c6n 75 kva,8 tap 250mcm 1250 0 pku51d6n 75 kva, 8 tap 500mcm 1250 1 bushcover arrester open position on loop tx used as radial 1250 1 bushdummy arrester normal open tx in loop 2 bushinsert\_arrester at adjacent tx to normal open in a loop 33 grdmeg1/2 meggar ground, drive rods, 1 location, 1/2" rods **Work Request** Number 924957 OH Primary - Cost for: Material only, TEC labor & overhead, vehicle Qty CU Definition 4 PKE601WF1B TEC material & labor to frame terminal pole CO & LA 4 FLOH103 Fuse meggar ground, drive rods, 1 location, 1/2" rods Primary Trenching - Labor Only Done by contractors Used to determine contractor labor cost on the Contractor Labor worksheet Definition Qtv CII 14003 Trenching feet required for 2" primary conduit 1803 Existing trench feet used for 2" primary conduit 14003 Install Pulling Tape (blow in tape for pull - trench feet used to determine contractor cost) Work Request Number 925017 Primary Conduit - Cost for Material only Material used by contractors to install the conduit system Qty CU Definition 40 COND2G Conduit, galvanized 2", 10' with coupling, for up terminal pole TEC # 2004389 16156 COND2 SCHA 2" PVC Schedule A conduit TEC # 2004488 16506 MULE TAPE Pulling tape - actual length - does not need any 5% adder TEC # 2007414 88 ELL2G90 2" elbow 90 galv 9.5" radius TEC # 2004395 1 ELL2G45 2" elbow 45 galv 9.5" radius TEC # 2004394 178 COUP2P Coupling, 2" PVC (2 per elbow) TEC # 2004507 33 GLUECONDF 2"& 3" pvc 1 qt for 500' fast dry 1ø splice box (30" x 48" x 18"), UG GR&S 6-21 3 HH1PHPRI







## Estimate Summary Design Number 1

Distribution Services Transformers 2000 Sq Ft **Contact Name:** Tampa Electric

**Printed Date:** 3/10/2021

District: CSA

WR No. 924920

Date Sched: 4/1/21 Date Required: 4/1/21

Additional Information: URD filing for 1501-2500 sq ft low density WR Description: LDUG 2000 sq ft TRANSFORMERS

INSTALLATION: Capital MATERIAL: \$79,554 OVERHEAD: \$11,002 \$90,556	\$0.00	<b>Total</b> \$79,554.38 \$11,002.38 \$90,556.76
OVERHEAD: \$11,002.	\$0.00 76 \$0.00	\$11,002.38
V,00=	76 \$0.00	
\$90,556		\$90,556.76
	0	
LABOR HOURS: 152.8	O	152.8
LABOR COST: \$6,726.8	1 \$0.00	\$6,726.81
OVERHEAD: \$8,913.0	2 \$0.00	\$8,913.02
\$15,639	83 \$0.00	\$15,639.83
VEHICLE: \$0.00	\$0.00	\$0.00
CONTRACTOR: \$0.00	\$0.00	\$0.00
ADDITIONAL ITEMS: \$0.00	\$0.00	\$0.00
SUBTOTAL: \$106,19	\$0.00	\$106,196.59
REMOVAL:		
MATERIAL: \$0.00	\$0.00	\$0.00
OVERHEAD: \$0.00	\$0.00	\$0.00
\$0.00	\$0.00	\$0.00
LABOR HOURS: 0	0	0
LABOR COST: \$0.00	\$0.00	\$0.00
OVERHEAD: \$0.00	\$0.00	\$0.00
\$0.00	\$0.00	\$0.00
VEHICLE: \$0.00	\$0.00	\$0.00
CONTRACTOR: \$0.00	\$0.00	\$0.00
ADDITIONAL ITEMS: \$0.00	\$0.00	\$0.00
SUBTOTAL: \$0.00	\$0.00	\$0.00
TRANSFER:		
LABOR HOURS: 0	0	0
LABOR COST: \$0.00	\$0.00	\$0.00
OVERHEAD: \$0.00	\$0.00	\$0.00
\$0.00	\$0.00	\$0.00
VEHICLE: \$0.00	\$0.00	\$0.00
CONTRACTOR: \$0.00	\$0.00	\$0.00
ADDITIONAL ITEMS: \$0.00	\$0.00	\$0.00
SUBTOTAL: \$0.00	\$0.00	\$0.00
TOTALS: \$106,196.5	9 \$0.00	\$106,196.59

THIS FORM IS NOT TO BE USED FOR CONTRIBUTION IN AID CONSTRUCTION (CIAC).



# Work Request Material Summary \*\*\*Includes Truck Stock\*\*\*

Design Number 1

**Printed Date: 3/10/2021** Dist: CSA

WR No. 924920

Page 1 of 1

2 2003815 ARRE 4 2003817 ARRE 30 2077906 CLAM 60 2078000 CLAM 4 2077931 CONN 90 2077939 COUP 30 2001315 PAD, 0		- rage roll					
rial Numbe	er Description	Unit Price	Total Cost	Asset?			
2003816	ARRESTER, UD, 10KV PARKING L/A, 8.40 KVR	\$144.06	\$288.12	Υ			
2003815	ARRESTER, URD, 10KV ELBOW L/A, 8.40 KVRM	\$63.66	\$127.32	Υ			
2003817	ARRESTER, URD, 10KV, BUSHING L/A, 8.40KV	\$192.51	\$770.04	Υ			
2077906	CLAMP, GROUND ROD, F/U/W 1/2"ROD	\$1.80	\$54.00	N			
2078000	CLAMP,GND,TRANSFORMER,#10 SOL-#1 STR CU	\$2.31	\$138.60	N			
2077931	CONNECTOR, VICE CU #2 STR	\$2.38	\$9.52	N			
2077939	COUPLER, GROUND ROD, F/U/W 1/2"ROD	\$4.78	\$430.20	N			
2001315	PAD, CONCRETE 40" X 45" X 4" 25- 50KVA T	\$103.25	\$3,097.50	N			
2001316	PAD, CONCRETE 44" X 52" X 4" 75-250KVA T	\$115.55	\$0.00	N			
2007395	PADLOCK, RED BRASS BODY 1/4" BRASS SHACK	\$22.97	\$689.10	N			
2007489	REPELLENT, FIRE ANT GRANULE 4 OZ BIFENTH	\$2.77	\$83.10	N			
2077980	ROD,GROUND,CU BONDED,1/2"X10',THREADLESS	\$13.72	\$1,646.40	N			
2004031	STUD, GALVANIZED, 11 THREAD PER INCH ALL	\$2.47	\$148.20	N			
2004904	TERMINAL, SLIP FIT AL 5/8 IN 8-POS #2-50	\$17.94	\$1,614.60	N			
2004948	TERMINAL, SLIP FIT ALUMINUM STUD TYPE, 6	\$7.54	\$0.00	N			
2004954	TERMINAL, SLIP FIT ALUMINUM STUD TYPE, 6	\$16.58	\$0.00	N			
2004950	TERMINAL, SLIP FIT ALUMINUM STUD TYPE, 8	\$8.28	\$0.00	N			
2001518	TX,PM,LP,1P,25 kVA,240/120,FR3,SS	\$2,001.00	\$12,006.00	Υ			
2001519	TX,PM,LP,1P,37.5 kVA,240/120,FR3,SS	\$2,108.00	\$16,864.00	Υ			
2001520	TX,PM,LP,1P,50 kVA,240/120,FR3,SS	\$2,592.00	\$41,472.00	Υ			
2001521	TX,PM,LP,1P,75 kVA,240/120,FR3,SS	\$3,044.00	\$0.00	Υ			
2004184	WIRE, COPPER, BARE, #4 SOFT DRAWN 7 STR	\$0.63	\$113.40	N			
2078011	WIRE, COPPER, TIE, #6 SOLID SOFT DRAWN	\$0.38	\$2.28	N			
		Total	\$79,554.38				
	2003816 2003815 2003817 2077906 20778000 2077931 2077939 2001315 2001316 2007395 2007489 2077980 2004031 2004904 2004954 2004954 2004950 2001518 2001519 2001520 2001521 2004184	2003816 ARRESTER, UD, 10KV PARKING L/A, 8.40 KVR 2003815 ARRESTER, URD, 10KV ELBOW L/A, 8.40 KVRM 2003817 ARRESTER, URD, 10KV, BUSHING L/A, 8.40KV 2077906 CLAMP, GROUND ROD, F/U/W 1/2"ROD 2078000 CLAMP,GND,TRANSFORMER,#10 SOL-#1 STR CU 2077931 CONNECTOR, VICE CU #2 STR 2077939 COUPLER, GROUND ROD, F/U/W 1/2"ROD 2001315 PAD, CONCRETE 40" X 45" X 4" 25- 50KVA T 2001316 PAD, CONCRETE 44" X 52" X 4" 75-250KVA T 2007395 PADLOCK, RED BRASS BODY 1/4" BRASS SHACK 2007489 REPELLENT, FIRE ANT GRANULE 4 OZ BIFENTH 2077980 ROD,GROUND,CU BONDED,1/2"X10',THREADLESS 2004031 STUD, GALVANIZED, 11 THREAD PER INCH ALL 2004904 TERMINAL, SLIP FIT AL 5/8 IN 8-POS #2-50 2004948 TERMINAL, SLIP FIT ALUMINUM STUD TYPE, 6 2004954 TERMINAL, SLIP FIT ALUMINUM STUD TYPE, 6 2004955 TERMINAL, SLIP FIT ALUMINUM STUD TYPE, 8 2001518 TX,PM,LP,1P,25 kVA,240/120,FR3,SS 2001520 TX,PM,LP,1P,50 kVA,240/120,FR3,SS 2001521 TX,PM,LP,1P,75 kVA,240/120,FR3,SS 2001521 TX,PM,LP,1P,75 kVA,240/120,FR3,SS 2001521 TX,PM,LP,1P,75 kVA,240/120,FR3,SS 2001184 WIRE, COPPER, BARE, #4 SOFT DRAWN 7 STR	Orial Number         Description         Unit Price           2003816         ARRESTER, UD, 10KV PARKING L/A, 8.40 KVR         \$144.06           2003815         ARRESTER, URD, 10KV ELBOW L/A, 8.40 KVRM         \$63.66           2003817         ARRESTER, URD, 10KV, BUSHING L/A, 8.40KV         \$192.51           2077906         CLAMP, GROUND ROD, F/U/W 1/2"ROD         \$1.80           2078000         CLAMP, GROUND ROD, F/U/W 1/2"ROD         \$2.31           2077931         CONNECTOR, VICE CU #2 STR         \$2.38           2077939         COUPLER, GROUND ROD, F/U/W 1/2"ROD         \$4.78           2001315         PAD, CONCRETE 40" X 45" X 4" 25- 50KVA T         \$103.25           2001316         PAD, CONCRETE 44" X 52" X 4" 75-250KVA T         \$115.55           2007395         PADLOCK, RED BRASS BODY 1/4" BRASS SHACK         \$22.97           2007489         REPELLENT, FIRE ANT GRANULE 4 OZ BIFENTH         \$2.77           2077980         ROD,GROUND,CU BONDED,1/2"X10",THREADLESS         \$13.72           2004931         STUD, GALVANIZED, 11 THREAD PER INCH ALL         \$2.47           2004948         TERMINAL, SLIP FIT AL 5/8 IN 8-POS #2-50         \$17.94           2004954         TERMINAL, SLIP FIT ALUMINUM STUD TYPE, 6         \$16.58           2004950         TERMINAL, SLIP FIT ALUMINUM STUD TYPE, 8<	Inial Number         Description         Unit Price         Total Cost           2003816         ARRESTER, UD, 10KV PARKING L/A, 8.40 KVR         \$144.06         \$288.12           2003815         ARRESTER, URD, 10KV BLBOW L/A, 8.40 KVRM         \$63.66         \$127.32           2003817         ARRESTER, URD, 10KV, BUSHING L/A, 8.40KV         \$192.51         \$770.04           2077906         CLAMP, GROUND ROD, F/U/W 1/2"ROD         \$1.80         \$54.00           2078000         CLAMP, GROUND ROD, F/U/W 1/2"ROD         \$1.80         \$54.00           2077931         CONNECTOR, VICE CU #2 STR         \$2.38         \$9.52           2077939         COUPLER, GROUND ROD, F/U/W 1/2"ROD         \$4.78         \$430.20           2001315         PAD, CONCRETE 40" X 45" X 4" 25- 50KVAT         \$103.25         \$3,097.50           2001316         PAD, CONCRETE 44" X 52" X 4" 25- 50KVAT         \$115.55         \$0.00           2007489         PADLOCK, RED BRASS BODY 1/4" BRASS SHACK         \$22.97         \$689.10           2007489         REPELLENT, FIRE ANT GRANULE 4 OZ BIFENTH         \$2.77         \$83.10           2077980         ROD, GROUND, CU BONDED, 1/2"X10", THREADLESS         \$13.72         \$1,646.40           2004904         TERMINAL, SLIP FIT ALL 5/8 IN 8-POS #2-50         \$17.94         \$1,614.6			



## Estimate Summary Design Number 1

Distribution Services Term Poles - low density 2000 sq ft

**Printed Date:** 3/10/2021

District: CSA

WR No. 924957

Date Sched: 4/1/21 Date Required: 4/1/21

Additional Information: Low density URD filing - 2000 sq ft homes

WR Description: LDUG 2000 sq ft TAKEOFFS

INSTALLATION:	Capital	Oper./Maint.	Total	
MATERIAL:	\$1,439.19	\$0.00	\$1,439.19	
OVERHEAD:	\$199.05	\$0.00	\$199.05	
	\$1,638.24	\$0.00	\$1,638.24	
LABOR HOURS:	22.62	0	22.62	
LABOR COST:	\$995.03	\$0.00	\$995.03	
OVERHEAD:	\$1,318.42	\$0.00	\$1,318.42	
	\$2,313.45	\$0.00	\$2,313.45	
VEHICLE:	\$0.00	\$0.00	\$0.00	
CONTRACTOR:	\$0.00	\$0.00	\$0.00	
ADDITIONAL ITEMS:	\$0.00	\$0.00	\$0.00	
SUBTOTAL:	\$3,951.69	\$0.00	\$3,951.69	
REMOVAL:				
MATERIAL:	\$0.00	\$0.00	\$0.00	
OVERHEAD:	\$0.00	\$0.00	\$0.00	
	\$0.00	\$0.00	\$0.00	
LABOR HOURS:	0	0	0	
LABOR COST:	\$0.00	\$0.00	\$0.00	
OVERHEAD:	\$0.00	\$0.00	\$0.00	
	\$0.00	\$0.00	\$0.00	
VEHICLE:	\$0.00	\$0.00	\$0.00	
CONTRACTOR:	\$0.00	\$0.00	\$0.00	
ADDITIONAL ITEMS:	\$0.00	\$0.00	\$0.00	
SUBTOTAL:	\$0.00	\$0.00	\$0.00	
TRANSFER:				
LABOR HOURS:	0	0	0	
LABOR COST:	\$0.00	\$0.00	\$0.00	
OVERHEAD:	\$0.00	\$0.00	\$0.00	
	\$0.00	\$0.00	\$0.00	
VEHICLE:	\$0.00	\$0.00	\$0.00	
CONTRACTOR:	\$0.00	\$0.00	\$0.00	
ADDITIONAL ITEMS:	\$0.00	\$0.00	\$0.00	
SUBTOTAL:	\$0.00	\$0.00	\$0.00	
TOTALS:	\$3,951.69	\$0.00	\$3,951.69	

THIS FORM IS NOT TO BE USED FOR CONTRIBUTION IN AID CONSTRUCTION (CIAC).



# Work Request Material Summary \*\*\*Includes Truck Stock\*\*\*

Design Number 1

**Printed Date: 3/10/2021** Dist: CSA

WR No. 924957

Page 1 of 1

	4 2003651 ARRE 4 2077754 BOLT, 4 2131366 BRAC 4 2077906 CLAM 4 2077911 CLAM 160 2078012 COND		. ugo	. 0	
Mate	erial Numbe	er Description	Unit Price	Total Cost	Asset?
NSTALL					
4	2003651	ARRESTER, LIGHTNING DISTRIBUTION CLASS 8	\$41.28	\$165.12	Υ
4	2077754	BOLT, MACHINE 5/8" X 10", GALV. FULL	\$1.04	\$4.16	N
4	2131366	BRACKET, FG, 1 PH, 1 POS, 18"	\$30.03	\$120.12	N
4	2077906	CLAMP, GROUND ROD, F/U/W 1/2"ROD	\$1.80	\$7.20	N
4	2077911	CLAMP, HOT LINE CU TO CU #6 SOL- 2 STR T	\$5.73	\$22.92	N
160	2078012	CONDUCTOR, COPPERCLAD, 3 STR. #9, DSA 30	\$0.84	\$134.40	N
12	2004187	CONDUCTOR,BARE,#2 CU,7-STR,SOFT-DRAWN	\$0.98	\$11.76	N
4	2077837	CONNECTOR, COMPRESSION H-BLOCK ACSR 2/0	\$0.66	\$2.64	N
8	2077930	CONNECTOR, VICE CU #4 STR	\$1.91	\$15.28	N
15	2077939	COUPLER, GROUND ROD, F/U/W 1/2"ROD	\$4.78	\$71.70	N
4	2003846	CUTOUT, 15KV, 100A FUSE HLDR, 300A UNVRS	\$70.74	\$282.96	Υ
4	2077793	FUSE LINK, 80A UNVRSL 100A CUTOUT 23" OA	\$6.67	\$26.68	N
4	2077822	KIT, ATTACHMENT, FOR ATTACHING "FLYING"	\$63.00	\$252.00	N
8	2077965	MOULDING, GROUND WIRE, PVC 1/2 IN X 8 FT	\$1.74	\$13.92	N
16	2077980	ROD,GROUND,CU BONDED,1/2"X10',THREADLESS	\$13.72	\$219.52	N
4	2077789	SCREW, LAG PILOT POINT 3/8 X 3	\$0.27	\$1.08	N
40	2077997	STAPLE, SECURES 1/2" PVC MOULDING TO WOO	\$0.27	\$10.80	N
4	2077828	STIRRUP, AL BODY & CU BAIL 1/0-397	\$17.19	\$68.76	N
4	2078006	WASHER, FLAT, GALVANIZED, 2" X 2" X 1/8"	\$0.24	\$0.96	N
4	2004184	WIRE, COPPER, BARE, #4 SOFT DRAWN 7 STR	\$0.63	\$2.65	N
12	2078011	WIRE, COPPER, TIE, #6 SOLID SOFT DRAWN	\$0.38	\$4.56	Ν
			Total	\$1,439.19	



## Estimate Summary Design Number 1

Distribution Services Primary conduit 2000 Sq Ft

**Printed Date:** 3/10/2021

District: CSA

WR No. 925017

Date Sched: 4/1/21 Date Required: 4/1/21

Additional Information: Low density 2000 sq ft URD filing WR Description: LDUG 2000 sq ft PRIMARY CONDUIT

INSTALLATION:	Capital	Oper./Maint.	Total
MATERIAL:	\$22,475.04	\$0.00	\$22,475.04
OVERHEAD:	\$3,108.30	\$0.00	\$3,108.30
	\$25,583.34	\$0.00	\$25,583.34
LABOR HOURS:	223.84	0	223.84
LABOR COST:	\$9,853.36	\$0.00	\$9,853.36
OVERHEAD:	\$13,055.70	\$0.00	\$13,055.70
	\$22,909.06	\$0.00	\$22,909.06
VEHICLE:	\$0.00	\$0.00	\$0.00
CONTRACTOR:	\$0.00	\$0.00	\$0.00
ADDITIONAL ITEMS:	\$0.00	\$0.00	\$0.00
SUBTOTAL:	\$48,492.40	\$0.00	\$48,492.40
REMOVAL:			
MATERIAL:	\$0.00	\$0.00	\$0.00
OVERHEAD:	\$0.00	\$0.00	\$0.00
	\$0.00	\$0.00	\$0.00
LABOR HOURS:	0	0	0
LABOR COST:	\$0.00	\$0.00	\$0.00
OVERHEAD:	\$0.00	\$0.00	\$0.00
	\$0.00	\$0.00	\$0.00
VEHICLE:	\$0.00	\$0.00	\$0.00
CONTRACTOR:	\$0.00	\$0.00	\$0.00
ADDITIONAL ITEMS:	\$0.00	\$0.00	\$0.00
SUBTOTAL:	\$0.00	\$0.00	\$0.00
TRANSFER:			
LABOR HOURS:	0	0	0
LABOR COST:	\$0.00	\$0.00	\$0.00
OVERHEAD:	\$0.00	\$0.00	\$0.00
	\$0.00	\$0.00	\$0.00
VEHICLE:	\$0.00	\$0.00	\$0.00
CONTRACTOR:	\$0.00	\$0.00	\$0.00
ADDITIONAL ITEMS:	\$0.00	\$0.00	\$0.00
SUBTOTAL:	\$0.00	\$0.00	\$0.00
TOTALS:	\$48,492.40	\$0.00	\$48,492.40

THIS FORM IS NOT TO BE USED FOR CONTRIBUTION IN AID CONSTRUCTION (CIAC).



d\_material\_item\_summary\_test\_all

# Work Request Material Summary \*\*\*Includes Truck Stock\*\*\*

Design Number 1

**Printed Date: 3/10/2021** Dist: CSA

WR No. 925017

Page 1 of 1

			_		
Mat	erial Numbe	r Description	Unit Price	Total Cost	Asset?
INSTALL					
33	2007227	CEMENT, PVC CLEAR FAST DRY QUART W/DAUBE	\$6.22	\$205.26	N
40	2004389	CONDUIT, GALVANIZED 2 IN 10 FT WITH COUP	\$6.78	\$271.20	Υ
16156	2004488	CONDUIT, PVC 2 IN 20 FT BELL END	\$1.03	\$16,640.68	Υ
178	2004507	COUPLING, PVC 2 IN SCH 40 TEMS 13.01	\$0.60	\$106.80	N
88	2004395	ELBOW, 2" 90 DEGREE ,GALVANIZED, 24" MIN	\$34.29	\$3,017.52	N
1	2004394	ELBOW, GALV 2 INCH 45 DEG THD 15" RADIUS	\$26.25	\$26.25	N
3	2004719	HANDHOLE, SPLICING SINGLE PHASE PRIMARY	\$554.21	\$1,662.63	Υ
18157	2007414	TAPE, PULLING, POLYSTER, RATED AT 1250#,	\$0.03	\$544.70	N
			Total	\$22,475.04	



## **Estimate Summary**

Design Number 1

Distribution Services Primary cable - 2000 Sq Ft **Printed Date: 3/11/2021** 

District: CSA

**WR No. 925022**Date Sched: 4/1/21
Date Required: 4/21/21

Additional Information: URD Low Density 2000 PSC filing WR Description: LDUG 2000 sq ft PRIMARY CABLE

<u> </u>	<u> </u>		
INSTALLATION:	Capital	Oper./Maint.	Total
MATERIAL:	\$40,010.51	\$0.00	\$40,010.51
OVERHEAD:	\$5,533.47	\$0.00	\$5,533.47
	\$45,543.98	\$0.00	\$45,543.98
LABOR HOURS:	249.02	0	249.02
LABOR COST:	\$10,961.75	\$0.00	\$10,961.75
OVERHEAD:	\$14,524.30	\$0.00	\$14,524.30
	\$25,486.05	\$0.00	\$25,486.05
VEHICLE:	\$0.00	\$0.00	\$0.00
CONTRACTOR:	\$0.00	\$0.00	\$0.00
ADDITIONAL ITEMS:	\$0.00	\$0.00	\$0.00
SUBTOTAL:	\$71,030.03	\$0.00	\$71,030.03
REMOVAL:			
MATERIAL:	\$0.00	\$0.00	\$0.00
OVERHEAD:	\$0.00	\$0.00	\$0.00
	\$0.00	\$0.00	\$0.00
LABOR HOURS:	0	0	0
LABOR COST:	\$0.00	\$0.00	\$0.00
OVERHEAD:	\$0.00	\$0.00	\$0.00
	\$0.00	\$0.00	\$0.00
VEHICLE:	\$0.00	\$0.00	\$0.00
CONTRACTOR:	\$0.00	\$0.00	\$0.00
ADDITIONAL ITEMS:	\$0.00	\$0.00	\$0.00
SUBTOTAL:	\$0.00	\$0.00	\$0.00
TRANSFER:			
LABOR HOURS:	0	0	0
LABOR COST:	\$0.00	\$0.00	\$0.00
OVERHEAD:	\$0.00	\$0.00	\$0.00
	\$0.00	\$0.00	\$0.00
VEHICLE:	\$0.00	\$0.00	\$0.00
CONTRACTOR:	\$0.00	\$0.00	\$0.00
ADDITIONAL ITEMS:	\$0.00	\$0.00	\$0.00
SUBTOTAL:	\$0.00	\$0.00	\$0.00
TOTALS:	\$71,030.03	\$0.00	\$71,030.03

THIS FORM IS NOT TO BE USED FOR CONTRIBUTION IN AID CONSTRUCTION (CIAC).



d\_material\_item\_summary\_test\_all

# Work Request Material Summary \*\*\*Includes Truck Stock\*\*\*

Design Number 1

**Printed Date: 3/10/2021** Dist: CSA

WR No. 925022

Page 1 of 1

I Numbe	r Description			
	i Description	Unit Price	Total Cost	Asset?
004577	ANCHOR, LEAD EXPANSION, MEDIUM DUTY, SIZ	\$0.66	\$0.00	N
003157	BOLT, 1/2" - 13 X 1-1/2" 18-8 SS HEX HEA	\$2.59	\$0.00	N
003167	BOLT, MACHINE GALV HEX HEAD 5/8 X 1-1/4"	\$0.18	\$0.00	N
004343	CABLE, ALUMINUM, 15KV, 1/C, 1/0 AWG SOLI	\$2.08	\$33,192.64	Υ
004514	CAP, CONDUIT 2"	\$12.21	\$48.84	N
004453	CAP, END CABLE 600 V CABLE RANGE .940 -	\$1.96	\$7.84	N
003752	CLAMP, CONDUIT GROUND 1-1/4 IN - 2 IN CO	\$7.92	\$31.68	N
077906	CLAMP, GROUND ROD, F/U/W 1/2"ROD	\$1.80	\$0.00	N
004488	CONDUIT, PVC 2 IN 20 FT BELL END	\$1.03	\$82.40	Υ
077837	CONNECTOR, COMPRESSION H-BLOCK ACSR 2/0	\$0.66	\$5.28	N
005009	CONNECTOR, LDBRK 8.3/14.4KV 200A 3POS	\$108.70	\$0.00	N
077931	CONNECTOR, VICE CU #2 STR	\$2.38	\$183.26	N
077939	COUPLER, GROUND ROD, F/U/W 1/2"ROD	\$4.78	\$0.00	N
004982	ENCLOSURE, 200A AL SWITCH MOD/1 PH DUMMY	\$1,122.04	\$0.00	Υ
004642	KIT, SEALING, CABLE ACCESSORY, 1/0 - 4/0	\$9.46	\$577.06	N
001315	PAD, CONCRETE 40" X 45" X 4" 25- 50KVA T	\$103.25	\$0.00	N
007394	PADLOCK, GREEN, TESS, BRASS BODY, WR2	\$21.24	\$0.00	N
007489	REPELLENT, FIRE ANT GRANULE 4 OZ BIFENTH	\$2.77	\$0.00	N
077980	ROD,GROUND,CU BONDED,1/2"X10',THREADLESS	\$13.72	\$0.00	N
004403	STRAP, GALV 2 IN 2 HOLE	\$0.28	\$8.96	N
004883	TERMINATOR, LOADBREAK 200 AMP, 1/0 SOL	\$37.76	\$2,303.36	Υ
004634	TERMINATOR, POTHEAD, 1/0 TO 4/0, STEM	\$61.22	\$244.88	Υ
078005	WASHER, FLAT, GALVANIZED, 2" X 2" X 1/8	\$0.23	\$0.00	N
078006	WASHER, FLAT, GALVANIZED, 2" X 2" X 1/8"	\$0.24	\$0.00	N
8 2004184	WIRE, COPPER, BARE, #4 SOFT DRAWN 7 STR	\$0.63	\$5.04	N
		Total	\$40,010.50	
	003157 003167 004343 004514 004453 003752 077906 004488 077837 005009 077931 077939 004642 001315 007394 007489 077980 004403 004883 004634 078005 078006	DO3157 BOLT, 1/2" - 13 X 1-1/2" 18-8 SS HEX HEA DO3167 BOLT, MACHINE GALV HEX HEAD 5/8 X 1-1/4" DO4343 CABLE, ALUMINUM, 15KV, 1/C, 1/0 AWG SOLI DO4514 CAP, CONDUIT 2" DO4453 CAP, END CABLE 600 V CABLE RANGE .940 - DO3752 CLAMP, CONDUIT GROUND 1-1/4 IN - 2 IN CO DO77906 CLAMP, GROUND ROD, F/U/W 1/2"ROD DO4488 CONDUIT, PVC 2 IN 20 FT BELL END DO5009 CONNECTOR, COMPRESSION H-BLOCK ACSR 2/0 DO5009 CONNECTOR, VICE CU #2 STR DO77931 CONNECTOR, VICE CU #2 STR DO77939 COUPLER, GROUND ROD, F/U/W 1/2"ROD DO4482 ENCLOSURE, 200A AL SWITCH MOD/1 PH DUMMY DO4642 KIT, SEALING, CABLE ACCESSORY, 1/0 - 4/0 DO1315 PAD, CONCRETE 40" X 45" X 4" 25- 50KVA T DO7394 PADLOCK, GREEN, TESS, BRASS BODY, WR2 DO7489 REPELLENT, FIRE ANT GRANULE 4 OZ BIFENTH DO77980 ROD, GROUND, CU BONDED, 1/2"X10', THREADLESS DO4403 STRAP, GALV 2 IN 2 HOLE DO4634 TERMINATOR, LOADBREAK 200 AMP, 1/0 SOL DO4634 TERMINATOR, POTHEAD, 1/0 TO 4/0, STEM DO78005 WASHER, FLAT, GALVANIZED, 2" X 2" X 1/8"	003157         BOLT, 1/2" - 13 X 1-1/2" 18-8 SS HEX HEA         \$2.59           003167         BOLT, MACHINE GALV HEX HEAD 5/8 X 1-1/4"         \$0.18           004343         CABLE, ALUMINUM, 15KV, 1/C, 1/0 AWG SOLI         \$2.08           004514         CAP, CONDUIT 2"         \$12.21           004453         CAP, END CABLE 600 V CABLE RANGE .940 -         \$1.96           003752         CLAMP, CONDUIT GROUND 1-1/4 IN - 2 IN CO         \$7.92           077906         CLAMP, GROUND ROD, F/UW 1/2"ROD         \$1.80           004488         CONDUIT, PVC 2 IN 20 FT BELL END         \$1.03           077837         CONNECTOR, COMPRESSION H-BLOCK ACSR 2/0         \$0.66           07931         CONNECTOR, LDBRK 8.3/14.4KV 200A 3POS         \$108.70           077931         CONNECTOR, VICE CU #2 STR         \$2.38           077939         COUPLER, GROUND ROD, F/UW 1/2"ROD         \$4.78           004642         KIT, SEALING, CABLE ACCESSORY, 1/0 - 4/0         \$9.46           001315         PAD, CONCRETE 40" X 45" X 4" 25- 50KVA T         \$103.25           007489         REPELLENT, FIRE ANT GRANULE 4 OZ BIFENTH         \$2.77           077980         ROD,GROUND,CU BONDED,1/2"X10",THREADLESS         \$13.72           004403         STRAP, GALV 2 IN 2 HOLE         \$0.28	003157         BOLT, 1/2" - 13 X 1-1/2" 18-8 SS HEX HEA         \$2.59         \$0.00           003167         BOLT, MACHINE GALV HEX HEAD 5/8 X 1-1/4"         \$0.18         \$0.00           004343         CABLE, ALUMINUM, 15KV, 1/C, 1/0 AWG SOLI         \$2.08         \$33,192.64           004514         CAP, CONDUIT 2"         \$12.21         \$48.84           004453         CAP, END CABLE 600 V CABLE RANGE .940 -         \$1.96         \$7.84           003752         CLAMP, CONDUIT GROUND 1-1/4 IN - 2 IN CO         \$7.92         \$31.68           077906         CLAMP, GROUND ROD, F/UW 1/2"ROD         \$1.80         \$0.00           004488         CONDUIT, PVC 2 IN 20 T BELL END         \$1.03         \$82.40           077837         CONNECTOR, COMPRESSION H-BLOCK ACSR 2/0         \$0.66         \$5.28           005009         CONNECTOR, VICE CU #2 STR         \$2.38         \$183.26           077931         CONNECTOR, VICE CU #2 STR         \$2.38         \$183.26           077939         COUPLER, GROUND ROD, F/UW 1/2"ROD         \$4.78         \$0.00           004982         ENCLOSURE, 200A AL SWITCH MOD/1 PH DUMMY         \$1,122.04         \$0.00           004642         KIT, SEALING, CABLE ACCESSORY, 1/0 - 4/0         \$9.46         \$577.06           001315         PAD,



## Estimate Summary Design Number 1

Distribution Services Sec Cable and Handholes 2000 sq ft **Printed Date: 3/11/2021** 

District: CSA

WR No. 925024

Date Sched: 4/1/21 Date Required: 4/1/21

Additional Information: URD low density 2000 homes - PSC filing WR Description: LDUG 2000 sq ft SECONDARY CABLE

INSTALLATION:	Capital	Oper./Maint.	Total
MATERIAL:	\$10,194.86	\$0.00	\$10,194.86
OVERHEAD:	\$1,409.95	\$0.00	_\$1,409.95
	\$11,604.81	\$0.00	\$11,604.81
LABOR HOURS:	161.28	0	161.28
LABOR COST:	\$7,099.38	\$0.00	\$7,099.38
OVERHEAD:	\$9,406.70	\$0.00	\$9,406.70
	\$16,506.08	\$0.00	\$16,506.08
VEHICLE:	\$0.00	\$0.00	\$0.00
CONTRACTOR:	\$0.00	\$0.00	\$0.00
ADDITIONAL ITEMS:	\$0.00	\$0.00	\$0.00
SUBTOTAL:	\$28,110.89	\$0.00	\$28,110.89
REMOVAL:			
MATERIAL:	\$0.00	\$0.00	\$0.00
OVERHEAD:	\$0.00	\$0.00	\$0.00
	\$0.00	\$0.00	\$0.00
LABOR HOURS:	0	0	0
LABOR COST:	\$0.00	\$0.00	\$0.00
OVERHEAD:	\$0.00	\$0.00	\$0.00
	\$0.00	\$0.00	\$0.00
VEHICLE:	\$0.00	\$0.00	\$0.00
CONTRACTOR:	\$0.00	\$0.00	\$0.00
ADDITIONAL ITEMS:	\$0.00	\$0.00	\$0.00
SUBTOTAL:	\$0.00	\$0.00	\$0.00
TRANSFER:			
LABOR HOURS:	0	0	0
LABOR COST:	\$0.00	\$0.00	\$0.00
OVERHEAD:	\$0.00	\$0.00	\$0.00
	\$0.00	\$0.00	\$0.00
VEHICLE:	\$0.00	\$0.00	\$0.00
CONTRACTOR:	\$0.00	\$0.00	\$0.00
ADDITIONAL ITEMS:	\$0.00	\$0.00	\$0.00
SUBTOTAL:	\$0.00	\$0.00	\$0.00
TOTALS:	\$28,110.89	\$0.00	\$28,110.89



# Work Request Material Summary \*\*\*Includes Truck Stock\*\*\*

Design Number 1

**Printed Date: 3/10/2021** Dist: CSA

WR No. 925024

Mat	erial Numbe	er Description	Unit Price	Total Cost	Asset?
INSTALL					
0	2004351	CABLE, CONVERSE, AL, UG, 600V, 2/C, 2/0,	\$1.01	\$0.00	Υ
2605	2004354	CABLE, SWEETBRIAR, AL,UG,600V,2/C,4/0 AW	\$1.39	\$3,621.23	Υ
0	2004356	CABLE, XHHW-2,AL,UG,600V,2/C,500 MCM, 37	\$4.33	\$0.00	Υ
0	2005021	CONNECTOR, 600V URD, 4 POSITION, CONDUCT	\$16.25	\$0.00	N
0	2005022	CONNECTOR, 600V URD, 6 POSITION, CONDUCT	\$14.92	\$0.00	N
69	2005024	CONNECTOR, 600V URD, 6 POSITION, CONDUCT	\$23.41	\$1,615.29	N
0	2005025	CONNECTOR, 600V, URD, 8 POSITION, CONDUC	\$30.35	\$0.00	N
0	2005020	CONNECTOR, URD 600 V 4 POSITION #10-350M	\$10.92	\$0.00	N
23	2000241	DECAL,WARNING,NOTICE,CLEARANCE,10" X 7"	\$3.56	\$81.88	N
23	2004714	HANDHOLE, ABOVE GRADE, LARGE DOME	\$186.22	\$4,283.06	N
23	2005212	MARKER, CURB LEXAN .040 THICK, ROUND 2.5	\$2.83	\$65.09	N
23	2007395	PADLOCK, RED BRASS BODY 1/4" BRASS SHACK	\$22.97	\$528.31	N
			Total	\$10,194.86	



## Estimate Summary Design Number 1

Distribution Services Secondary conduit-2000 sq ft

**Printed Date:** 3/10/2021

District: CSA

WR No. 925026

Date Sched: 4/1/21 Date Required: 4/1/21

Additional Information: URD low density 2000 sq ft PSC filing WR Description: LDUG 2000 sq ft SECONDARY CONDUIT

INSTALLATION:	Capital	Oper./Maint.	Total
MATERIAL:	\$6,602.28	\$0.00	\$6,602.28
OVERHEAD:	\$913.09	\$0.00	\$913.09
	\$7,515.37	\$0.00	\$7,515.37
LABOR HOURS:	63.08	0	63.08
LABOR COST:	\$2,776.65	\$0.00	\$2,776.65
OVERHEAD:	\$3,679.04	\$0.00	\$3,679.04
	\$6,455.69	\$0.00	\$6,455.69
VEHICLE:	\$0.00	\$0.00	\$0.00
CONTRACTOR:	\$0.00	\$0.00	\$0.00
ADDITIONAL ITEMS:	\$0.00	\$0.00	\$0.00
SUBTOTAL:	\$13,971.06	\$0.00	\$13,971.06
REMOVAL:			
MATERIAL:	\$0.00	\$0.00	\$0.00
OVERHEAD:	\$0.00	\$0.00	\$0.00
	\$0.00	\$0.00	\$0.00
LABOR HOURS:	0	0	0
LABOR COST:	\$0.00	\$0.00	\$0.00
OVERHEAD:	\$0.00	\$0.00	\$0.00
	\$0.00	\$0.00	\$0.00
VEHICLE:	\$0.00	\$0.00	\$0.00
CONTRACTOR:	\$0.00	\$0.00	\$0.00
ADDITIONAL ITEMS:	\$0.00	\$0.00	\$0.00
SUBTOTAL:	\$0.00	\$0.00	\$0.00
TRANSFER:			
LABOR HOURS:	0	0	0
LABOR COST:	\$0.00	\$0.00	\$0.00
OVERHEAD:	\$0.00	\$0.00	\$0.00
	\$0.00	\$0.00	\$0.00
VEHICLE:	\$0.00	\$0.00	\$0.00
CONTRACTOR:	\$0.00	\$0.00	\$0.00
ADDITIONAL ITEMS:	\$0.00	\$0.00	\$0.00
SUBTOTAL:	\$0.00	\$0.00	\$0.00
TOTALS:	\$13,971.06	\$0.00	\$13,971.06



# Work Request Material Summary \*\*\*Includes Truck Stock\*\*\*

Design Number 1

**Printed Date: 3/10/2021** Dist: CSA

WR No. 925026

Mate	rial Numbe	er Description	Unit Price	Total Cost	Asset?
INSTALL					
1	2007227	CEMENT, PVC CLEAR FAST DRY QUART W/DAUBE	\$6.22	\$6.22	N
8	2007228	CEMENT, PVC GRAY MEDIUM DRY QUART W/DAUB	\$7.27	\$58.16	N
0	2004488	CONDUIT, PVC 2 IN 20 FT BELL END	\$1.03	\$0.00	Υ
340	2004517	CONDUIT, PVC P & C 3 IN 20 FT	\$1.70	\$578.00	Υ
1871	2004529	CONDUIT, PVC, 4" X 20', DB-60-TC-6	\$2.78	\$5,201.38	Υ
0	2004507	COUPLING, PVC 2 IN SCH 40 TEMS 13.01	\$0.60	\$0.00	N
8	2004521	COUPLING, PVC 3 IN SCH 40 TEMS 13.01	\$2.95	\$23.60	N
84	2004535	COUPLING, PVC 4 IN SCH 40 TEMS 13.01	\$4.28	\$359.52	N
0	2004511	ELBOW, CONDUIT PVC 2 IN SCH 40 90 DEG 9-	\$1.26	\$0.00	N
0	2004427	ELBOW, GALV 4 IN 45 DEG THD 16 IN RAD	\$45.37	\$0.00	N
0	2004510	ELBOW, PVC 2 IN 45 DEG 9-1/2 IN RAD SCH	\$0.94	\$0.00	N
0	2004523	ELBOW, PVC 3 IN 45 DEG 13 IN RAD SCH 40	\$3.62	\$0.00	N
4	2004524	ELBOW, PVC 3 IN 90 DEG 13 IN RAD SCH 40	\$4.52	\$18.08	N
42	2004538	ELBOW, PVC 4", 90 DEG., 16" RADIUS, SCHE	\$6.68	\$280.56	N
2559	2007414	TAPE, PULLING, POLYSTER, RATED AT 1250#,	\$0.03	\$76.76	N
			Total	\$6,602.28	



## Estimate Summary Design Number 1

Distribution Services Service Cable-2000 sq ft **Printed Date:** 3/11/2021

District: CSA

WR No. 925028

Date Sched: 4/1/21 Date Required: 4/1/21

Additional Information: Low density URD filing 2000 sq ft WR Description: LDUG 2000 sq ft SERVICE CABLE

INSTALLATION:	Capital	Oper./Maint.	Total	
MATERIAL:	\$23,370.30	\$0.00	\$23,370.30	
OVERHEAD:	\$3,232.12	\$0.00	\$3,232.12	
	\$26,602.42	\$0.00	\$26,602.42	
LABOR HOURS:	1.94	0	1.94	
LABOR COST:	\$85.46	\$0.00	\$85.46	
OVERHEAD:	\$113.22	\$0.00	\$113.22	
	\$198.68	\$0.00	\$198.68	
VEHICLE:	\$0.00	\$0.00	\$0.00	
CONTRACTOR:	\$0.00	\$0.00	\$0.00	
ADDITIONAL ITEMS:	\$0.00	\$0.00	\$0.00	
SUBTOTAL:	\$26,801.10	\$0.00	\$26,801.10	
REMOVAL:				
MATERIAL:	\$0.00	\$0.00	\$0.00	
OVERHEAD:	\$0.00	\$0.00	\$0.00	
	\$0.00	\$0.00	\$0.00	
LABOR HOURS:	0	0	0	
LABOR COST:	\$0.00	\$0.00	\$0.00	
OVERHEAD:	\$0.00	\$0.00	\$0.00	
	\$0.00	\$0.00	\$0.00	
VEHICLE:	\$0.00	\$0.00	\$0.00	
CONTRACTOR:	\$0.00	\$0.00	\$0.00	
ADDITIONAL ITEMS:	\$0.00	\$0.00	\$0.00	
SUBTOTAL:	\$0.00	\$0.00	\$0.00	
TRANSFER:				
	_			
LABOR HOURS:	0	0	0	
LABOR COST: OVERHEAD:	\$0.00	\$0.00	\$0.00	
OVERHEAD.	\$0.00	\$0.00	\$0.00	
	\$0.00	\$0.00	\$0.00	
VEHICLE:	\$0.00	\$0.00	\$0.00	
CONTRACTOR:	\$0.00	\$0.00	\$0.00	
ADDITIONAL ITEMS:	\$0.00	\$0.00	\$0.00	
SUBTOTAL:	\$0.00	\$0.00	\$0.00	
TOTALS:	\$26,801.10	\$0.00	\$26,801.10	



# Work Request Material Summary \*\*\*Includes Truck Stock\*\*\*

Design Number 1

**Printed Date: 3/11/2021** Dist: CSA

WR No. 925028

Mate	erial Numbe	er Description	Unit Price	Total Cos	t Asset?
INSTALL					
17795	2004351	CABLE, CONVERSE, AL, UG, 600V, 2/C, 2/0,	\$1.01	\$16,338.77	Υ
3883	2004354	CABLE, SWEETBRIAR, AL, UG, 600V, 2/C, 4/0 AW	\$1.39	\$4,498.04	Υ
			Total	\$23,370.30	



## Estimate Summary Design Number 1

Distribution Services Meter Labor- 2000 sq ft

**Printed Date:** 3/10/2021

District: CSA

WR No. 925029

Date Sched: 4/1/21 Date Required: 4/1/21

Additional Information: Low density URD filing 2000 sq ft homes

WR Description: LDUG 2000 sq ft METERS

INSTALLATION:	Capital	Oper./Maint.	Total	
MATERIAL:	\$0.00	\$0.00	\$0.00	
OVERHEAD:	\$0.00	\$0.00	\$0.00	
	\$0.00	\$0.00	\$0.00	
LABOR HOURS:	42.07	0	42.07	
LABOR COST:	\$1,851.92	\$0.00	\$1,851.92	
OVERHEAD:	\$2,453.80	\$0.00	\$2,453.80	
	\$4,305.72	\$0.00	\$4,305.72	
VEHICLE:	\$0.00	\$0.00	\$0.00	
CONTRACTOR:	\$0.00	\$0.00	\$0.00	
ADDITIONAL ITEMS:	\$0.00	\$0.00	\$0.00	
SUBTOTAL:	\$4,305.72	\$0.00	\$4,305.72	
REMOVAL:				
MATERIAL:	\$0.00	\$0.00	\$0.00	
OVERHEAD:	\$0.00	\$0.00	\$0.00	
	\$0.00	\$0.00	\$0.00	
LABOR HOURS:	0	0	0	
LABOR COST:	\$0.00	\$0.00	\$0.00	
OVERHEAD:	\$0.00	\$0.00	\$0.00	
	\$0.00	\$0.00	\$0.00	
VEHICLE:	\$0.00	\$0.00	\$0.00	
CONTRACTOR:	\$0.00	\$0.00	\$0.00	
ADDITIONAL ITEMS:	\$0.00	\$0.00	\$0.00	
SUBTOTAL:	\$0.00	\$0.00	\$0.00	
TRANSFER:				
	0	0	0	
LABOR HOURS: LABOR COST:		-		
OVERHEAD:	\$0.00	\$0.00	\$0.00 \$0.00	
	\$0.00	\$0.00		
	\$0.00	\$0.00	\$0.00 \$0.00	
VEHICLE:	\$0.00	\$0.00		
CONTRACTOR:	\$0.00	\$0.00	\$0.00 \$0.00	
ADDITIONAL ITEMS:	\$0.00	\$0.00	<del>.</del>	
SUBTOTAL:	\$0.00	\$0.00	\$0.00	
TOTALS:	\$4,305.72	\$0.00	\$4,305.72	



## Estimate Summary Design Number 1

Distribution Services Service Conduit- 2000 sq ft

**Printed Date:** 3/10/2021

District: CSA

WR No. 925030

Date Sched: 4/1/21 Date Required: 4/1/21

Additional Information: Low density URD filing for 2000 sq ft homes WR Description: LDUG 2000 sq ft SERVICE CONDUIT

INSTALLATION:	Capital	Oper./Maint.	Total
MATERIAL:	\$27,272.06	\$0.00	\$27,272.06
OVERHEAD:	\$3,771.72	\$0.00	\$3,771.72
	\$31,043.78	\$0.00	\$31,043.78
LABOR HOURS:	767.62	0	767.62
LABOR COST:	\$33,791.97	\$0.00	\$33,791.97
OVERHEAD:	\$44,774.34	\$0.00	\$44,774.34
	\$78,566.31	\$0.00	\$78,566.31
VEHICLE:	\$0.00	\$0.00	\$0.00
CONTRACTOR:	\$0.00	\$0.00	\$0.00
ADDITIONAL ITEMS:	\$0.00	\$0.00	\$0.00
SUBTOTAL:	\$109,610.09	\$0.00	\$109,610.09
REMOVAL:			
MATERIAL:	\$0.00	\$0.00	\$0.00
OVERHEAD:	\$0.00	\$0.00	\$0.00
	\$0.00	\$0.00	\$0.00
LABOR HOURS:	0	0	0
LABOR COST:	\$0.00	\$0.00	\$0.00
OVERHEAD:	\$0.00	\$0.00	\$0.00
	\$0.00	\$0.00	\$0.00
VEHICLE:	\$0.00	\$0.00	\$0.00
CONTRACTOR:	\$0.00	\$0.00	\$0.00
ADDITIONAL ITEMS:	\$0.00	\$0.00	\$0.00
SUBTOTAL:	\$0.00	\$0.00	\$0.00
TRANSFER:			
LABOR HOURS:	0	0	0
LABOR COST:	\$0.00	\$0.00	\$0.00
OVERHEAD:	\$0.00	\$0.00	\$0.00
	\$0.00	\$0.00	\$0.00
VEHICLE:	\$0.00	\$0.00	\$0.00
CONTRACTOR:	\$0.00	\$0.00	\$0.00
ADDITIONAL ITEMS:	\$0.00	\$0.00	\$0.00
SUBTOTAL:	\$0.00	\$0.00	\$0.00
TOTALS:	\$109,610.09	\$0.00	\$109,610.09




# Work Request Material Summary \*\*\*Includes Truck Stock\*\*\*

Design Number 1

**Printed Date: 3/10/2021** Dist: CSA

WR No. 925030

Materi	al Number	Description	Unit Price	Total Cost	Asset?
INSTALL					
23	2004492	ADAPTER,COND PVC FMLE 2" SCH 40 SOCXFPT	\$0.57	\$13.11	N
188	2004493	ADAPTOR, 2" PVC, FEMALE SLIP TO MALE THR	\$0.40	\$75.20	N
37	2007227	CEMENT, PVC CLEAR FAST DRY QUART W/DAUBE	\$6.22	\$230.14	N
23	2004409	COND,SRVC RISER,TYPE IIPVC,40,2.5"X7'	\$12.00	\$276.00	N
15237	2004488	CONDUIT, PVC 2 IN 20 FT BELL END	\$1.03	\$15,694.11	Υ
2070	2004491	CONDUIT, PVC 2 IN 250 FT ROLL FLEXIBLE	\$1.13	\$2,339.10	N
23	2004518	CONDUIT, PVC 3 IN X 250 FT ROLL FLEXIBL	\$2.16	\$49.68	N
3121	2004517	CONDUIT, PVC P & C 3 IN 20 FT	\$1.70	\$5,305.70	Υ
188	2004401	CONDUIT, SERVICE RISER, PVC, 2"	\$4.92	\$924.96	N
754	2004507	COUPLING, PVC 2 IN SCH 40 TEMS 13.01	\$0.60	\$452.40	N
138	2004521	COUPLING, PVC 3 IN SCH 40 TEMS 13.01	\$2.95	\$407.10	N
504	2004511	ELBOW, CONDUIT PVC 2 IN SCH 40 90 DEG 9-	\$1.26	\$635.04	N
0	2004510	ELBOW, PVC 2 IN 45 DEG 9-1/2 IN RAD SCH	\$0.94	\$0.00	N
0	2004523	ELBOW, PVC 3 IN 45 DEG 13 IN RAD SCH 40	\$3.62	\$0.00	N
69	2004524	ELBOW, PVC 3 IN 90 DEG 13 IN RAD SCH 40	\$4.52	\$311.88	N
188	2004396	NUT, LOCK GALV 2 IN	\$0.54	\$101.52	N
23	2004408	NUT, LOCK GALV 2-1/2 IN	\$1.06	\$24.38	N
14391	2007414	TAPE, PULLING, POLYSTER, RATED AT 1250#,	\$0.03	\$431.74	N
			Total	\$27,272.06	



### OH Construction Cost Data Summary Low Density (210-Lot) OH Subdivision Costs

	Α	В	C (C + M )	D	E (F + L)	F (G+H+1)	G	H (G x J x TLF)	(G x K x CLF)	J	K	L	M (D x MHR)	N (C+E)
			Material and		Total Labor		Base	TEC Labor	Contract Labor	TEC	Contractor		Material	
Line #	Work Type/WR #	Description	Handling	Material	Plus Vehicles	Total Labor	Labor	Overheads	Overheads	Work %	Work %	Vehicle	Handling	Total
1	Transformers		40.000.00								400/			
2	925037	Install & Ground Transformers	49,232.37	\$43,871.30	18,530.21	16,572.33	9,649.44	6,148.62	774.27	60%	40%	\$1,957.87	5,361.07	67,762.58
3	Primary													
4	925038	Install Primary Line	3,780.00	\$3,368.38	9,895.97	8,850.38	5,153.24	3,283.64	413.50	60%	40%	\$1,045.59	411.62	13,675.97
,	523030	includes Grounding Primary Takeoffs	3,700.00	φ3,300.30	3,033.31	0,000.00	3,133.24	3,203.04	410.00	0076	4070	φ1,040.05	411.02	13,073.37
7	Poles	includes Grounding Primary Takeons												
8	925039	Install Poles and Guy Stubs	35,516.15	\$31,648.68	58,469.09	52,291.34	30,447.26	19,400.99	2,443.09	60%	40%	\$6,177.75	3,867.47	93,985.24
9	020000	Includes Haul Poles Out	00,010.10	ψο 1,0 10.00	00,100.00	02,201.01	00,111.20	10,100.00	2,110.00	0070	1070	ψο,	0,007.17	00,000.21
10	Secondary	modes rider side out												
11	925040	Install Secondary Cable	28,563.08	\$25,452.75	33,643.82	30,089.07	17,519.72	11,163.57	1,405.78	60%	40%	\$3,554.75	3,110.33	62,206.90
12		,				,		,	,				-,	. ,
13	Services													
14	926547	Install Service Cable & Meters	31,785.04	\$28,323.86	16,788.28	15,014.46	8,742.35	5,570.63	701.49	60%	40%	\$1,773.82	3,461.18	48,573.32
15														
16														
17	Engineering	Design/Inspection/Coordination	-	-	13,788.39	13,788.39	-	-	-	100%	0%	-	-	13,788.39
18														
19	Tree Trim		-	-	-	-	-	-	-			-	-	-
20														
21	Totals (Sum of lines:	2, 5, 8, 11, 14, 17, and 19)	\$ 148,876.63 \$	132,664.97	\$ 151,115.76	\$ 136,605.98	\$ 71,512.01 \$	45,567.45	\$ 5,738.12		-	\$ 14,509.79	\$ 16,211.66 \$	299,992.39
22	Cost per Lot	(line 21 / 210 lots)	\$ 708.94		\$ 719.60								\$	1,428.54

Adjustment Factors			
TEC Operations Labor Overhead Factor	TLF =	1.062	
Contractor Labor Overhead Factor	CLF =	0.2006	
Current year material handling charge rate	MHR =	0.1222	

TAMPA ELECTRIC COMPANY DOCKET NO. 20210064-EI STAFF'S THIRD DATA REQUEST REQUEST NO. 3b

### Low Density - 210 Lots - Overhead Material List

This worksheet lists the totals for major materials to be listed on the associated work request print as requested by the PSC.

- 1225.0 Total Connected KVA
- 1258.9 Total peak demand KVA
  - 0 25 kVA Transformers
  - 4 37.5 kVA Transformers
  - 17 50 kVA Transformers
  - 3 75 kVA Transformers
- 10130 #2AAAC Primary
  - 65 Primary Poles
  - 0 2/0 AWG Triplex Secondary
- 8000 4/0 AWG Triplex Secondary
- 2135 #2AAAC Secondary Neutral
- 1515 2-2/0 & 1-1/0 AL Triplex Service Drop (considered secondary)
- 545 2-4/0 & 1-2/0 AL Triplex Service Drop (considered secondary)
- 35 Secondary Poles
- 9360 2-2/0 & 1-1/0 AL Triplex Service Drop
- 0 2-4/0 & 1-2/0 AL Triplex Service Drop

### Summary of assemblies (CU's) for Low Density 2000 sq ft Overhead Design - March 2021

Work Request #1	925037	- Transformers (enter these	e Construction Units into W	'orkPro)			
	25 KVA	37.5 KVA	50 KVA	75 KVA	Stirrup	Spacer	Grounding
Assemblies ====>	PKT11W3F	PKT11W4F	PKT11W5F	PKT11W6F	ALSTRP1/0	SEWC	GRDMEG1/2
Total Quantities ==>	0	4	17	3	24	24	24

Work Request #2	925038	Primary						
	#2 AAAC	1st span	Add'l	Fused cutout	Deadend & tap	2 way lateral	Fuse	Grounding
Assemblies ====>	WIOPA	WIO1F	WIO1A	PKP102WB3A	PKP101WA3A	PKP105WA4A	FLOH103	GRDMEG1/2
Total Quantities ==>	10130	19	43	2	7	2	2	5

Work Request #3	925039	- Poles and Guys											
Should be ====>	Pole haul	1ø tangent	1ø tangent	1ø Deadend	1ø angle <20	1ø angle <20	1ø angle >20	1ø angle >20	3 ø	Down guys	Pole hardware	Guy wire	Down guys
Assemblies ====>	POLE_HAUL	STP101_TAN_40C2	STP101_TAN_45C2	STP401_DE_40C2	STP101_ANG_40C2	STP101_ANG_45C2	STP301_RC_40C2	STP301_RC_45C2	STP104_TAN_45C2	PKG12W2H	PKG31W1H	GUYSTR3/8	PKG11W1F
Total Quantities ==>	65	12	1	11	20	1	17	1	2	56	2	70	0

Work Request #4	925040	- Secondary - From Second	dary&Neutral worksheet								
	2/0	4/0	#2 Neutral	1st span	Add'l	1st span	Add'l	Eyebolt	Eyenut	DE+Bolt	
Assemblies ====>	WIO3SB	WIO3SC	WIOPA	WIO1F	WIO1A	WIOCF	WIOCA	SEW1DEN	SEG1DEN	PKS11W	CABLEOPEN
Total Quantities ==>	0	8000	2135	9	2	33	20	4	12	30	12

More of Work Request #4		<ul> <li>Secondary continued</li> </ul>	<ul> <li>From Secondary&amp;Neutral v</li> </ul>	orksheet and SlackSecondary	(service cable) & Secondar	y Poles worksheet					
	Pole hardware	Guy wire		35' Class 4	35' Class 6	30' Class 6	Down guy				
Assemblies ====>	PKG31W1H	GUYSTR3/8	POLE_HAUL	STS11C	STS11B	STS11A	PKG11W1H	PKS21G	CA2/0TPX	CA4/0TPX	SVLABOR
Total Quantities ==>	16	1390	35	35	0	0	0	34	1515	545	34

Work Request #5	926547	- Services		
Assemblies ==>> Total Quantities ==>	CA2/0TPX 9360	CA4/0TPX 0	SVLABOR 0	METERLABOR 210



## Estimate Summary Design Number 1

Distribution Services LDOH 2000 sq ft Transformers **Printed Date:** 3/10/2021

District: CSA

WR No. 925037

Date Sched: 4/1/21 Date Required: 4/1/21

Additional Information: Used for Low Density 2000 sq ft 3.5 ton ac WR Description: LDOH 2000 sq ft TRANSFORMERS

INSTALLATION:	Capital	Oper./Maint.	Total	
MATERIAL:	\$43,871.30	\$0.00	\$43,871.30	
OVERHEAD:	\$6,067.39	\$0.00	\$6,067.39	
	\$49,938.69	\$0.00	\$49,938.69	
LABOR HOURS:	219.24	0	219.24	
LABOR COST:	\$9,649.44	\$0.00	\$9,649.44	
OVERHEAD:	\$12,785.56	\$0.00	\$12,785.56	
	\$22,435.00	\$0.00	\$22,435.00	
VEHICLE:	\$0.00	\$0.00	\$0.00	
CONTRACTOR:	\$0.00	\$0.00	\$0.00	
ADDITIONAL ITEMS:	\$0.00	\$0.00	\$0.00	
SUBTOTAL:	\$72,373.69	\$0.00	\$72,373.69	
REMOVAL:				
MATERIAL:	\$0.00	\$0.00	\$0.00	
OVERHEAD:	\$0.00	\$0.00	\$0.00	
	\$0.00	\$0.00	\$0.00	
LABOR HOURS:	0	0	0	
LABOR COST:	\$0.00	\$0.00	\$0.00	
OVERHEAD:	\$0.00	\$0.00	\$0.00	
	\$0.00	\$0.00	\$0.00	
VEHICLE:	\$0.00	\$0.00	\$0.00	
CONTRACTOR:	\$0.00	\$0.00	\$0.00	
ADDITIONAL ITEMS:	\$0.00	\$0.00	\$0.00	
SUBTOTAL:	\$0.00	\$0.00	\$0.00	
TRANSFER:				
LABOR HOURS:	0	0	0	
LABOR COST:	\$0.00	\$0.00	\$0.00	
OVERHEAD:	\$0.00	\$0.00	\$0.00	
	\$0.00	\$0.00	\$0.00	
VEHICLE:	\$0.00	\$0.00	\$0.00	
CONTRACTOR:	\$0.00	\$0.00	\$0.00	
ADDITIONAL ITEMS:	\$0.00	\$0.00	\$0.00	
SUBTOTAL:	\$0.00	\$0.00	\$0.00	
TOTALS:	\$72,373.69	\$0.00	\$72,373.69	



# Work Request Material Summary \*\*\*Includes Truck Stock\*\*\*

Design Number 1

**Printed Date: 3/10/2021** Dist: CSA

WR No. 925037 Page 1 of 1

Mate	rial Number	Description	Unit Price	Total Cost	Asset?
INSTALL					
24	2003646	ARRESTER, DISTRIBUTION, 10KV, 8.4KV MCOV	\$39.68	\$952.32	Υ
24	2077754	BOLT, MACHINE 5/8" X 10", GALV. FULL	\$1.04	\$24.96	N
48	2077755	BOLT,MACHINE,SQ HEAD,5/8"X12",ONE SQ NUT	\$1.16	\$55.68	N
24	2003690	BRACKET, CUTOUT, ARRESTER & POTHEAD DWG	\$7.22	\$173.28	N
24	2004660	BRACKET,"L" 5-5/8"IN LENGTH FOR MTG CUTO	\$10.41	\$249.84	N
312	2004197	CABLE, HANDCOIL, COPPER, 600V, 2/0 AWG,	\$2.32	\$723.84	N
36	2004199	CABLE, HANDCOIL, COPPER, 600V, 4/0 AWG,	\$3.75	\$135.00	N
24	2077906	CLAMP, GROUND ROD, F/U/W 1/2"ROD	\$1.80	\$43.20	N
24	2077911	CLAMP, HOT LINE CU TO CU #6 SOL- 2 STR T	\$5.73	\$137.52	N
48	2078000	CLAMP,GND,TRANSFORMER,#10 SOL-#1 STR CU	\$2.31	\$110.88	N
960	2078012	CONDUCTOR, COPPERCLAD, 3 STR. #9, DSA 30	\$0.84	\$806.40	N
6	2003528	CONNECTOR, 2-BOLT AL MAIN 336-500MCM TAP	\$25.78	\$154.68	N
63	2077839	CONNECTOR, COMPRESSION H-BLOCK ACSR 1/0-	\$0.53	\$33.39	N
24	2077837	CONNECTOR, COMPRESSION H-BLOCK ACSR 2/0	\$0.66	\$15.84	N
3	2077845	CONNECTOR, COMPRESSION H-BLOCK ACSR 4/0	\$0.68	\$2.04	N
96	2077930	CONNECTOR, VICE CU #4 STR	\$1.91	\$183.36	N
72	2077939	COUPLER, GROUND ROD, F/U/W 1/2"ROD	\$4.78	\$344.16	N
42	2003516	COVER, SNAP-ON SQUEEZON CONNECTOR D DIE	\$0.39	\$16.38	N
24	2003846	CUTOUT, 15KV, 100A FUSE HLDR, 300A UNVRS	\$70.74	\$1,697.76	Υ
17	2077806	FUSE LINK, 10A UNVRSL 100A CUTOUT 23" OA	\$3.91	\$66.47	N
3	2077807	FUSE LINK, 15A UNVRSL 100A CUTOUT 23" OA	\$3.93	\$11.79	N
4	2077805	FUSE LINK, 7A UNVRSL 100A CUTOUT 23" OAL	\$3.89	\$15.56	N
48	2077965	MOULDING, GROUND WIRE, PVC 1/2 IN X 8 FT	\$1.74	\$83.52	N
24	2007368	PROTECTOR, WILD LIFE, SLIP-ON TYPE	\$5.35	\$128.40	N
96	2077980	ROD,GROUND,CU BONDED,1/2"X10',THREADLESS	\$13.72	\$1,317.12	N
24	2077767	ROLLED BOLT, DOUBLE-ARMING, 5/8"X 16"	\$2.65	\$63.60	N
24	2077789	SCREW, LAG PILOT POINT 3/8 X 3	\$0.27	\$6.48	N
24	2077812	SPACER, CABLED SECONDARY	\$6.79	\$162.96	N
240	2077997	STAPLE, SECURES 1/2" PVC MOULDING TO WOO	\$0.27	\$64.80	N
24	2077826	STIRRUP, AL BODY & CU BAIL 2-4/0	\$10.18	\$244.32	N
4	2001368	TX,OH,37.5 kVA,7.62/13.2Y,120/240,FR3	\$1,253.83	\$5,015.32	Υ
17	2001369	TX,OH,50 kVA,7.62/13.2Y,120/240,FR3	\$1,463.60	\$24,881.20	Υ
3	2001370	TX,OH,75 kVA,7.62/13.2Y,120/240,FR3	\$1,924.56	\$5,773.68	Υ
120	2078006	WASHER, FLAT, GALVANIZED, 2" X 2" X 1/8"	\$0.24	\$28.80	N
72	2078014	WIRE, ALUMINUM, TIE, #4 BARE ANNEALED	\$0.11	\$7.92	N
76	2004184	WIRE, COPPER, BARE, #4 SOFT DRAWN 7 STR	\$0.63	\$47.63	N
240	2078011	WIRE, COPPER, TIE, #6 SOLID SOFT DRAWN	\$0.38	\$91.20	N
			Total	\$43,871.30	



## **Estimate Summary**

Design Number 1

Distribution Services LDOH 2000 sq ft Primary **Printed Date:** 3/10/2021

District: CSA

WR No. 925038

Date Sched: 4/1/21 Date Required: 4/1/21

Additional Information: Used for 2000 square foot design WR Description: LDOH 2000 sq ft PRIMARY

<u> </u>	<u> </u>			
INSTALLATION:	Capital	Oper./Maint.	Total	
MATERIAL:	\$3,368.38	\$0.00	\$3,368.38	
OVERHEAD:	\$465.86	\$0.00	\$465.86	
	\$3,834.24	\$0.00	\$3,834.24	
LABOR HOURS:	117.08	0	117.08	
LABOR COST:	\$5,153.24	\$0.00	\$5,153.24	
OVERHEAD:	\$6,828.03	\$0.00	\$6,828.03	
	\$11,981.27	\$0.00	\$11,981.27	
VEHICLE:	\$0.00	\$0.00	\$0.00	
CONTRACTOR:	\$0.00	\$0.00	\$0.00	
ADDITIONAL ITEMS:	\$0.00	\$0.00	\$0.00	
SUBTOTAL:	\$15,815.51	\$0.00	\$15,815.51	
REMOVAL:				
MATERIAL:	\$0.00	\$0.00	\$0.00	
OVERHEAD:	\$0.00	\$0.00	\$0.00	
	\$0.00	\$0.00	\$0.00	
LABOR HOURS:	0	0	0	
LABOR COST:	\$0.00	\$0.00	\$0.00	
OVERHEAD:	\$0.00	\$0.00	\$0.00	
	\$0.00	\$0.00	\$0.00	
VEHICLE:	\$0.00	\$0.00	\$0.00	
CONTRACTOR:	\$0.00	\$0.00	\$0.00	
ADDITIONAL ITEMS:	\$0.00	\$0.00	\$0.00	
SUBTOTAL:	\$0.00	\$0.00	\$0.00	
TRANSFER:				
THATOI EK				
LABOR HOURS:	0	0	0	
LABOR COST:	\$0.00	\$0.00	\$0.00	
OVERHEAD:	\$0.00	\$0.00	\$0.00	
	\$0.00	\$0.00	\$0.00	
VEHICLE:	\$0.00	\$0.00	\$0.00	
CONTRACTOR:	\$0.00	\$0.00	\$0.00	
ADDITIONAL ITEMS:	\$0.00	\$0.00	\$0.00	
SUBTOTAL:	\$0.00	\$0.00	\$0.00	
TOTALS:	\$15,815.51	\$0.00	\$15,815.51	



# Work Request Material Summary \*\*\*Includes Truck Stock\*\*\*

Design Number 1

**Printed Date: 3/10/2021** Dist: CSA

WR No. 925038

			raye		
Materi	ial Number	Description	Unit Price	Total Cost	Asset?
INSTALL					
5	2003646	ARRESTER, DISTRIBUTION, 10KV, 8.4KV MCOV	\$39.68	\$198.40	Υ
9	2077739	BOLT, EYE, 5/8 IN. X 10 IN., GALVANIZED	\$3.12	\$28.08	N
7	2077754	BOLT, MACHINE 5/8" X 10", GALV. FULL	\$1.04	\$7.28	N
2	2077780	BOLT, SPOOL, 5/8" X 10", GALV. SINGLE UP	\$4.16	\$8.32	N
5	2003681	BRACKET, "L", LIGHTNING ARRESTER 10 KV	\$7.95	\$39.75	N
2	2003685	BRACKET, FIBERGLASS STANDOFF VERTICAL16"	\$25.98	\$51.96	N
2	2004660	BRACKET,"L" 5-5/8"IN LENGTH FOR MTG CUTO	\$10.41	\$20.82	N
18	2077818	CLAMP, DEADEND ACSR OR AAC #2-4/0OR .30-	\$9.12	\$164.16	N
5	2077906	CLAMP, GROUND ROD, F/U/W 1/2"ROD	\$1.80	\$9.00	N
16	2077911	CLAMP, HOT LINE CU TO CU #6 SOL- 2 STR T	\$5.73	\$91.68	N
10637	2004331	CONDUCTOR, BARE OVERHEAD, 2 AWG, AAAC, 7	\$0.15	\$1,595.48	Υ
200	2078012	CONDUCTOR, COPPERCLAD, 3 STR. #9, DSA 30	\$0.84	\$168.00	N
22	2077838	CONNECTOR, COMPRESSION H-BLOCK ACSR #2-1	\$0.41	\$9.02	N
16	2077837	CONNECTOR, COMPRESSION H-BLOCK ACSR 2/0	\$0.66	\$10.56	N
10	2077930	CONNECTOR, VICE CU #4 STR	\$1.91	\$19.10	N
15	2077939	COUPLER, GROUND ROD, F/U/W 1/2"ROD	\$4.78	\$71.70	N
2	2003846	CUTOUT, 15KV, 100A FUSE HLDR, 300A UNVRS	\$70.74	\$141.48	Υ
4	2077765	DOUBLE-ARMING, GALVANIZED 5/8 "X 12"	\$2.35	\$9.40	N
2	2077794	FUSE LINK, 103A UNVRSL 100A CUTOUT 23" O	\$24.29	\$48.58	N
2	2077954	INSULATOR, PIN TYPE, 10KV, ANSI CLASS 55	\$3.75	\$7.50	N
2	2077952	INSULATOR, SPOOL, ANSI CLASS 53-3, TRANS	\$1.21	\$2.42	N
9	2077959	INSULATOR, SUSPENSION, POLYMER, 25KV, AP	\$11.86	\$106.74	N
10	2077965	MOULDING, GROUND WIRE, PVC 1/2 IN X 8 FT	\$1.74	\$17.40	N
9	2077783	NUT, EYE, STANDARD, 1-1/2" GALVANIZED FO	\$1.51	\$13.59	N
20	2077980	ROD,GROUND,CU BONDED,1/2"X10',THREADLESS	\$13.72	\$274.40	N
7	2077789	SCREW, LAG PILOT POINT 3/8 X 3	\$0.27	\$1.89	N
50	2077997	STAPLE, SECURES 1/2" PVC MOULDING TO WOO	\$0.27	\$13.50	N
2	2077828	STIRRUP, AL BODY & CU BAIL 1/0-397	\$17.19	\$34.38	N
14	2077826	STIRRUP, AL BODY & CU BAIL 2-4/0	\$10.18	\$142.52	N
2	2003613	TIE, TOP, FORMED WIRE #2 ACSR OR #2 AAAC	\$2.87	\$5.74	N
22	2078006	WASHER, FLAT, GALVANIZED, 2" X 2" X 1/8"	\$0.24	\$5.28	N
4	2078014	WIRE, ALUMINUM, TIE, #4 BARE ANNEALED	\$0.11	\$0.44	N
67	2004184	WIRE, COPPER, BARE, #4 SOFT DRAWN 7 STR	\$0.63	\$42.21	N
20	2078011	WIRE, COPPER, TIE, #6 SOLID SOFT DRAWN	\$0.38	\$7.60	N
			Total	\$3,368.37	



## Estimate Summary Design Number 1

Distribution Services LDOH 2000 sq ft - POLES

**Printed Date:** 3/10/2021

District: CSA

WR No. 925039

Date Sched: 4/1/21 Date Required: 4/1/21

Additional Information: Used for 2000 square foot design WR Description: LDOH 2000 sq ft POLES

INSTALLATION:	Capital	Oper./Maint.	Total	
MATERIAL:	\$31,648.68	\$0.00	\$31,648.68	
OVERHEAD:	\$4,377.02	\$0.00	\$4,377.02	
	\$36,025.70	\$0.00	\$36,025.70	
LABOR HOURS:	691.7	0	691.7	
LABOR COST:	\$30,447.26	\$0.00	\$30,447.26	
OVERHEAD:	\$40,342.60	\$0.00	\$40,342.60	
	\$70,789.86	\$0.00	\$70,789.86	
VEHICLE:	\$0.00	\$0.00	\$0.00	
CONTRACTOR:	\$0.00	\$0.00	\$0.00	
ADDITIONAL ITEMS:	\$0.00	\$0.00	\$0.00	
SUBTOTAL:	\$106,815.56	\$0.00	\$106,815.56	
REMOVAL:				
MATERIAL:	\$0.00	\$0.00	\$0.00	
OVERHEAD:	\$0.00	\$0.00	\$0.00	
	\$0.00	\$0.00	\$0.00	
LABOR HOURS:	0	0	0	
LABOR COST:	\$0.00	\$0.00	\$0.00	
OVERHEAD:	\$0.00	\$0.00	\$0.00	
	\$0.00	\$0.00	\$0.00	
VEHICLE:	\$0.00	\$0.00	\$0.00	
CONTRACTOR:	\$0.00	\$0.00	\$0.00	
ADDITIONAL ITEMS:	\$0.00	\$0.00	\$0.00	
SUBTOTAL:	\$0.00	\$0.00	\$0.00	
TRANSFER:				
LABOR HOURS:	0	0	0	
LABOR COST:	\$0.00	\$0.00	\$0.00	
OVERHEAD:	\$0.00	\$0.00	\$0.00	
	\$0.00	\$0.00	\$0.00	
VEHICLE:	\$0.00	\$0.00	\$0.00	
CONTRACTOR:	\$0.00	\$0.00	\$0.00	
ADDITIONAL ITEMS:	\$0.00	\$0.00	\$0.00	
SUBTOTAL:	\$0.00	\$0.00	\$0.00	
TOTALS:	\$106,815.56	\$0.00	\$106,815.56	



# Work Request Material Summary \*\*\*Includes Truck Stock\*\*\*

Design Number 1

**Printed Date: 3/10/2021** Dist: CSA

WR No. 925039

				, 1 01 1	
Mate	rial Numbe	r Description	Unit Price	Total Cost	Asset?
INSTALL					
56	2003632	ANCHOR,SCRW GALV 10" WING 1-1/4" ROD 8"	\$48.15	\$2,696.40	Ν
37	2077739	BOLT, EYE, 5/8 IN. X 10 IN., GALVANIZED	\$3.12	\$115.44	N
114	2077764	BOLT, MACHINE 3/4" X 12", GALV	\$2.41	\$274.74	Ν
68	2077754	BOLT, MACHINE 5/8" X 10", GALV. FULL	\$1.04	\$70.72	N
40	2077753	BOLT, MACHINE 5/8" X 8", GALV.	\$1.05	\$42.00	N
2	2077780	BOLT, SPOOL, 5/8" X 10", GALV. SINGLE UP	\$4.16	\$8.32	N
44	2077755	BOLT,MACHINE,SQ HEAD,5/8"X12",ONE SQ NUT	\$1.16	\$51.04	N
4	2003686	BRACKET, FIBERGLASS STANDOFF VERTICAL24"	\$48.88	\$195.52	N
18	2077818	CLAMP, DEADEND ACSR OR AAC #2-4/0OR .30-	\$9.12	\$164.16	N
19	2003508	CLAMP, SUSPENSION AL ANGLE RANGE .50 TO	\$13.95	\$265.05	N
40	2077924	CLEVIS, STEEL LESS INSULATOR 5/8 IN PIN	\$9.38	\$375.20	N
315	2078012	CONDUCTOR, COPPERCLAD, 3 STR. #9, DSA 30	\$0.84	\$264.60	N
60	2077837	CONNECTOR, COMPRESSION H-BLOCK ACSR 2/0	\$0.66	\$39.60	N
63	2077930	CONNECTOR, VICE CU #4 STR	\$1.91	\$120.33	N
4	2077765	DOUBLE-ARMING, GALVANIZED 5/8 "X 12"	\$2.35	\$9.40	N
56	2003636	EXTENSION ROD, ANCHOR 1-1/4 X 72 6 FT	\$50.54	\$2,830.24	Ν
36	2077901	FIBERGLASS RIDGE-PIN	\$28.87	\$1,039.32	N
226	2077949	GRIP,GUY,FORMED WIRE DEADEND,3/8"EHS	\$2.27	\$513.02	N
37	2077862	GUARD, LINE #2 ACSR & AAAC STR 6/1, 7	\$1.95	\$72.15	N
114	2077951	HOOK, GUY	\$2.73	\$311.22	N
40	2077954	INSULATOR, PIN TYPE, 10KV, ANSI CLASS 55	\$3.75	\$150.00	N
2	2077952	INSULATOR, SPOOL, ANSI CLASS 53-3, TRANS	\$1.21	\$2.42	N
58	2077961	INSULATOR, STRAIN FIBERGLASS 36 IN 15,00	\$14.73	\$854.34	N
37	2077959	INSULATOR, SUSPENSION, POLYMER, 25KV, AP	\$11.86	\$438.82	N
56	2077979	MARKER, GUY WIRE PLASTIC 8' IN LENGTH CO	\$4.43	\$248.08	N
60	2002857	POLE, WOOD, 40FT CLASS 2, CCA TREATED	\$272.68	\$16,360.80	Υ
5	2002858	POLE, WOOD, 45 FT CLASS 2, CCA TREATED.	\$323.31	\$1,616.55	Υ
31	2077767	ROLLED BOLT, DOUBLE-ARMING, 5/8"X 16"	\$2.65	\$82.15	N
114	2077790	SCREW, LAG 1/2" X 4", GALV., TWIST DRIVE	\$0.47	\$53.58	N
71	2077812	SPACER, CABLED SECONDARY	\$6.79	\$482.09	N
21	2003612	TIE, PREFORMED SIDE TIE #2 ACSR OR #2 A	\$2.64	\$55.44	N
19	2003613	TIE, TOP, FORMED WIRE #2 ACSR OR #2 AAAC	\$2.87	\$54.53	N
114	2078002	WASHER, CURVED, MALLEABLE, 3" X 3"	\$1.22	\$139.08	N
221	2078006	WASHER, FLAT, GALVANIZED, 2" X 2" X 1/8"	\$0.24	\$53.04	N
217	2078014	WIRE, ALUMINUM, TIE, #4 BARE ANNEALED	\$0.11	\$23.87	N
4774	2005879	WIRE,GUY,EHS STEEL,GALV,3/8",15.4K RBS	\$0.33	\$1,575.42	N
		·	Total	\$31,648.68	



## **Estimate Summary**

Design Number 1

Distribution Services LDOH 2000 sq ft Secondary **Printed Date:** 3/10/2021

District: CSA

WR No. 925040

Date Sched: 4/1/21 Date Required: 4/1/21

Additional Information: Used for 2000 sq ft 3.5 TON AC design WR Description: LDOH 2000 sq ft SECONDARY

INSTALLATION:	Capital	Oper./Maint.	Total	
MATERIAL:	\$25,452.75	\$0.00	\$25,452.75	
OVERHEAD:	\$3,520.12	\$0.00	\$3,520.12	
	\$28,972.87	\$0.00	\$28,972.87	
LABOR HOURS:	397.97	0	397.97	
LABOR COST:	\$17,519.72	\$0.00	\$17,519.72	
OVERHEAD:	\$23,213.62	\$0.00	\$23,213.62	
	\$40,733.34	\$0.00	\$40,733.34	
VEHICLE:	\$0.00	\$0.00	\$0.00	
CONTRACTOR:	\$0.00	\$0.00	\$0.00	
ADDITIONAL ITEMS:	\$0.00	\$0.00	\$0.00	
SUBTOTAL:	\$69,706.21	\$0.00	\$69,706.21	
REMOVAL:				
MATERIAL:	\$0.00	\$0.00	\$0.00	
OVERHEAD:	\$0.00	\$0.00	\$0.00	
	\$0.00	\$0.00	\$0.00	
LABOR HOURS:	0	0	0	
LABOR COST:	\$0.00	\$0.00	\$0.00	
OVERHEAD:	\$0.00	\$0.00	\$0.00	
	\$0.00	\$0.00	\$0.00	
VEHICLE:	\$0.00	\$0.00	\$0.00	
CONTRACTOR:	\$0.00	\$0.00	\$0.00	
ADDITIONAL ITEMS:	\$0.00	\$0.00	\$0.00	
SUBTOTAL:	\$0.00	\$0.00	\$0.00	
TRANSFER:				
LABOR HOURS:	0	0	0	
LABOR COST:	\$0.00	\$0.00	\$0.00	
OVERHEAD:	\$0.00	\$0.00	\$0.00	
	\$0.00	\$0.00	\$0.00	
VEHICLE:	\$0.00	\$0.00	\$0.00	
CONTRACTOR:	\$0.00	\$0.00	\$0.00	
ADDITIONAL ITEMS:	\$0.00	\$0.00	\$0.00	
SUBTOTAL:	\$0.00	\$0.00	\$0.00	
TOTALS:	\$69,706.21	\$0.00	\$69,706.21	



# Work Request Material Summary \*\*\*Includes Truck Stock\*\*\*

Design Number 1

**Printed Date: 3/10/2021** Dist: CSA

WR No. 925040

			ı age	1 01 1	
Mate	rial Numbe	r Description	Unit Price	Total Cost	Asset?
INSTALL					
8	2003632	ANCHOR,SCRW GALV 10" WING 1-1/4" ROD 8"	\$48.15	\$385.20	N
34	2077739	BOLT, EYE, 5/8 IN. X 10 IN., GALVANIZED	\$3.12	\$106.08	N
24	2077764	BOLT, MACHINE 3/4" X 12", GALV	\$2.41	\$57.84	N
8	2077755	BOLT,MACHINE,SQ HEAD,5/8"X12",ONE SQ NUT	\$1.16	\$9.28	N
8400	2004339	CABLE, OVERHEAD SECONDARY, TRIPLEX, 4/0	\$1.72	\$14,448.00	Υ
1591	2004364	CABLE, SERVICE DROP AL 2-2/0 & 1-1/0 NEU	\$0.96	\$1,527.17	Υ
627	2004366	CABLE, SERVICE DROP AL 2-4/0 & 1-2/0 NEU	\$1.42	\$890.06	Υ
64	2077818	CLAMP, DEADEND ACSR OR AAC #2-4/0OR .30-	\$9.12	\$583.68	N
2242	2004331	CONDUCTOR, BARE OVERHEAD, 2 AWG, AAAC, 7	\$0.15	\$336.27	Υ
192	2077839	CONNECTOR, COMPRESSION H-BLOCK ACSR 1/0-	\$0.53	\$101.76	N
30	2077837	CONNECTOR, COMPRESSION H-BLOCK ACSR 2/0	\$0.66	\$19.80	N
30	2077931	CONNECTOR, VICE CU #2 STR	\$2.38	\$71.40	N
128	2003516	COVER, SNAP-ON SQUEEZON CONNECTOR D DIE	\$0.39	\$49.92	N
8	2003636	EXTENSION ROD, ANCHOR 1-1/4 X 72 6 FT	\$50.54	\$404.32	N
32	2077949	GRIP,GUY,FORMED WIRE DEADEND,3/8"EHS	\$2.27	\$72.64	N
24	2077951	HOOK, GUY	\$2.73	\$65.52	N
16	2077961	INSULATOR, STRAIN FIBERGLASS 36 IN 15,00	\$14.73	\$235.68	N
8	2077979	MARKER, GUY WIRE PLASTIC 8' IN LENGTH CO	\$4.43	\$35.44	N
46	2077783	NUT, EYE, STANDARD, 1-1/2" GALVANIZED FO	\$1.51	\$69.46	N
0	2002836	POLE, WOOD 30 FT CLASS 6 CCA TREATED NO	\$82.69	\$0.00	Υ
35	2002842	POLE, WOOD, 35 FT, CLASS 4, CCA TREATED.	\$141.93	\$4,967.55	Υ
35	2077767	ROLLED BOLT, DOUBLE-ARMING, 5/8"X 16"	\$2.65	\$92.75	N
24	2077790	SCREW, LAG 1/2" X 4", GALV., TWIST DRIVE	\$0.47	\$11.28	N
35	2077812	SPACER, CABLED SECONDARY	\$6.79	\$237.65	N
24	2078002	WASHER, CURVED, MALLEABLE, 3" X 3"	\$1.22	\$29.28	N
108	2078006	WASHER, FLAT, GALVANIZED, 2" X 2" X 1/8"	\$0.24	\$25.92	N
105	2078014	WIRE, ALUMINUM, TIE, #4 BARE ANNEALED	\$0.11	\$11.55	N
60	2004184	WIRE, COPPER, BARE, #4 SOFT DRAWN 7 STR	\$0.63	\$37.80	N
1726	2005879	WIRE,GUY,EHS STEEL,GALV,3/8",15.4K RBS	\$0.33	\$569.58	N
			Total	\$25,452.75	



## Estimate Summary Design Number 1

Distribution Services LDOH 2000 sq ft SERVICE

**Printed Date:** 3/10/2021

District: CSA

WR No. 926547

Date Sched: 4/1/21 Date Required: 4/1/21

Additional Information: Used for 2000 square foot design WR Description: LDOH 2000 sq ft SERVICE

INSTALLATION:	Capital	Oper./Maint.	Total
MATERIAL:	\$9,449.06	\$0.00	\$9,449.06
OVERHEAD:	\$1,306.80	\$0.00	\$1,306.80
	\$10,755.86	\$0.00	\$10,755.86
LABOR HOURS:	198.6	0	198.6
LABOR COST:	\$8,742.35	\$0.00	\$8,742.35
OVERHEAD:	\$11,583.63	\$0.00	\$11,583.63
	\$20,325.98	\$0.00	\$20,325.98
VEHICLE:	\$0.00	\$0.00	\$0.00
CONTRACTOR:	\$0.00	\$0.00	\$0.00
ADDITIONAL ITEMS:	\$0.00	\$0.00	\$0.00
SUBTOTAL:	\$31,081.84	\$0.00	\$31,081.84
REMOVAL:			
MATERIAL:	\$0.00	\$0.00	\$0.00
OVERHEAD:	\$0.00	\$0.00	\$0.00
	\$0.00	\$0.00	\$0.00
LABOR HOURS:	0	0	0
LABOR COST:	\$0.00	\$0.00	\$0.00
OVERHEAD:	\$0.00	\$0.00	\$0.00
	\$0.00	\$0.00	\$0.00
VEHICLE:	\$0.00	\$0.00	\$0.00
CONTRACTOR:	\$0.00	\$0.00	\$0.00
ADDITIONAL ITEMS:	\$0.00	\$0.00	\$0.00
SUBTOTAL:	\$0.00	\$0.00	\$0.00
TRANSFER:			
LABOR HOURS:	0	0	0
LABOR COST:	\$0.00	\$0.00	\$0.00
OVERHEAD:	\$0.00	\$0.00	\$0.00
	\$0.00	\$0.00	\$0.00
VEHICLE:	\$0.00	\$0.00	\$0.00
CONTRACTOR:	\$0.00	\$0.00	\$0.00
ADDITIONAL ITEMS:	\$0.00	\$0.00	\$0.00
SUBTOTAL:	\$0.00	\$0.00	\$0.00
TOTALS:	\$31,081.84	\$0.00	\$31,081.84



# Work Request Material Summary \*\*\*Includes Truck Stock\*\*\*

Design Number 1

**Printed Date: 3/10/2021** 

Dist: CSA WR No. 926547

			•		
Mat	erial Number	r Description	Unit Price	Total Cost	Asset?
INSTALL					
9828	2004364	CABLE, SERVICE DROP AL 2-2/0 & 1-1/0 NEU	\$0.96	\$9,434.88	Υ
0	2004366	CABLE, SERVICE DROP AL 2-4/0 & 1-2/0 NEU	\$1.42	\$0.00	Υ
2	2003770	CLAMP, MID SPAN ALUMINUM 1/4 IN - 1/2 IN	\$7.09	\$14.18	N
			Total	\$9,449.06	

### HIGH DENSITY MODEL 4/2021 (176 lots)

**Underground Costs (per lot)** 

	MATER	IAL	LABO	R	TOTA	L			
ITEM	COST	% CHANGE	COST	% CHANGE	COST	% CHANGE	EXPLANATION OF % CHANGE		
SERVICE	288.33	66.47%	260.66	46.99%	548.99	56.62% Underground material up, contractor rates up			
PRIMARY	138.27	29.97%	61.14	18.53%	199.41	26.23%	Underground material up, Cable labor re-evaluation caused labor increase		
SECONDARY	78.14	99.59%	70.32	26.07%	148.46	56.39%	Underground material up, Cable labor re-evaluation caused labor increase		
TRANSFORMERS	267.25	7.38%	68.77	11.21%	336.02	8.14%	Underground material up, TEC & Contractor overhead down		
TRENCHING									
PRIMARY & SECONDARY			175.02	-11.71%	175.02	-11.71%	Contractor rates down		
SERVICES			317.91	-7.46%	317.91	-7.46%	Contractor rates down		
SUB-TOTAL	771.99	36.00%	953.82	7.38%	1,725.81	18.54%			
STORES HANDLING	94.34	18.89%			94.34	18.89%	Higher material costs produces higher handling costs		
SUB-TOTAL	866.33	33.90%	953.82	7.38%	1,820.15	18.56%			
ENGINEERING			61.28	0.00%	61.28	0.00%			
TOTAL	866.33	33.90%	1,015.10	6.90%	1,881.43	17.84%			
					528.93		Value of the Life Cycle Operational Cost Including Storm and Lost Pole Attachment Revenue		
Total with NPV Factor					2,410.36				

Overhead Costs (per lot)

	MATE	RIAL	LABO	R	TOTA	<b>NL</b>					
ITEM	COST	% CHANGE	COST	% CHANGE	COST	% CHANGE	EXPLANATION OF % CHANGE				
SERVICE	142.24	70.76%	91.83	6.98%	234.07	38.39%	Material up, Labor up				
PRIMARY	12.88	19.59%	35.17	17.70%	48.05	18.20%	Material up, Labor up				
SECONDARY	64.40	10.81%	106.36	-1.55%	170.76	2.77%	Material up, Labor down				
INITIAL TREE TRIM			0.00		0.00						
POLES	113.97	8.83%	205.55	10.04%	319.52	9.61%	Material up, Labor up				
TRANSFORMERS	157.68	3.30%	70.27	11.95%	227.95	5.82%	Material up, Labor up				
SUB-TOTAL	491.17	19.93%	509.18	7.58%	1,000.35	13.31%					
STORES HANDLING	60.02	4.82%			60.02	4.82%	Higher material costs produces higher handling costs				
SUB-TOTAL	551.19	18.07%	509.18	7.58%	1,060.37	12.79%					
ENGINEERING			61.28	0.00%	61.28	0.00%					
TOTAL	551.19	18.07%	570.46	6.71%	1,121.65	12.01%					
	<u> </u>				1,387.02	1	Value of the Life Cycle Operational Cost Including Storm and Lost Pole Attachment Revenue				
Total with NPV Factor					2 508 67						

### Differential Costs (per lot)

	MATER	IAL	LABO	R	TOTAL		
ITEM	COST	% CHANGE	COST	% CHANGE	COST	% CHANGE	
Differential (per lot)	315.14	74.92%	444.64	7.15%	759.78	27.66%	
NPV amount					-858.09		
Differential (per lot)					-98.31	-85.66%	

Includes NPV of Operational Cost



### **UG Construction Cost Data Summary**

High Density (176-Lot) UG Subdivision Costs

	Α	В	С	D	E	F	G	Н	1	J	K	L	М	N
			(D+ M)		(F + L)	(G + H + I)		(G x J x TLF)	(G x K x CLF)				(D x MHR)	(C+E)
			Material and		Total Labor		Base	Operations Labor	Contract Labor	TEC	Contractor		Material	
Line :	# Work Type/WR #	Description	Handling	Material	Plus Vehicles	Total Labor	Labor	Overheads	Overheads	Work %	Work %	Vehicle	Handling	Total
1	Transformers													
2	##################### Insta		51,230.95	\$45,652.25	5,902.34	5,278.71	\$3,073.59	1,958.49	246.62	60%	40%	\$623.63	5,578.70	57,133.29
3	######################################		1,553.57	\$1,384.40	2,747.51	2,457.21	\$1,430.74	911.67	114.80	60%	40%	\$290.30	169.17	4,301.08
4	Contr Prep	pare Pad Site			3,453.17	3,453.17	\$ <u>2,876.20</u>		576.97	0%	100%			3,453.17
5			52,784.53	47,036.65	12,103.01	11,189.08	7,380.53	2,870.16	938.39			913.93	5,747.88	64,887.54
6	Primary													
7	925096 Prim	ary Line - OH-UG Takeoffs	683.67	\$609.22	710.03	635.01	\$369.74	235.60	29.67	60%	40%	\$75.02	74.45	1,393.69
8		und OH to UG Take-offs	155.36	\$138.44	317.36	283.82	\$165.26	105.30	13.26	60%	40%	\$33.53	16.92	472.71
9	925098 Prim	ary Conduit (Material Only)	9,381.68	\$8,360.08	-	-	-	-	-			-	1,021.60	9,381.68
10	925100 Prima	ary Cable	17,088.65	\$15,227.81	9,733.47	8,705.05	\$5,068.62	3,229.72	406.71	60%	40%	\$1,028.42	1,860.84	26,822.12
11			27,309.35	24,335.55	10,760.86	9,623.88	5,603.62	3,570.63	449.63			1,136.97	2,973.80	38,070.21
12	Secondary													
13	925103 Seco	ondary Cable	9,649.74	\$8,598.95	12,377.13	11,069.38	\$6,445.28	4,106.93	517.17	60%	40%	\$1,307.75	1,050.79	22,026.87
14	925104 Seco	ondary Conduit (Material Only)	5,783.11	\$5,153.37	-	-	-	-	-			-	629.74	5,783.11
15			15,432.85	13,752.32	12,377.13	11,069.38	6,445.28	4,106.93	517.17			1,307.75	1,680.53	27,809.98
16	Service													
17	925106 Serv	rice Cable	18,244.13	\$16,257.47	42,893.98	42,893.98	\$35,727.12	-	7,166.86	0%	100%	_	1,986.66	61,138.11
18	925108 Set N	Meters	17,751.95	\$15,818.88	2,981.50	2,666.48	\$1,552.59	989.31	124.58	60%	40%	\$315.02	1,933.07	20,733.45
19	925110 Serv	rice Conduit (Material Only)	20,950.73	\$18,669.34	· -	· -	_	_	_				2,281.39	20,950.73
20		37	56,946.81	50,745.69	45,875.48	45,560.46	37,279.71	989.31	7,291.44			315.02	6,201.12	102,822.29
21	Trenching			,-	,	,	,		.,				-,	,
22	Contractc Prima	ary Trenching	_		17,584.53	17,584.53	\$14,646.45		2,938.08	0%	100%	_	_	17,584.53
23		ondary Trenching	_		4,372.98	4,372.98	\$3,642.33		730.65	0%	100%	_	_	4,372.98
24	TEC Inspection	, ,	_		8,846.62	8,385.42	\$8,385.42		-	0%	0%	\$461.20	_	8,846.62
25	120 moposion				30,804.13	30,342.93	26,674.20		3.668.73	070	070	461.20		30,804.13
26					00,004.10	00,042.00	20,014.20		0,000.70			401.20		00,004.10
27	Contracts Svc	Trenching Pri. Prop	_		33.344.02	33,344.02	\$27,772.80	_	5,571.22	0%	100%	_	_	33,344.02
28		Trenching Rts-of-Wy		_	14,437.70	14,437.70	\$12,025.40		2,412.30	0%	100%			14,437.70
29	TEC Inspection	• ,		-	8,169.92	7,744.00	\$7,744.00		2,412.50	0%	0%	\$425.92	-	8,169.92
30	TEO INSPECTION	II IOI Service			55,951.64	55,525.72	47,542.20		7,983.52	070	070	425.92	<del></del>	55,951.64
31			-	-	55,951.04	55,525.72	47,542.20	-	7,903.52			425.92	-	55,951.64
32	Engineering Design	ign/Inspection/Coordination	_	_	10,785.62									10,785.62
33	Ligineening Desi	gramapectionacourumation			10,765.62									10,700.02
34	Totals (Sum of lines 5	5, 11, 15, 20, 25, 30, and 32)	152,473.55		178,657.87	163,311.45	130,925.54	11,537.03	20,848.89			4,560.79	16,603.34	331,131.42
35	Cost "Per Lot" (Line 34	4/ 176 lots)	866.33		1,015.10									1,881.43

Adjustment Factors			
TEC Labor Overhead Factor (excludes engineering)	TLF =	1.062	
Contractor Labor Overhead Factor	CLF =	0.2006	
Current year material handling charge rate	MHR =	0.1222	

### High Density - 176 lot - Contractor Labor - Underground Estimate

- 1. Update the contractor labor rates on this page. The numbers to be updated are highlighted in blue.
- 1a. Hover over the red comment symbol in the corner of the cell. That refers to the source of the information. The contractor labor rates come from the E.D. Field Construction Department - the Conduit Coordinators -Mike Capparelli, Steve Furry, Jerry Manning, Bill Baxter.

  2. Transfer the contractors costs to the HDdifferentialMonth-Year.xls file. The numbers are highlighted in yellow.
- 2a. Hover over the red comment symbol in the corner of the cell that refers to the destination of the contractor cost.
- 3. In 2006 TEC added pad site preparation cost, a contractor cost.

### Prepare pad site (Primary Contractor Labor Costs) Total Cost Pad sites \$2,876.20 \$143.81 20

		Primary Tren	ching & Con	duit (Prir	nary Contractor Labor Costs)
		Total	Cost	Feet	
		\$11,762.40	\$2.08	5655	Trenching Cost
		\$2,884.05	\$0.51	5655	Conduit Installation - 2"
		\$0.00	\$0.00	5655	Pull-tape Installation (used exact length for labor cost not 5% extra)
Primary Trenching	Total	\$14,646.45			
		Socondary T	ronohina 8 C	onduit (I	Primary Contractor Labor Costs)
					-Tilliary Contractor Labor Costs)
		<u>Total</u>	Cost	Feet	
		\$2,706.08	\$2.08	1301	Trenching Cost
		\$0.00	\$0.51	0	Conduit Installation - 2"
		\$149.05	\$0.55	271	Conduit Installation - 3"
		\$787.20	\$0.64	1230	Conduit Installation - 4"

Service Trenching & Conduit (Primary Contractor Labor Costs)

Total	Cost	Feet	
\$7,829.12	\$2.08	3764	Trenching feet required for 2" service conduit
\$0.00	\$2.08	0	Trenching feet required for 3" service conduit
\$4,196.28	\$0.51	8228	Conduit Installation - 2"
\$0.00	\$0.55	0	Conduit Installation - 3"
\$0.00	\$0.00	8228	Pull-tape Installation (used exact length not 5% extra)

Svc Trenching Rts-of-Wy Sub-total \$12,025.40

Secondary Trenching

### Service Trenching & Conduit on Private Property (Service Contractor Labor Costs)

 Total
 Cost
 Feet

 Sub-total
 \$27,772.80
 \$5.26
 5280
 Trenching feet and conduit = 30ft x 176

Service Cable (Service Contractor Labor Costs) Total
Sub-total \$35,727.12 \$2.34 Feet
15268 Installing 2/0 or 4/0 Cable in existing conduit Service Cable Labor Total \$75.525.32

\$0.00

Ineraction (TECO Labor Cost)

\$0.00

Total \$3,642.33

	inspection ( i	ECO Labor V	CUSL			
	TEC Labor	TEC Labor		<b>TEC Vehicle</b>	<b>TEC Vehicle</b>	
	Total	Rate	Feet/Qty	Rate	Total	Inspection costs for Primary Contractor (TECO Labor Cost)
	\$4,423.47	\$88.00	5655	\$4.84	\$243.29	Primary Inspection chg = (mach. trnch ft / 900 ft per day)*(8 hr/day)*Contractor rate
	\$1,017.67	\$88.00	1301	\$4.84	\$55.97	Secondary Inspection chg = (mach. trnch ft / 900 ft per day)*(8 hr/day)*Contractor rate
	\$2,944.28	\$88.00	3764	\$4.84	\$161.94	Service ROW Inspection chg = (machine trench ft / 900 ft per day)*(8 hr/day)*Contractor rate
Sub-total	\$8,385.42				\$461.20	
	TEC Labor	TEC Labor		<b>TEC Vehicle</b>	<b>TEC Vehicle</b>	

Total Inspection costs for Service Contractor (TECO Labor Cost)
\$425.92 Service Private Property Inspection = .5hr x # of lots x rate Total Rate Feet/Qty Rate \$7,744.00 Sub-total \$7,744.00 \$425.92 \$88.00 \$2.42 \$425.92

1501 Pull-tape Installation (used exact length not 5% extra)

### High Density - 176 Lots - Underground Material List

This worksheet lists the totals for major materials to be listed on the associated work request print as requested by the PSC.

- 750 Total Connected KVA
- 804 Total peak demand KVA
  - 0 25 kVA Transformers
- 20 37.5 kVA Transformers
- 0 50 kVA Transformers
- 0 75 kVA Transformers
- 5655 Trench Feet of 1/0 AL Primary Cable
  - 0 Existing trench feet of 1/0 AL Primary Cable
  - 0 Trench Feet of 2/0 AL Secondary Cable
  - 0 Existing trench feet of 2/0 AL Secondary Cable
- 1301 Trench Feet of 4/0 AL Secondary Cable
- 200 Existing trench feet of 4/0 AL Secondary Cable
  Trench Feet of 500 MCM AL Secondary Cable
  - 0 Existing trench feet of 500 MCM AL Secondary Cable
- 9044 Trench Feet of 2/0 AL Service Cable
- 4464 Existing trench feet of 2/0 AL Service Cable
  - 0 Trench Feet of 4/0 AL Service Cable
  - 0 Existing trench feet of 4/0 AL Service Cable
  - **0 Load Break Cabinet**

### Notes:

- 1. 1250 SF Homes
- 2. 2.5 Ton AC Units
- 3. 40' Service run from property corner to meter location
- 4. Voltage drop less than or equal to 12.0 volts
- 5. Voltage flicker less than or equal to 12.0 volts

### High Density - 176 Lots - Underground Material CU List

This worksheet summarizes the entries from the other worksheets (from PoleAveA through PoleOakHill) and provides the Contractor Labor worksheet with input totals to calculate contractor costs.

**Transformer Material CUs** 

Work Request	
Number	

925091	<u> </u>		
020001			
Qty CU	Definition	Total Con	nected KVA
0 pku51a3n	25 kva, 6 tap 250mcm	0	
0 pku51c3n	25 kva, 8 tap 250mcm	0	0
0 pku51a4n	37.5 kva, 6 tap 250mcm	0	0
0 pku51b4n	37.5 kva, 6 tap 500mcm	0	0
0 pku51c4n	37.5 kva, 8 tap 250mcm	0	0
20 pku51d4n	37.5 kva, 8 tap 500mcm	750	750
0 pku51a5n	50 kva, 6 tap 250mcm	0	750
0 pku51b5n	50 kva,6 tap 500mcm	0	750
0 pku51c5n	50 kva,8 tap 250mcm	0	750
0 pku51d5n	50 kva,8 tap 500mcm	0	750
0 pku51a6n	75 kva, 6 tap 250mcm	0	750
0 pku51b6n	75 kva, 6 tap 500mcm	0	750
0 pku51c6n	75 kva,8 tap 250mcm	0	750
0 pku51d6n	75 kva, 8 tap 500mcm	0	750
1 bushcover	Cover hot Tx bushing - at open position on	loop tx, or at ra	adial Tx
1 bushdummy	Parking bushing at normal open tx in loop		

### Work Request

Number 925095 **Ground Pad Mounted Tx - Material CUs** 

Qty CU Definition

20 grdmeg1/2 meggar ground, drive rods, 1 location, 1/2" rods

### Work Request

<u>Number</u> 925096 Primary Overhead - Material CUs

Qty CU
2 PKE601WF1B
2 FLOH103

Definition

TEC material & labor to frame terminal pole CO & LA Fuse

Work Request Number 925097

Meggar Ground at Terminal Pole

Qty CU Definition

2 grdmeg1/2 meggar ground, drive rods, 1 location, 1/2" rods

### Primary Trenching - Labor Only - Done By Contractors

Used to determine contractor labor cost on the Contractor Labor worksheet

Qty CU Definition

5655 Trenching feet required for 2" primary conduit

0 Existing trench feet used for 2" primary conduit

5655 Install Pulling Tape (blow in tape for pull - trench feet used to determine contractor cost)

### Work Request

<u>Number</u> 925100 Primary Cable

Qty CU	Definition	
2 pku16wf	pothead, 38' 1c 1/0AL cable, 20' pvc, ground conn, wood pole	76
40 pku11f	safebreak, 5' 1c 1/0AL cable, ground conn	200
0 pku31p3	switch cubicle(lbc) 1ph, 200a deadfront, 3 position w/pad, grnd	
0 pku31p4	switch cubicle(lbc) 1ph, 200a deadfront, 4 position w/pad, grnd	
0 fault1pa	fault indicator, 1ph 1/0-4/0 above grade, 400a	
5655 CA1/0CN1C	AL cable, 1/0AL concentric neutral 15kV includes labor - round up to	6524.1
0 win1f	labor to pull up cable in conduit	

60

### Work Request Number 925098 Primary Conduit - Material Only Material used by contractors to install the conduit system Qty CH Definition 20 5512000 Conduit, galvanized 2", 10' with coupling, for up terminal pole 5875 5522000 2" conduit 6095 5853530 Pulling tape - actual length 48 5512220 2" elbow 90 galv 9.5" radius 8 5512210 2" elbow 45 galv 9.5" radius 112 5522180 Coupling, 2" PVC (2 per elbow) 12 gluecondf 2"&3" pvc 1 qt for 500' fast dry Secondary Trenching - Labor Only - Done By Contractors Used to determine contractor labor cost on the Contractor Labor worksheet Qty Definition 0 Trenching feet required for 2" secondary conduit 0 Existing trench feet used for 2" secondary conduit 71 Trenching feet required for 3" secondary conduit 200 Existing trench feet used for 3" secondary conduit 1230 Trenching feet required for 4" secondary conduit 0 Existing trench feet used for 4" secondary conduit 1501 Install Pulling Tape (blow in tape for pull - trench feet used to determine contractor cost) Work Request Number Secondary Cable & Hand Holes CU Definition Qty 0 wiu3sb 2c 2/0 1c 1 neutral, 600 v - added 5% here 1691 CA4/0INS3CAI 2c 4/0 1c 2/0 neutral, 600v includes labor - added 5% h€ 2029.2 2c 500 1c 350 neutral, 600v - added 5% here 0 wiu3sn 0 insbus350/4 crab 4 position up to 350mcm 0 insbus350/6 crab 6 position up to 350mcm 0 insbus500/4 crab 4 position up to 500mcm crab 6 position up to 500mcm 66 insbus500/6 0 insbus500/8 crab 8 position up to 500mcm labor to pull ug cable in conduit 0 wiu1f 22 syhottx energize ug secondary in transformer 22 svhothh energize ug secondary in hand hole 0 hhsec secondary h/h 12"x20", 3 or 4 2/0 or 4/0 svc w/ 2/0 or 4/0 sec 22 HH LARGE PE secondary h/h 14"x18" large pedestal, 5 to 7 2/0 or 4/0 svc w/ 4/0 or 500 sec (any time 500 u Work Request Secondary Conduit - Material Only Number 925104 Material used by contractors to install the conduit system CU Definition Qty 0 5522000 2" conduit sched A bell end 291 5523000 3" conduit sched A bell end 1410 5524000 4" conduit sched A bell end 1901 5853530 Pulling tape, plus adding 5% extra here 0 5522220 2" elbow 90 PVC 9.5" radius 0 5522210 2" elbow 45 PVC 9.5" radius 8 5523220 3" elbow 90 PVC 13" radius 3" elbow 45 PVC 13" radius 0 5523210 4" elbow 90 PVC 16" radius 36 5524220 0 5514300 4" elbow 90 galv 30" radius 0 5514210 4" elbow 45 galv 16" radius 0 5522180 Coupling, 2" PVC (2 per elbow)

Coupling, 3" PVC (2 per elbow)

Coupling, 4" PVC (2 per elbow) 2"&3" pvc 1 qt for 500' fast dry

4"& 6" pvc 1 qt for 250' medium dry

16 5523180

72 5524180

1 gluecondf

6 gluecondm

	Work Request	•
	925108	Set Meter
Qty	CU	Definition
	meterlabor 1900006	meter, kwh 30a 240v
		hing - Labor Only - Done By Contractors
Qty	Used to detern	nine contractor labor cost on the Contractor Labor worksheet  Definition
-	Number of 2/0	
		for 2" service conduit on private property-service contractor
		for 10' stub of 2" service conduit installed by primary contractor for 2" service conduit installed by primary contractor
		reet used for 2" service conduit installed by primary contractor
		Γape for 2" conduit (blow in tape for pull - Primary Contractor)
		for 3" service conduit on private property-service contractor for 10' stub of 3" service conduit installed by primary contractor
		for 3" service conduit installed by primary contractor
0	Existing trench	feet used for 3" service conduit installed by primary contractor
0	Install Pulling	Tape for 3" conduit (blow in tape for pull - Primary Contractor)
13508		
1760 15268	Work Request Number	
13200	925106	Service Cable Material Only  Material used by contractors to install the conduit system
		,
Qty		
	CU wiu3sh	Definition 2c 2/0 & 1c 1 neutral, 600 v service cable 16031.4
15268	wiu3sb wiu3sc Work Request	2c 2/0 & 1c 1 neutral, 600 v service cable 16031.4 2c 4/0 & 1c 2/0 neutral, 600 v service cable 0
15268 0	wiu3sb wiu3sc	2c 2/0 & 1c 1 neutral, 600 v service cable 16031.4 2c 4/0 & 1c 2/0 neutral, 600 v service cable 0
15268 0 15268 Qty	wiu3sb wiu3sc Work Request Number 925110	2c 2/0 & 1c 1 neutral, 600 v service cable 16031.4 2c 4/0 & 1c 2/0 neutral, 600 v service cable 0  Service Conduit Material Only Material used by contractors to install the conduit system  Definition
15268 0 15268 <b>Qty</b> 5280	wiu3sb wiu3sc  Work Request Number 925110  CU Conduit for 2":	2c 2/0 & 1c 1 neutral, 600 v service cable 16031.4 2c 4/0 & 1c 2/0 neutral, 600 v service cable 0  Service Conduit Material Only Material used by contractors to install the conduit system  Definition service on private property-service contractor
15268 0 15268 <b>Qty</b> 5280 3520	wiu3sb wiu3sc  Work Request Number 925110  CU Conduit for 10	2c 2/0 & 1c 1 neutral, 600 v service cable 16031.4 2c 4/0 & 1c 2/0 neutral, 600 v service cable 0  t  Service Conduit Material Only Material used by contractors to install the conduit system  Definition service on private property-service contractor 's stub of 2" service installed by primary contractor
15268 0 15268 <b>Qty</b> 5280 3520 6468 11748	wiu3sb wiu3sc  Work Request Number 925110  CU Conduit for 2": Conduit for 10 Conduit for 2": Pulling Tape in	2c 2/0 & 1c 1 neutral, 600 v service cable 16031.4 2c 4/0 & 1c 2/0 neutral, 600 v service cable 0  Service Conduit Material Only Material used by contractors to install the conduit system  Definition service on private property-service contractor 's stub of 2" service installed by primary contractor service installed by primary contractor nstalled in 2" conduit by Primary Contractor)
15268 0 15268 <b>Qty</b> 5280 3520 6468 11748 15268	wiu3sb wiu3sc  Work Request Number 925110  CU Conduit for 2": Conduit for 2": Pulling Tape in	2c 2/0 & 1c 1 neutral, 600 v service cable 16031.4 2c 4/0 & 1c 2/0 neutral, 600 v service cable 0  Service Conduit Material Only Material used by contractors to install the conduit system  Definition service on private property-service contractor 's tub of 2" service installed by primary contractor service installed by primary contractor nstalled in 2" conduit by Primary Contractor) Total 2" conduit for work order quantity
15268 0 15268 <b>Qty</b> 5280 3520 6468 11748 15268 448	wiu3sb wiu3sc  Work Request Number 925110  CU Conduit for 10 Conduit for 2": Conduit for 2": Pulling Tape is 5522200 5522220	2c 2/0 & 1c 1 neutral, 600 v service cable 16031.4 2c 4/0 & 1c 2/0 neutral, 600 v service cable 0  t  Service Conduit Material Only Material used by contractors to install the conduit system  Definition service on private property-service contractor 's stub of 2" service installed by primary contractor service installed by primary contractor neutralled in 2" conduit by Primary Contractor) Total 2" conduit for work order quantity 2" elbow 90 PVC 9.5" radius
15268 0 15268 15268 5280 3520 6468 11748 15268 448 0	wiu3sb wiu3sc  Work Request Number 925110  CU Conduit for 2": Conduit for 2": Pulling Tape in	2c 2/0 & 1c 1 neutral, 600 v service cable 2c 4/0 & 1c 2/0 neutral, 600 v service cable 0  Service Conduit Material Only Material used by contractors to install the conduit system  Definition service on private property-service contractor ' stub of 2" service installed by primary contractor service installed by primary contractor nstalled in 2" conduit by Primary Contractor) Total 2" conduit for work order quantity 2" elbow 90 PVC 9.5" radius 2" elbow 45 PVC 9.5" radius 2" galvanized Lock Nut
15268 0 15268 2ty 5280 3520 6468 11748 15268 448 0 176 176	wiu3sb wiu3sc  Work Request Number 925110  CU  Conduit for 2": Conduit for 10 Conduit for 2": Pulling Tape in 5522000 5522220 5522220 5512260 5522030	2c 2/0 & 1c 1 neutral, 600 v service cable 16031.4 2c 4/0 & 1c 2/0 neutral, 600 v service cable 0  Service Conduit Material Only Material used by contractors to install the conduit system  Definition service on private property-service contractor 's tub of 2" service installed by primary contractor service installed by primary contractor installed in 2" conduit by Primary Contractor Total 2" conduit for work order quantity 2" elbow 90 PVC 9.5" radius 2" galvanized Lock Nut 2" Flexible PVC conduit
15268 0 15268 15268 5280 3520 6468 11748 15268 448 0 176 176 176	wiu3sb wiu3sc  Work Request Number 925110  CU Conduit for 2": Conduit for 10 Conduit for 2 ape is 5522000 5522220 5522220 5522210 5512260 5522030 5522050	2c 2/0 & 1c 1 neutral, 600 v service cable 2c 4/0 & 1c 2/0 neutral, 600 v service cable 0  Service Conduit Material Only Material used by contractors to install the conduit system  Definition service on private property-service contractor 's tub of 2" service installed by primary contractor service installed by primary contractor neutralled in 2" conduit by Primary Contractor Total 2" conduit for work order quantity 2" elbow 90 PVC 9.5" radius 2" elbow 45 PVC 9.5" radius 2" glavanized Lock Nut 2" Flexible PVC conduit 2" PVC Adapter, male thread/female slip
15268 0 15268 2ty 5280 3520 6468 11748 15268 448 0 176 176 176	wiu3sb wiu3sc  Work Request Number 925110  CU  Conduit for 2": Conduit for 10 Conduit for 2": Pulling Tape in 5522000 5522220 5522220 5512260 5522030	2c 2/0 & 1c 1 neutral, 600 v service cable 16031.4 2c 4/0 & 1c 2/0 neutral, 600 v service cable 0  Service Conduit Material Only Material used by contractors to install the conduit system  Definition service on private property-service contractor 's tub of 2" service installed by primary contractor service installed by primary contractor installed in 2" conduit by Primary Contractor Total 2" conduit for work order quantity 2" elbow 90 PVC 9.5" radius 2" galvanized Lock Nut 2" Flexible PVC conduit
15268 0 15268 0 15268 5280 3520 1766 1766 1766 1766 176 176 176 176 176	wiu3sb wiu3sc  Work Request Number 925110  CU Conduit for 2": Conduit for 10 Conduit for 2": 5522000 5522210 5512260 5522230 5522230 5522030 5522150 Conduit for 3":	2c 2/0 & 1c 1 neutral, 600 v service cable 2c 4/0 & 1c 2/0 neutral, 600 v service cable 0  Service Conduit Material Only Material used by contractors to install the conduit system  Definition service on private property-service contractor 's tub of 2" service installed by primary contractor service installed by primary contractor service installed by primary Contractor) Total 2" conduit for work order quantity 2" elbow 90 PVC 9.5" radius 2" elbow 45 PVC 9.5" radius 2" galvanized Lock Nut 2" Flexible PVC conduit 2" PVC Adapter, male thread/female slip 2" PVC Service Riser Coupling, 2" PVC (2 per elbow) service on private property-service contractor
15268 0 15268 0 15268 0 15280 3520 6468 448 0 176 176 176 176 896 0 0	wiu3sb wiu3sc  Work Request Number 925110  CU Conduit for 10 Conduit for 10 Conduit for 2": 5522000 5522220 5522220 5522220 5522230 5522230 5522230 5522280 Conduit for 3": Conduit for 10	2c 2/0 & 1c 1 neutral, 600 v service cable 2c 4/0 & 1c 2/0 neutral, 600 v service cable 0  Service Conduit Material Only Material used by contractors to install the conduit system  Definition service on private property-service contractor 's stub of 2" service installed by primary contractor service installed by primary contractor service installed by primary Contractor stalled in 2" conduit by Primary Contractor) Total 2" conduit for work order quantity 2" elbow 90 PVC 9.5" radius 2" elbow 45 PVC 9.5" radius 2" glavanized Lock Nut 2" Flexible PVC conduit 2" PVC Adapter, male thread/female slip 2" PVC Service Riser Coupling, 2" PVC (2 per elbow) service on private property-service contractor 's stub of 3" service installed by primary contractor
15268 0 15268 0 15268 15280 3520 6468 11748 15268 448 0 176 176 176 176 896 0 0	wiu3sb wiu3sc  Work Request Number 925110  CU Conduit for 10 Conduit for 2": Pulling Tape in 5522200 5522220 5522210 5512260 5522230 5522210 5512260 5522030 Conduit for 10 Conduit for 3": Conduit for 3":	2c 2/0 & 1c 1 neutral, 600 v service cable 2c 4/0 & 1c 2/0 neutral, 600 v service cable 0  Service Conduit Material Only Material used by contractors to install the conduit system  Definition service on private property-service contractor 's tub of 2" service installed by primary contractor service installed by primary contractor service installed by primary Contractor) Total 2" conduit for work order quantity 2" elbow 90 PVC 9.5" radius 2" elbow 45 PVC 9.5" radius 2" galvanized Lock Nut 2" Flexible PVC conduit 2" PVC Adapter, male thread/female slip 2" PVC Service Riser Coupling, 2" PVC (2 per elbow) service on private property-service contractor
15268 0 115268 0 115268 0 15280 3520 6468 11748 0 1766 1766 176 176 176 176 0 0 0 0 0	wiu3sb wiu3sc  Work Request Number 925110  CU Conduit for 10 Conduit for 2": Conduit for 2": Folian Tape in S522200 S522210 S522210 S522210 S522210 S522210 C5522230 S522210 C5522300 Conduit for 3": Fulling Tape in S523000	2c 2/0 & 1c 1 neutral, 600 v service cable 2c 4/0 & 1c 2/0 neutral, 600 v service cable 0  Service Conduit Material Only Material used by contractors to install the conduit system  Definition service on private property-service contractor 's tub of 2" service installed by primary contractor service installed by primary contractor service installed by primary Contractor) Total 2" conduit for work order quantity 2" elbow 90 PVC 9.5" radius 2" elbow 45 PVC 9.5" radius 2" galvanized Lock Nut 2" Flexible PVC conduit 2" PVC Adapter, male thread/female slip 2" PVC Service Riser Coupling, 2" PVC (2 per elbow) service on private property-service contractor 's tub of 3" service installed by primary contractor
15268 0 15268 0 15268 0 15280 3520 3520 448 0 176 176 176 176 896 0 0 0 0 0	wiu3sb wiu3sc  Work Request Number 925110  CU Conduit for 2": Conduit for 2": Fulling Tape in 5522200 5522220 5522220 5522220 5522210 5512260 5522230 55222180 Conduit for 10 Conduit for 3": Conduit for 3": Pulling Tape in 5523000 5523220	2c 2/0 & 1c 1 neutral, 600 v service cable 2c 4/0 & 1c 2/0 neutral, 600 v service cable 0  Service Conduit Material Only Material used by contractors to install the conduit system  Definition service on private property-service contractor 's tub of 2" service installed by primary contractor service installed by primary contractor service installed by primary Contractor)  Total 2" conduit for work order quantity 2" elbow 90 PVC 9.5" radius 2" elbow 45 PVC 9.5" radius 2" galvanized Lock Nut 2" Flexible PVC conduit 2" PVC Adapter, male thread/female slip 2" PVC Service Riser Coupling, 2" PVC (2 per elbow) service on private property-service contractor 's tub of 3" service installed by primary contractor service installed by primary contractor service installed by Primary Contractor Total 3" conduit for work order quantity 3" elbow 90 PVC 13" radius
15268 0 0 15268 0 15268 0 15280 3520 6468 448 0 1766 176 176 176 176 0 0 0 0 0	wiu3sb wiu3sc  Work Request Number 925110  CU Conduit for 2": Conduit for 10 Conduit for 2": Fulling Tape in 5522000 5522220 5522220 5522230 5522230 5522280 Conduit for 3": Conduit for 10 Conduit for 3": Conduit for 3": Pulling Tape in 5523200 5523220 5523210	2c 2/0 & 1c 1 neutral, 600 v service cable 2c 4/0 & 1c 2/0 neutral, 600 v service cable 0  Service Conduit Material Only Material used by contractors to install the conduit system  Definition service on private property-service contractor 's tub of 2" service installed by primary contractor service installed by primary contractor service installed by primary Contractor) Total 2" conduit for work order quantity 2" elbow 90 PVC 9.5" radius 2" elbow 45 PVC 9.5" radius 2" galvanized Lock Nut 2" Flexible PVC conduit 2" PVC Adapter, male thread/female slip 2" PVC Service Riser Coupling, 2" PVC (2 per elbow) service on private property-service contractor 's tub of 3" service installed by primary contractor
15268 0 15268 0 15280 3520 6468 11748 448 0 1766 1766 176 176 996 0 0 0 0 0 0	wiu3sb wiu3sc  Work Request Number 925110  CU  Conduit for 2": Conduit for 2": Pulling Tape is 552200 5522210 5512260 5522230 5522280 Conduit for 3": Conduit for 3": Pulling Tape is 5523000 5523220 5523210 5523220 5523220	2c 2/0 & 1c 1 neutral, 600 v service cable 2c 4/0 & 1c 2/0 neutral, 600 v service cable 0  Service Conduit Material Only Material used by contractors to install the conduit system  Definition service on private property-service contractor 's stub of 2" service installed by primary contractor service installed by primary contractor service installed by Primary Contractor  Total 2" conduit for work order quantity 2" elbow 90 PVC 9.5" radius 2" galvanized Lock Nut 2" Flexible PVC conduit 2" PVC Adapter, male thread/female slip 2" PVC Service Riser Coupling, 2" PVC (2 per elbow) service on private property-service contractor 's sub of 3" service installed by primary contractor service installed by primary contractor service installed by primary contractor  Total 3" conduit for work order quantity 3" elbow 90 PVC 13" radius 3" elbow 45 PVC 13" radius at house riser 3" elbow 90 PVC 13" radius at house riser
15268 0 15268 0 15280 3520 3520 1768 1768 1768 1768 1768 1768 1768 1768	wiu3sb wiu3sc  Work Request Number 925110  CU  Conduit for 2": Conduit for 10 Conduit for 2": 5522000 5522220 5522210 5512260 5522230 Conduit for 3": Conduit for 3": Pulling Tape in 5523000 5523220 5523210 5523220 5523220 5523220 5523220 5523220 5523220 5512670	2c 2/0 & 1c 1 neutral, 600 v service cable 2c 4/0 & 1c 2/0 neutral, 600 v service cable 0  Service Conduit Material Only Material used by contractors to install the conduit system  Definition service on private property-service contractor 's tub of 2" service installed by primary contractor service installed by primary contractor service installed by primary contractor) Total 2" conduit for work order quantity 2" elbow 90 PVC 9.5" radius 2" galvanized Lock Nut 2" Flexible PVC conduit 2" PVC Adapter, male thread/female slip 2" PVC Service Riser Coupling, 2" PVC (2 per elbow) service on private property-service contractor 's tub of 3" service installed by primary contractor Total 3" conduit for work order quantity 3" elbow 90 PVC 13" radius 3" elbow 45 PVC 13" radius 3" elbow 90 PVC 13" radius at house riser 3" elbow 90 PVC 13" radius at house riser 2-1/2" galvanized Lock Nut Used by contractors to install conduit system
15268 0 15268 0 15268 25280 3520 6468 448 0 176 176 176 176 896 0 0 0 0 0 0 0 0 0 0	wiu3sb wiu3sc  Work Request Number 925110  CU Conduit for 2": Conduit for 2": Conduit for 2": Fulling Tape in 5522000 5522220 5522210 5512260 5512270 5522180 Conduit for 10 Conduit for 3": Conduit for 3": Conduit for 3": Pulling Tape in 5523000 5523220 5523210 5523210 5512770 5523220 5512670 5523030	2c 2/0 & 1c 1 neutral, 600 v service cable 2c 4/0 & 1c 2/0 neutral, 600 v service cable 0  Service Conduit Material Only Material used by contractors to install the conduit system  Definition service on private property-service contractor 's tub of 2" service installed by primary contractor service installed by primary contractor netalled in 2" conduit by Primary Contractor  Total 2" conduit for work order quantity 2" elbow 90 PVC 9.5" radius 2" elbow 45 PVC 9.5" radius 2" elbow 45 PVC onduit 2" Flexible PVC conduit 2" PVC Adapter, male thread/female slip 2" PVC Service Riser Coupling, 2" PVC (2 per elbow) service on private property-service contractor 's tub of 3" service installed by primary contractor service installed by primary contractor service installed by primary contractor Total 3" conduit for work order quantity 3" elbow 90 PVC 13" radius 2-1/2" galvanized Lock Nut Used by contractors to install conduit system 3" Flexible PVC conduit
15268 0 115268 0 115268 0 15280 3520 6468 448 0 1766 1766 1766 1766 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0	wiu3sb wiu3sc  Work Request Number 925110  CU  Conduit for 2": Conduit for 10 Conduit for 2": 5522000 5522220 5522210 5512260 5522230 Conduit for 3": Conduit for 3": Pulling Tape in 5523000 5523220 5523210 5523220 5523220 5523220 5523220 5523220 5523220 5512670	2c 2/0 & 1c 1 neutral, 600 v service cable 2c 4/0 & 1c 2/0 neutral, 600 v service cable 0  Service Conduit Material Only Material used by contractors to install the conduit system  Definition service on private property-service contractor 's tub of 2" service installed by primary contractor service installed by primary contractor service installed by primary contractor) Total 2" conduit for work order quantity 2" elbow 90 PVC 9.5" radius 2" galvanized Lock Nut 2" Flexible PVC conduit 2" PVC Adapter, male thread/female slip 2" PVC Service Riser Coupling, 2" PVC (2 per elbow) service on private property-service contractor 's tub of 3" service installed by primary contractor Total 3" conduit for work order quantity 3" elbow 90 PVC 13" radius 3" elbow 45 PVC 13" radius 3" elbow 90 PVC 13" radius at house riser 3" elbow 90 PVC 13" radius at house riser 2-1/2" galvanized Lock Nut Used by contractors to install conduit system
15268 0 15268 0 15268 5280 3520 6468 11748 15268 448 0 1766 1766 176 176 896 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0	wiu3sb wiu3sc  Work Request Number 925110  CU Conduit for 2": Conduit for 10 Conduit for 2": Pulling Tape in 5522200 5522210 5512260 5512270 5522180 Conduit for 10 Conduit for 3": Conduit for 3": Pulling Tape in 5523200 5523210 5512370 5523210 5512370 5523220 5523210 5512670 55233200 5512670 55233300 5521000	2c 2/0 & 1c 1 neutral, 600 v service cable 2c 4/0 & 1c 2/0 neutral, 600 v service cable 0  Service Conduit Material Only Material used by contractors to install the conduit system  Definition service on private property-service contractor 's tub of 2" service installed by primary contractor service installed by primary contractor service installed by Primary Contractor nutatalled in 2" conduit by Primary Contractor  Total 2" conduit for work order quantity 2" elbow 90 PVC 9.5" radius 2" elbow 45 PVC 9.5" radius 2" galvanized Lock Nut 2" Flexible PVC conduit 2" PVC Adapter, male thread/female slip 2" PVC Service Riser Coupling, 2" PVC (2 per elbow) service on private property-service contractor 's tub of 3" service installed by primary contractor service installed by primary contractor nutation in 3" conduit by Primary Contractor)  Total 3" conduit for work order quantity 3" elbow 90 PVC 13" radius 2-1/2" house riser 3" elbow 90 PVC 13" radius at house riser 2-1/2" galvanized Lock Nut Used by contractors to install conduit system 3" Flexible PVC conduit 2-1/2"PVC Adapter, male thread/female slip



## Estimate Summary Design Number 1

**Contact Name:** Tampa Electric

Distribution Services HDUG Transformers

**Printed Date: 3/11/2021** 

District: CSA

WR No. 925091

Date Sched: 4/1/21 Date Required: 4/1/21

Additional Information: Full PSC Filing 10/2010

WR Description: HDUG 1250 sq ft TRANSFORMERS

<u>'</u>	<u> </u>			
INSTALLATION:	Capital	Oper./Maint.	Total	
MATERIAL:	\$45,652.25	\$0.00	\$45,652.25	
OVERHEAD:	\$6,313.70	\$0.00	\$6,313.70	
	\$51,965.95	\$0.00	\$51,965.95	
LABOR HOURS:	69.84	0	69.84	
LABOR COST:	\$3,073.59	\$0.00	\$3,073.59	
OVERHEAD:	\$4,072.50	\$0.00	\$4,072.50	
	\$7,146.09	\$0.00	\$7,146.09	
VEHICLE:	\$0.00	\$0.00	\$0.00	
CONTRACTOR:	\$0.00	\$0.00	\$0.00	
ADDITIONAL ITEMS:	\$0.00	\$0.00	\$0.00	
SUBTOTAL:	\$59,112.04	\$0.00	\$59,112.04	
REMOVAL:				
MATERIAL:	\$0.00	\$0.00	\$0.00	
OVERHEAD:	\$0.00	\$0.00	\$0.00	
	\$0.00	\$0.00	\$0.00	
LABOR HOURS:	0	0	0	
LABOR COST:	\$0.00	\$0.00	\$0.00	
OVERHEAD:	\$0.00	\$0.00	\$0.00	
	\$0.00	\$0.00	\$0.00	
VEHICLE:	\$0.00	\$0.00	\$0.00	
CONTRACTOR:	\$0.00	\$0.00	\$0.00	
ADDITIONAL ITEMS:	\$0.00	\$0.00	\$0.00	
SUBTOTAL:	\$0.00	\$0.00	\$0.00	
TRANSFER:				
LABOR HOURS:	0	0	0	
LABOR COST:	\$0.00	\$0.00	\$0.00	
OVERHEAD:	\$0.00	\$0.00	\$0.00	
	\$0.00	\$0.00	\$0.00	
VEHICLE:	\$0.00	\$0.00	\$0.00	
CONTRACTOR:	\$0.00	\$0.00	\$0.00	
ADDITIONAL ITEMS:	\$0.00	\$0.00	\$0.00	
SUBTOTAL:	\$0.00	\$0.00	\$0.00	
TOTALS:	\$59,112.04	\$0.00	\$59,112.04	



# Work Request Material Summary \*\*\*Includes Truck Stock\*\*\*

Design Number 1

**Printed Date: 3/11/2021** Dist: CSA

WR No. 925091

			9			
Mat	erial Numbe	er Description	Unit Price	Total Cost	Asset?	
INSTALL						
1	2004816	BUSHING, PARKING, 15KV, INSULATED	\$38.70	\$38.70	N	
20	2077906	CLAMP, GROUND ROD, F/U/W 1/2"ROD	\$1.80	\$36.00	N	
40	2078000	CLAMP,GND,TRANSFORMER,#10 SOL-#1 STR CU	\$2.31	\$92.40	N	
2	2077931	CONNECTOR, VICE CU #2 STR	\$2.38	\$4.76	N	
1	2004817	COVER, BUSHING 15 KV PDMT EQUIP W/FLEXIB	\$25.11	\$25.11	N	
20	2001315	PAD, CONCRETE 40" X 45" X 4" 25- 50KVA T	\$103.25	\$2,065.00	N	
20	2007395	PADLOCK, RED BRASS BODY 1/4" BRASS SHACK	\$22.97	\$459.40	N	
20	2007489	REPELLENT, FIRE ANT GRANULE 4 OZ BIFENTH	\$2.77	\$55.40	N	
40	2004031	STUD, GALVANIZED, 11 THREAD PER INCH ALL	\$2.47	\$98.80	N	
9	2004948	TERMINAL, SLIP FIT ALUMINUM STUD TYPE, 6	\$7.54	\$67.86	N	
6	2004954	TERMINAL, SLIP FIT ALUMINUM STUD TYPE, 6	\$16.58	\$99.48	N	
45	2004950	TERMINAL, SLIP FIT ALUMINUM STUD TYPE, 8	\$8.28	\$372.60	N	
20	2001519	TX,PM,LP,1P,37.5 kVA,240/120,FR3,SS	\$2,108.00	\$42,160.00	Υ	
120	2004184	WIRE, COPPER, BARE, #4 SOFT DRAWN 7 STR	\$0.63	\$75.60	N	
3	2078011	WIRE, COPPER, TIE, #6 SOLID SOFT DRAWN	\$0.38	\$1.14	N	
			Total	\$45,652.25		



## Estimate Summary Design Number 1

Distribution Services HDUG GRD Transformers

**Printed Date: 3/11/2021** 

District: CSA

WR No. 925095

Date Sched: 4/1/21 Date Required: 4/1/21

Additional Information: Full PSC Filing 10/2010

WR Description: HDUG 1250 sq ft GROUND TRANSFORMERS

INSTALLATION:	Capital	Oper./Maint.	Total	
MATERIAL:	\$1,384.40	\$0.00	\$1,384.40	
OVERHEAD:	\$191.46	\$0.00	\$191.46	
	\$1,575.86	\$0.00	\$1,575.86	
LABOR HOURS:	32.5	0	32.5	
LABOR COST:	\$1,430.74	\$0.00	\$1,430.74	
OVERHEAD:	\$1,895.73	\$0.00	\$1,895.73	
	\$3,326.47	\$0.00	\$3,326.47	
VEHICLE:	\$0.00	\$0.00	\$0.00	
CONTRACTOR:	\$0.00	\$0.00	\$0.00	
ADDITIONAL ITEMS:	\$0.00	\$0.00	\$0.00	
SUBTOTAL:	\$4,902.33	\$0.00	\$4,902.33	
REMOVAL:				
MATERIAL:	\$0.00	\$0.00	\$0.00	
OVERHEAD:	\$0.00	\$0.00	\$0.00	
	\$0.00	\$0.00	\$0.00	
LABOR HOURS:	0	0	0	
LABOR COST:	\$0.00	\$0.00	\$0.00	
OVERHEAD:	\$0.00	\$0.00	\$0.00	
	\$0.00	\$0.00	\$0.00	
VEHICLE:	\$0.00	\$0.00	\$0.00	
CONTRACTOR:	\$0.00	\$0.00	\$0.00	
ADDITIONAL ITEMS:	\$0.00	\$0.00	\$0.00	
SUBTOTAL:	\$0.00	\$0.00	\$0.00	
TRANSFER:				
LABOR HOURS:	0	0	0	
LABOR COST:	\$0.00	\$0.00	\$0.00	
OVERHEAD:	\$0.00	\$0.00	\$0.00	
	\$0.00	\$0.00	\$0.00	
VEHICLE:	\$0.00	\$0.00	\$0.00	
CONTRACTOR:	\$0.00	\$0.00	\$0.00	
ADDITIONAL ITEMS:	\$0.00	\$0.00	\$0.00	
SUBTOTAL:	\$0.00	\$0.00	\$0.00	
TOTALS:	\$4,902.33	\$0.00	\$4,902.33	



# Work Request Material Summary \*\*\*Includes Truck Stock\*\*\*

Design Number 1

**Printed Date: 3/11/2021** Dist: CSA

WR No. 925095

				9•	. •	
	Material Number	Description	Unit Price	Total Cost	Asset?	
INSTALI	L					
	60	2077939	COUPLER, GROUND ROD, F/U/W 1/2"ROD	\$4.78	\$286.80	N
	80	2077980	ROD,GROUND,CU BONDED,1/2"X10',THREADLESS	\$13.72	\$1,097.60	N
				Total	\$1,384.40	



## Estimate Summary Design Number 1

Distribution Services HDUG FRAME OH Takeoff

**Printed Date:** 3/11/2021

District: CSA

WR No. 925096

Date Sched: 4/1/21 Date Required: 4/1/21

Additional Information: Full PSC Filing 10/2010 WR Description: HDUG 1250 sq ft TAKEOFFS

INSTALLATION:	Capital	Oper./Maint.	Total
MATERIAL:	\$609.22	\$0.00	\$609.22
OVERHEAD:	\$84.24	\$0.00	\$84.24
	\$693.46	\$0.00	\$693.46
LABOR HOURS:	8.4	0	8.4
LABOR COST:	\$369.74	\$0.00	\$369.74
OVERHEAD:	\$489.92	\$0.00	\$489.92
	\$859.66	\$0.00	\$859.66
VEHICLE:	\$0.00	\$0.00	\$0.00
CONTRACTOR:	\$0.00	\$0.00	\$0.00
ADDITIONAL ITEMS:	\$0.00	\$0.00	\$0.00
SUBTOTAL:	\$1,553.12	\$0.00	\$1,553.12
REMOVAL:			
MATERIAL:	\$0.00	\$0.00	\$0.00
OVERHEAD:	\$0.00	\$0.00	\$0.00
	\$0.00	\$0.00	\$0.00
LABOR HOURS:	0	0	0
LABOR COST:	\$0.00	\$0.00	\$0.00
OVERHEAD:	\$0.00	\$0.00	\$0.00
	\$0.00	\$0.00	\$0.00
VEHICLE:	\$0.00	\$0.00	\$0.00
CONTRACTOR:	\$0.00	\$0.00	\$0.00
ADDITIONAL ITEMS:	\$0.00	\$0.00	\$0.00
SUBTOTAL:	\$0.00	\$0.00	\$0.00
TRANSFER:			
LABOR HOURS:	0	0	0
LABOR COST:	\$0.00	\$0.00	\$0.00
OVERHEAD:	\$0.00	\$0.00	\$0.00
	\$0.00	\$0.00	\$0.00
VEHICLE:	\$0.00	\$0.00	\$0.00
CONTRACTOR:	\$0.00	\$0.00	\$0.00
ADDITIONAL ITEMS:	\$0.00	\$0.00	\$0.00
SUBTOTAL:	\$0.00	\$0.00	\$0.00
TOTALS:	\$1,553.12	\$0.00	\$1,553.12



## Work Request Material Summary \*\*\*Includes Truck Stock\*\*\*

Design Number 1

**Printed Date: 3/11/2021** Dist: CSA

WR No. 925096

			3-		
Mater	rial Numbe	er Description	Unit Price	<b>Total Cost</b>	Asset?
INSTALL					
2	2003651	ARRESTER, LIGHTNING DISTRIBUTION CLASS 8	\$41.28	\$82.56	Υ
2	2077754	BOLT, MACHINE 5/8" X 10", GALV. FULL	\$1.04	\$2.08	N
2	2131366	BRACKET, FG, 1 PH, 1 POS, 18"	\$30.03	\$60.06	N
2	2077906	CLAMP, GROUND ROD, F/U/W 1/2"ROD	\$1.80	\$3.60	N
2	2077911	CLAMP, HOT LINE CU TO CU #6 SOL- 2 STR T	\$5.73	\$11.46	N
80	2078012	CONDUCTOR, COPPERCLAD, 3 STR. #9, DSA 30	\$0.84	\$67.20	N
6	2004187	CONDUCTOR,BARE,#2 CU,7-STR,SOFT-DRAWN	\$0.98	\$5.88	N
2	2077837	CONNECTOR, COMPRESSION H-BLOCK ACSR 2/0	\$0.66	\$1.32	N
4	2077930	CONNECTOR, VICE CU #4 STR	\$1.91	\$7.64	N
0	2077939	COUPLER, GROUND ROD, F/U/W 1/2"ROD	\$4.78	\$0.00	N
2	2003846	CUTOUT, 15KV, 100A FUSE HLDR, 300A UNVRS	\$70.74	\$141.48	Υ
2	2077794	FUSE LINK, 103A UNVRSL 100A CUTOUT 23" O	\$24.29	\$48.58	N
2	2077822	KIT, ATTACHMENT, FOR ATTACHING "FLYING"	\$63.00	\$126.00	N
4	2077965	MOULDING, GROUND WIRE, PVC 1/2 IN X 8 FT	\$1.74	\$6.96	N
0	2077980	ROD,GROUND,CU BONDED,1/2"X10',THREADLESS	\$13.72	\$0.00	N
2	2077789	SCREW, LAG PILOT POINT 3/8 X 3	\$0.27	\$0.54	N
20	2077997	STAPLE, SECURES 1/2" PVC MOULDING TO WOO	\$0.27	\$5.40	N
2	2077828	STIRRUP, AL BODY & CU BAIL 1/0-397	\$17.19	\$34.38	N
2	2078006	WASHER, FLAT, GALVANIZED, 2" X 2" X 1/8"	\$0.24	\$0.48	N
2	2004184	WIRE, COPPER, BARE, #4 SOFT DRAWN 7 STR	\$0.63	\$1.32	N
6	2078011	WIRE, COPPER, TIE, #6 SOLID SOFT DRAWN	\$0.38	\$2.28	N
			Total	\$609.22	



#### **Estimate Summary**

Design Number 1

Dist Svcs HDUG GRD takeoff POLE

**Printed Date: 3/11/2021** 

District: CSA

WR No. 925097

Date Sched: 4/1/21 Date Required: 4/1/21

Additional Information: Full PSC Filing 10/2010

WR Description: HDUG 1250 sq ft GROUND TAKEOFFS

INSTALLATION:	Capital	Oper./Maint.	Total
MATERIAL:	\$138.44	\$0.00	\$138.44
OVERHEAD:	\$19.15	\$0.00	\$19.15
	\$157.59	\$0.00	\$157.59
LABOR HOURS:	3.75	0	3.75
LABOR COST:	\$165.26	\$0.00	\$165.26
OVERHEAD:	\$218.97	\$0.00	\$218.97
	\$384.23	\$0.00	\$384.23
VEHICLE:	\$0.00	\$0.00	\$0.00
CONTRACTOR:	\$0.00	\$0.00	\$0.00
ADDITIONAL ITEMS:	\$0.00	\$0.00	\$0.00
SUBTOTAL:	\$541.82	\$0.00	\$541.82
REMOVAL:			
MATERIAL:	\$0.00	\$0.00	\$0.00
OVERHEAD:	\$0.00	\$0.00	\$0.00
	\$0.00	\$0.00	\$0.00
LABOR HOURS:	0	0	0
LABOR COST:	\$0.00	\$0.00	\$0.00
OVERHEAD:	\$0.00	\$0.00	\$0.00
	\$0.00	\$0.00	\$0.00
VEHICLE:	\$0.00	\$0.00	\$0.00
CONTRACTOR:	\$0.00	\$0.00	\$0.00
ADDITIONAL ITEMS:	\$0.00	\$0.00	\$0.00
SUBTOTAL:	\$0.00	\$0.00	\$0.00
TRANSFER:			
LABOR HOURS:	0	0	0
LABOR COST:	\$0.00	\$0.00	\$0.00
OVERHEAD:	\$0.00	\$0.00	\$0.00
	\$0.00	\$0.00	\$0.00
VEHICLE:	\$0.00	\$0.00	\$0.00
CONTRACTOR:	\$0.00	\$0.00	\$0.00
ADDITIONAL ITEMS:	\$0.00	\$0.00	\$0.00
SUBTOTAL:	\$0.00	\$0.00	\$0.00
TOTALS:	\$541.82	\$0.00	\$541.82



## Work Request Material Summary \*\*\*Includes Truck Stock\*\*\*

Design Number 1

**Printed Date: 3/11/2021** 

Dist: CSA WR No. 925097

				•		
	Mate	erial Number	Description	Unit Price	Total Cost	Asset?
INSTAL	.L					
	6	2077939	COUPLER, GROUND ROD, F/U/W 1/2"ROD	\$4.78	\$28.68	N
	8	2077980	ROD,GROUND,CU BONDED,1/2"X10',THREADLESS	\$13.72	\$109.76	N
				Total	\$138.44	



### Estimate Summary Design Number 1

Distribution Engineering HDUG Pri Conduit Material

**Printed Date: 3/11/2021** 

District: CSA

WR No. 925098 Date Sched: 4/1/21 Date Required: 4/1/21

Additional Information: Full PSC Filing 10/2010

WR Description: HDUG 1250 sq ft PRIMARY CONDUIT

INSTALLATION:	Capital	Oper./Maint.	Total
MATERIAL:	\$8,360.08	\$0.00	\$8,360.08
OVERHEAD:	\$1,156.20	\$0.00	\$1,156.20
	\$9,516.28	\$0.00	\$9,516.28
LABOR HOURS:	0	0	0
LABOR COST:	\$0.05	\$0.00	\$0.05
OVERHEAD:	\$0.07	\$0.00	\$0.07
	\$0.12	\$0.00	\$0.12
VEHICLE:	\$0.00	\$0.00	\$0.00
CONTRACTOR:	\$0.00	\$0.00	\$0.00
ADDITIONAL ITEMS:	\$0.00	\$0.00	\$0.00
SUBTOTAL:	\$9,516.40	\$0.00	\$9,516.40
REMOVAL:			
MATERIAL:	\$0.00	\$0.00	\$0.00
OVERHEAD:	\$0.00	\$0.00	\$0.00
	\$0.00	\$0.00	\$0.00
LABOR HOURS:	0	0	0
LABOR COST:	\$0.00	\$0.00	\$0.00
OVERHEAD:	\$0.00	\$0.00	\$0.00
	\$0.00	\$0.00	\$0.00
VEHICLE:	\$0.00	\$0.00	\$0.00
CONTRACTOR:	\$0.00	\$0.00	\$0.00
ADDITIONAL ITEMS:	\$0.00	\$0.00	\$0.00
SUBTOTAL:	\$0.00	\$0.00	\$0.00
TRANSFER:			
LABOR HOURS:	0	0	0
LABOR COST:	\$0.00	\$0.00	\$0.00
OVERHEAD:	\$0.00	\$0.00	\$0.00
	\$0.00	\$0.00	\$0.00
VEHICLE:	\$0.00	\$0.00	\$0.00
CONTRACTOR:	\$0.00	\$0.00	\$0.00
ADDITIONAL ITEMS:	\$0.00	\$0.00	\$0.00
SUBTOTAL:	\$0.00	\$0.00	\$0.00
TOTALS:	\$9,516.40	\$0.00	\$9,516.40



## Work Request Material Summary \*\*\*Includes Truck Stock\*\*\*

Design Number 1

**Printed Date: 3/11/2021** Dist: CSA

WR No. 925098

			. 5 .		
Mate	erial Numbe	er Description	Unit Price	Total Cost	Asset?
INSTALL					
12	2007227	CEMENT, PVC CLEAR FAST DRY QUART W/DAUBE	\$6.22	\$74.64	N
20	2004389	CONDUIT, GALVANIZED 2 IN 10 FT WITH COUP	\$6.78	\$135.60	Υ
5935	2004488	CONDUIT, PVC 2 IN 20 FT BELL END	\$1.03	\$6,113.05	Υ
108	2004507	COUPLING, PVC 2 IN SCH 40 TEMS 13.01	\$0.60	\$64.80	N
46	2004395	ELBOW, 2" 90 DEGREE ,GALVANIZED, 24" MIN	\$34.29	\$1,577.34	N
8	2004394	ELBOW, GALV 2 INCH 45 DEG THD 15" RADIUS	\$26.25	\$210.00	N
6155	2007414	TAPE, PULLING, POLYSTER, RATED AT 1250#,	\$0.03	\$184.65	N
			Total	\$8,360.08	



#### **Estimate Summary**

Design Number 1

Dist Svcs HDUG PRIMARY **Printed Date: 3/11/2021** 

District: CSA

WR No. 925100

Date Sched: 4/1/21 Date Required: 4/1/21

Additional Information: Full PSC Filing 10/2010

WR Description: HDUG 1250 sq ft PRIMARY CABLE

INSTALLATION:	Capital	Oper./Maint.	Total
MATERIAL:	\$15,227.81	\$0.00	\$15,227.81
OVERHEAD:	\$2,106.01	\$0.00	\$2,106.01
	\$17,333.82	\$0.00	\$17,333.82
LABOR HOURS:	115.14	0	115.14
LABOR COST:	\$5,068.62	\$0.00	\$5,068.62
OVERHEAD:	\$6,715.92	\$0.00	\$6,715.92
	\$11,784.54	\$0.00	\$11,784.54
VEHICLE:	\$0.00	\$0.00	\$0.00
CONTRACTOR:	\$0.00	\$0.00	\$0.00
ADDITIONAL ITEMS:	\$0.00	\$0.00	\$0.00
SUBTOTAL:	\$29,118.36	\$0.00	\$29,118.36
REMOVAL:			
MATERIAL:	\$0.00	\$0.00	\$0.00
OVERHEAD:	\$0.00	\$0.00	\$0.00
	\$0.00	\$0.00	\$0.00
LABOR HOURS:	0	0	0
LABOR COST:	\$0.00	\$0.00	\$0.00
OVERHEAD:	\$0.00	\$0.00	\$0.00
	\$0.00	\$0.00	\$0.00
VEHICLE:	\$0.00	\$0.00	\$0.00
CONTRACTOR:	\$0.00	\$0.00	\$0.00
ADDITIONAL ITEMS:	\$0.00	\$0.00	\$0.00
SUBTOTAL:	\$0.00	\$0.00	\$0.00
TRANSFER:			
LABOR HOURS:	0	0	0
LABOR COST:	\$0.00	\$0.00	\$0.00
OVERHEAD:	\$0.00	\$0.00	\$0.00
	\$0.00	\$0.00	\$0.00
VEHICLE:	\$0.00	\$0.00	\$0.00
CONTRACTOR:	\$0.00	\$0.00	\$0.00
ADDITIONAL ITEMS:	\$0.00	\$0.00	\$0.00
SUBTOTAL:	\$0.00	\$0.00	\$0.00
TOTALS:	\$29,118.36	\$0.00	\$29,118.36



## Work Request Material Summary \*\*\*Includes Truck Stock\*\*\*

Design Number 1

**Printed Date: 3/11/2021** Dist: CSA

WR No. 925100

Mat	erial Numbe	er Description	Unit Price	Total Cost	Asset?
INSTALL					
6304	2004343	CABLE, ALUMINUM, 15KV, 1/C, 1/0 AWG SOLI	\$2.08	\$13,112.53	Υ
2	2004514	CAP, CONDUIT 2"	\$12.21	\$24.42	N
2	2004453	CAP, END CABLE 600 V CABLE RANGE .940 -	\$1.96	\$3.92	N
2	2003752	CLAMP, CONDUIT GROUND 1-1/4 IN - 2 IN CO	\$7.92	\$15.84	N
0	2004488	CONDUIT, PVC 2 IN 20 FT BELL END	\$1.03	\$0.00	Υ
2	2077837	CONNECTOR, COMPRESSION H-BLOCK ACSR 2/0	\$0.66	\$1.32	N
44	2077931	CONNECTOR, VICE CU #2 STR	\$2.38	\$104.72	N
40	2004642	KIT, SEALING, CABLE ACCESSORY, 1/0 - 4/0	\$9.46	\$378.40	N
8	2004403	STRAP, GALV 2 IN 2 HOLE	\$0.28	\$2.24	N
40	2004883	TERMINATOR, LOADBREAK 200 AMP, 1/0 SOL	\$37.76	\$1,510.40	Υ
2	2004633	TERMINATOR, POTHEAD 15KV OUTDOOR 1/0 JCN	\$35.75	\$71.50	Υ
4	2004184	WIRE, COPPER, BARE, #4 SOFT DRAWN 7 STR	\$0.63	\$2.52	N
			Total	\$15,227.81	



### Estimate Summary Design Number 1

Dist Svcs HDUG SECONDARY

**Printed Date:** 3/11/2021

District: CSA

WR No. 925103

Date Sched: 4/1/21 Date Required: 4/1/21

Additional Information: Full PSC Filing 10/2010

WR Description: HDUG 1250 sq ft SECONDARY CABLE

INSTALLATION:	Capital	Oper./Maint.	Total
MATERIAL:	\$8,598.95	\$0.00	\$8,598.95
OVERHEAD:	\$1,189.23	\$0.00	\$1,189.23
	\$9,788.18	\$0.00	\$9,788.18
LABOR HOURS:	146.42	0	146.42
LABOR COST:	\$6,445.28	\$0.00	\$6,445.28
OVERHEAD:	\$8,540.02	\$0.00	\$8,540.02
	\$14,985.30	\$0.00	\$14,985.30
VEHICLE:	\$0.00	\$0.00	\$0.00
CONTRACTOR:	\$0.00	\$0.00	\$0.00
ADDITIONAL ITEMS:	\$0.00	\$0.00	\$0.00
SUBTOTAL:	\$24,773.48	\$0.00	\$24,773.48
REMOVAL:			
MATERIAL:	\$0.00	\$0.00	\$0.00
OVERHEAD:	\$0.00	\$0.00	\$0.00
	\$0.00	\$0.00	\$0.00
LABOR HOURS:	0	0	0
LABOR COST:	\$0.00	\$0.00	\$0.00
OVERHEAD:	\$0.00	\$0.00	\$0.00
	\$0.00	\$0.00	\$0.00
VEHICLE:	\$0.00	\$0.00	\$0.00
CONTRACTOR:	\$0.00	\$0.00	\$0.00
ADDITIONAL ITEMS:	\$0.00	\$0.00	\$0.00
SUBTOTAL:	\$0.00	\$0.00	\$0.00
TRANSFER:			
LABOR HOURS:	0	0	0
LABOR COST:	\$0.00	\$0.00	\$0.00
OVERHEAD:	\$0.00	\$0.00	\$0.00
	\$0.00	\$0.00	\$0.00
VEHICLE:	\$0.00	\$0.00	\$0.00
CONTRACTOR:	\$0.00	\$0.00	\$0.00
ADDITIONAL ITEMS:	\$0.00	\$0.00	\$0.00
SUBTOTAL:	\$0.00	\$0.00	\$0.00
TOTALS:	\$24,773.48	\$0.00	\$24,773.48



## Work Request Material Summary \*\*\*Includes Truck Stock\*\*\*

Design Number 1

**Printed Date: 3/11/2021** Dist: CSA

WR No. 925103

Page 1 of 1

			•		
Mate	erial Numbe	er Description	Unit Price	Total Cost	Asset?
INSTALL					
2029	2004354	CABLE, SWEETBRIAR, AL, UG, 600V, 2/C, 4/0 AW	\$1.39	\$2,820.59	Υ
45	2005022	CONNECTOR, 600V URD, 6 POSITION, CONDUCT	\$14.92	\$671.40	N
12	2005025	CONNECTOR, 600V, URD, 8 POSITION, CONDUC	\$30.35	\$364.20	N
22	2000241	DECAL,WARNING,NOTICE,CLEARANCE,10" X 7"	\$3.56	\$78.32	N
22	2004714	HANDHOLE, ABOVE GRADE, LARGE DOME	\$186.22	\$4,096.84	N
22	2005212	MARKER, CURB LEXAN .040 THICK, ROUND 2.5	\$2.83	\$62.26	N
22	2007395	PADLOCK, RED BRASS BODY 1/4" BRASS SHACK	\$22.97	\$505.34	N
			Total	\$8,598.95	

HD-22



#### **Estimate Summary**

Design Number 1

Dist Svcs HDUG SEC CONDUIT **Printed Date:** 3/11/2021

District: CSA

WR No. 925104

Date Sched: 4/1/21 Date Required: 4/1/21

Additional Information: Full PSC Filing 10/2010

WR Description: HDUG 1250 sq ft SECONDARY CONDUIT

INSTALLATION:	Capital	Oper./Maint.	Total	
MATERIAL:	\$5,153.37	\$0.00	\$5,153.37	
OVERHEAD:	\$712.71	\$0.00	\$712.71	
	\$5,866.08	\$0.00	\$5,866.08	
LABOR HOURS:	0	0	0	
LABOR COST:	\$0.03	\$0.00	\$0.03	
OVERHEAD:	\$0.05	\$0.00	\$0.05	
	\$0.08	\$0.00	\$0.08	
VEHICLE:	\$0.00	\$0.00	\$0.00	
CONTRACTOR:	\$0.00	\$0.00	\$0.00	
ADDITIONAL ITEMS:	\$0.00	\$0.00	\$0.00	
SUBTOTAL:	\$5,866.16	\$0.00	\$5,866.16	
REMOVAL:				
MATERIAL:	\$0.00	\$0.00	\$0.00	
OVERHEAD:	\$0.00	\$0.00	\$0.00	
	\$0.00	\$0.00	\$0.00	
LABOR HOURS:	0	0	0	
LABOR COST:	\$0.00	\$0.00	\$0.00	
OVERHEAD:	\$0.00	\$0.00	\$0.00	
	\$0.00	\$0.00	\$0.00	
VEHICLE:	\$0.00	\$0.00	\$0.00	
CONTRACTOR:	\$0.00	\$0.00	\$0.00	
ADDITIONAL ITEMS:	\$0.00	\$0.00	\$0.00	
SUBTOTAL:	\$0.00	\$0.00	\$0.00	
TRANSFER:				
LABOR HOURS:	0	0	0	
LABOR COST:	\$0.00	\$0.00	\$0.00	
OVERHEAD:	\$0.00	\$0.00	\$0.00	
	\$0.00	\$0.00	\$0.00	
VEHICLE:	\$0.00	\$0.00	\$0.00	
CONTRACTOR:	\$0.00	\$0.00	\$0.00	
ADDITIONAL ITEMS:	\$0.00	\$0.00	\$0.00	
SUBTOTAL:	\$0.00	\$0.00	\$0.00	
TOTALS:	\$5,866.16	\$0.00	\$5,866.16	



d\_material\_item\_summary\_test\_all

## Work Request Material Summary \*\*\*Includes Truck Stock\*\*\*

Design Number 1

**Printed Date: 3/11/2021** Dist: CSA

WR No. 925104

		. 3 .		
erial Numbe	er Description	Unit Price	Total Cost	Asset?
2007227	CEMENT, PVC CLEAR FAST DRY QUART W/DAUBE	\$6.22	\$6.22	N
2007228	CEMENT, PVC GRAY MEDIUM DRY QUART W/DAUB	\$7.27	\$43.62	N
2004517	CONDUIT, PVC P & C 3 IN 20 FT	\$1.70	\$494.70	Υ
2004529	CONDUIT, PVC, 4" X 20', DB-60-TC-6	\$2.78	\$3,919.80	Υ
2004521	COUPLING, PVC 3 IN SCH 40 TEMS 13.01	\$2.95	\$47.20	N
2004535	COUPLING, PVC 4 IN SCH 40 TEMS 13.01	\$4.28	\$308.16	N
2004524	ELBOW, PVC 3 IN 90 DEG 13 IN RAD SCH 40	\$4.52	\$36.16	N
2004538	ELBOW, PVC 4", 90 DEG., 16" RADIUS, SCHE	\$6.68	\$240.48	N
2007414	TAPE, PULLING, POLYSTER, RATED AT 1250#,	\$0.03	\$57.03	N
		Total	\$5,153.37	
	2007227 2007228 2004517 2004529 2004521 2004535 2004524 2004538	2007227 CEMENT, PVC CLEAR FAST DRY QUART W/DAUBE 2007228 CEMENT, PVC GRAY MEDIUM DRY QUART W/DAUB 2004517 CONDUIT, PVC P & C 3 IN 20 FT 2004529 CONDUIT, PVC, 4" X 20', DB-60-TC-6 2004521 COUPLING, PVC 3 IN SCH 40 TEMS 13.01 2004535 COUPLING, PVC 4 IN SCH 40 TEMS 13.01 2004524 ELBOW, PVC 3 IN 90 DEG 13 IN RAD SCH 40 2004538 ELBOW, PVC 4", 90 DEG., 16" RADIUS, SCHE	2007227 CEMENT, PVC CLEAR FAST DRY QUART W/DAUBE \$6.22 2007228 CEMENT, PVC GRAY MEDIUM DRY QUART W/DAUB \$7.27 2004517 CONDUIT, PVC P & C 3 IN 20 FT \$1.70 2004529 CONDUIT, PVC, 4" X 20', DB-60-TC-6 \$2.78 2004521 COUPLING, PVC 3 IN SCH 40 TEMS 13.01 \$2.95 2004535 COUPLING, PVC 4 IN SCH 40 TEMS 13.01 \$4.28 2004524 ELBOW, PVC 3 IN 90 DEG 13 IN RAD SCH 40 \$4.52 2004538 ELBOW, PVC 4", 90 DEG., 16" RADIUS, SCHE \$6.68 2007414 TAPE, PULLING, POLYSTER, RATED AT 1250#, \$0.03	2007227       CEMENT, PVC CLEAR FAST DRY QUART W/DAUBE       \$6.22       \$6.22         2007228       CEMENT, PVC GRAY MEDIUM DRY QUART W/DAUB       \$7.27       \$43.62         2004517       CONDUIT, PVC P & C 3 IN 20 FT       \$1.70       \$494.70         2004529       CONDUIT, PVC, 4" X 20', DB-60-TC-6       \$2.78       \$3,919.80         2004521       COUPLING, PVC 3 IN SCH 40 TEMS 13.01       \$2.95       \$47.20         2004535       COUPLING, PVC 4 IN SCH 40 TEMS 13.01       \$4.28       \$308.16         2004524       ELBOW, PVC 3 IN 90 DEG 13 IN RAD SCH 40       \$4.52       \$36.16         2004538       ELBOW, PVC 4", 90 DEG., 16" RADIUS, SCHE       \$6.68       \$240.48         2007414       TAPE, PULLING, POLYSTER, RATED AT 1250#,       \$0.03       \$57.03



#### **Estimate Summary**

Design Number 1

Dist Svcs HDUG SERVICE CABLE

**Printed Date:** 3/11/2021

District: CSA

WR No. 925106

Date Sched: 4/1/21 Date Required: 4/1/21

Additional Information: Full PSC Filing 10/2010

WR Description: HDUG 1250 sq ft SERVICE CABLE

INSTALLATION:	Capital	Oper./Maint.	Total	
MATERIAL:	\$16,257.47	\$0.00	\$16,257.47	
OVERHEAD:	\$2,248.40	\$0.00	\$2,248.40	
	\$18,505.87	\$0.00	\$18,505.87	
LABOR HOURS:	1.53	0	1.53	
LABOR COST:	\$67.48	\$0.00	\$67.48	
OVERHEAD:	\$89.41	\$0.00	\$89.41	
	\$156.89	\$0.00	\$156.89	
VEHICLE:	\$0.00	\$0.00	\$0.00	
CONTRACTOR:	\$0.00	\$0.00	\$0.00	
ADDITIONAL ITEMS:	\$0.00	\$0.00	\$0.00	
SUBTOTAL:	\$18,662.76	\$0.00	\$18,662.76	
REMOVAL:				
MATERIAL:	\$0.00	\$0.00	\$0.00	
OVERHEAD:	\$0.00	\$0.00	\$0.00	
	\$0.00	\$0.00	\$0.00	
LABOR HOURS:	0	0	0	
LABOR COST:	\$0.00	\$0.00	\$0.00	
OVERHEAD:	\$0.00	\$0.00	\$0.00	
	\$0.00	\$0.00	\$0.00	
VEHICLE:	\$0.00	\$0.00	\$0.00	
CONTRACTOR:	\$0.00	\$0.00	\$0.00	
ADDITIONAL ITEMS:	\$0.00	\$0.00	\$0.00	
SUBTOTAL:	\$0.00	\$0.00	\$0.00	
TRANSFER:				
LABOR HOURS:	0	0	0	
LABOR TOOKS.	\$0.00	\$0.00	\$0.00	
OVERHEAD:	\$0.00	\$0.00	\$0.00	
	\$0.00	\$0.00	\$0.00	
VEHICLE:	\$0.00	\$0.00	\$0.00	
CONTRACTOR:	\$0.00	\$0.00	\$0.00	
ADDITIONAL ITEMS:	\$0.00	\$0.00	\$0.00	
SUBTOTAL:	\$0.00	\$0.00	\$0.00	
TOTALS:	\$18,662.76	\$0.00	\$18,662.76	



# Work Request Material Summary \*\*\*Includes Truck Stock\*\*\*

Design Number 1

**Printed Date: 3/11/2021** Dist: CSA

WR No. 925106

	Mate	erial Numbe	r Description	Description Unit Price				
IN	ISTALL							
	16097	2004351	CABLE, CONVERSE, AL, UG, 600V, 2/C, 2/0,	\$1.01	\$16,257.47	Υ		
				Total	\$16.257.47			



#### **Estimate Summary**

Design Number 1

Dist Svcs HDUG SET METERS **Printed Date:** 3/11/2021

District: CSA

WR No. 925108

Date Sched: 4/1/21 Date Required: 4/1/21

Additional Information: Full PSC Filing 10/2010 WR Description: HDUG 1250 sq ft METERS

INSTALLATION:	Capital	Oper./Maint.	Total
MATERIAL:	\$0.00	\$0.00	\$0.00
OVERHEAD:	\$0.00	\$0.00	\$0.00
	\$0.00	\$0.00	\$0.00
LABOR HOURS:	35.27	0	35.27
LABOR COST:	\$1,552.59	\$0.00	\$1,552.59
OVERHEAD:	\$2,057.18	\$0.00	\$2,057.18
	\$3,609.77	\$0.00	\$3,609.77
VEHICLE:	\$0.00	\$0.00	\$0.00
CONTRACTOR:	\$0.00	\$0.00	\$0.00
ADDITIONAL ITEMS:	\$0.00	\$0.00	\$0.00
SUBTOTAL:	\$3,609.77	\$0.00	\$3,609.77
REMOVAL:			
MATERIAL:	\$0.00	\$0.00	\$0.00
OVERHEAD:	\$0.00	\$0.00	\$0.00
	\$0.00	\$0.00	\$0.00
LABOR HOURS:	0	0	0
LABOR COST:	\$0.00	\$0.00	\$0.00
OVERHEAD:	\$0.00	\$0.00	\$0.00
	\$0.00	\$0.00	\$0.00
VEHICLE:	\$0.00	\$0.00	\$0.00
CONTRACTOR:	\$0.00	\$0.00	\$0.00
ADDITIONAL ITEMS:	\$0.00	\$0.00	\$0.00
SUBTOTAL:	\$0.00	\$0.00	\$0.00
TRANSFER:			
LABOR HOURS:	0	0	0
LABOR COST:	\$0.00	\$0.00	\$0.00
OVERHEAD:	\$0.00	\$0.00	\$0.00
	\$0.00	\$0.00	\$0.00
VEHICLE:	\$0.00	\$0.00	\$0.00
CONTRACTOR:	\$0.00	\$0.00	\$0.00
ADDITIONAL ITEMS:	\$0.00	\$0.00	\$0.00
SUBTOTAL:	\$0.00	\$0.00	\$0.00
TOTALS:	\$3,609.77	\$0.00	\$3,609.77



#### **Estimate Summary**

Design Number 1

Dist Svcs HDUG SERVICE CONDUIT

**Printed Date:** 3/11/2021

District: CSA

WR No. 925110

Date Sched: 4/1/21 Date Required: 4/1/21

Additional Information: Full PSC Filing 10/2010

WR Description: HDUG 1250 sq ft SERVICE CONDUIT

INSTALLATION:	Capital	Oper./Maint.	Total
MATERIAL:	\$18,669.34	\$0.00	\$18,669.34
OVERHEAD:	\$2,581.97	\$0.00	\$2,581.97
	\$21,251.31	\$0.00	\$21,251.31
LABOR HOURS:	0	0	0
LABOR COST:	\$0.13	\$0.00	\$0.13
OVERHEAD:	\$0.19	\$0.00	\$0.19
	\$0.32	\$0.00	\$0.32
VEHICLE:	\$0.00	\$0.00	\$0.00
CONTRACTOR:	\$0.00	\$0.00	\$0.00
ADDITIONAL ITEMS:	\$0.00	\$0.00	\$0.00
SUBTOTAL:	\$21,251.63	\$0.00	\$21,251.63
REMOVAL:			
MATERIAL:	\$0.00	\$0.00	\$0.00
OVERHEAD:	\$0.00	\$0.00	\$0.00
	\$0.00	\$0.00	\$0.00
LABOR HOURS:	0	0	0
LABOR COST:	\$0.00	\$0.00	\$0.00
OVERHEAD:	\$0.00	\$0.00	\$0.00
	\$0.00	\$0.00	\$0.00
VEHICLE:	\$0.00	\$0.00	\$0.00
CONTRACTOR:	\$0.00	\$0.00	\$0.00
ADDITIONAL ITEMS:	\$0.00	\$0.00	\$0.00
SUBTOTAL:	\$0.00	\$0.00	\$0.00
TRANSFER:			
LABOR HOURS:	0	0	0
LABOR COST:	\$0.00	\$0.00	\$0.00
OVERHEAD:	\$0.00	\$0.00	\$0.00
	\$0.00	\$0.00	\$0.00
VEHICLE:	\$0.00	\$0.00	\$0.00
CONTRACTOR:	\$0.00	\$0.00	\$0.00
ADDITIONAL ITEMS:	\$0.00	\$0.00	\$0.00
SUBTOTAL:	\$0.00	\$0.00	\$0.00
TOTALS:	\$21,251.63	\$0.00	\$21,251.63




## Work Request Material Summary \*\*\*Includes Truck Stock\*\*\*

Design Number 1

**Printed Date: 3/11/2021** Dist: CSA

WR No. 925110

Material Number Description		•			
Mate	erial Numbe	er Description	Unit Price	Total Cost	Asset?
INSTALL					
176	2004493	ADAPTOR, 2" PVC, FEMALE SLIP TO MALE THR	\$0.40	\$70.40	N
31	2007227	CEMENT, PVC CLEAR FAST DRY QUART W/DAUBE	\$6.22	\$192.82	N
15330	2004488	CONDUIT, PVC 2 IN 20 FT BELL END	\$1.03	\$15,789.90	Υ
176	2004491	CONDUIT, PVC 2 IN 250 FT ROLL FLEXIBLE	\$1.13	\$198.88	N
176	2004401	CONDUIT, SERVICE RISER, PVC, 2"	\$4.92	\$865.92	N
896	2004507	COUPLING, PVC 2 IN SCH 40 TEMS 13.01	\$0.60	\$537.60	N
448	2004511	ELBOW, CONDUIT PVC 2 IN SCH 40 90 DEG 9-	\$1.26	\$564.48	N
176	2004396	NUT, LOCK GALV 2 IN	\$0.54	\$95.04	N
11810	2007414	TAPE, PULLING, POLYSTER, RATED AT 1250#,	\$0.03	\$354.30	N
			Total	\$18,669.34	



#### OH Construction Cost Data Summary

High Density (176-Lot) OH Subdivision Costs

	Α	В	C (D+ M)	D	(F + L)	F (G + H + I)	G	H (G x J x TLF)	(G x K x CLF)	J	К	L	M (D x MHR)	N (C+E)
Line #	Work Type/WR #	Description	Material and Handling	Material	Total Labor Plus Vehicles	Total Labor	Base Labor	Operations Labor Overheads	Contract Labor Overheads	TEC Work %	Contractor Work %	Vehicle	Material Handling	Total
	, μ=	25500,000												
1 2	Transformers 925111	Install & Ground Transformers	31,143.07	27,751.80	12,366.93	11,060.26	6,439.97	4,103.55	516.74	60%	40%	\$1,306.67	3,391.27	43,510.00
3	323111	motali d Ground Hansiornicis	01,140.07	27,701.00	12,000.00	11,000.20	0,400.01	4,100.00	010.74	0070	4070	ψ1,000.01	0,001.21	40,010.00
	Primary													
5	925112	Install Primary Line	2,544.16	2,267.12	6,190.06	5,536.03	3,223.42	2,053.96	258.65	60%	40%	\$654.03	277.04	8,734.22
6		includes Grounding Primary Takeoffs												
	Poles													
8 9	925113	Install Poles and Guy Stubs Includes Haul Poles Out	22,510.66	20,059.40	36,177.05	32,354.65	18,838.88	12,004.13	1,511.63	60%	40%	\$3,822.41	2,451.26	58,687.71
	Secondary	Includes Haul Poles Out												
11	925114	Install Secondary Cable	12,719.79	11,334.69	18,719.51	16,741.64	9,748.02	6,211.44	782.18	60%	40%	\$1,977.87	1,385.10	31,439.30
12		, .												
13	Services													
14	927142	Install Service Cable	10,342.22	9,216.02	12,847.44	11,490.00	6,690.19	4,262.99	536.82	60%	40%	\$1,357.44	1,126.20	23,189.66
15	927163	Install Meters	17,751.95	\$ <u>15,818.88</u>	3,314.51	2,666.48	1,552.59	989.31	124.58	60%	40%	648.03	1,933.07	21,066.46
16 17			28,094.16	25,034.90	16,161.95	14,156.48	8,242.78	5,252.30	661.40			2,005.47	3,059.26	44,256.11
18 19	Engineering	Design/Inspection/Coordination	-	-	10,785.62		-	-	-	100%	0%		-	10,785.62
20 21	Tree Trim		-	-	-	-	-	-	-			-	-	-
22	Totals (Sum of lines 2	2, 5, 8, 11, 16, 18, and 20)	97,011.84	86,447.91	100,401.14	79,849.06	46,493.07	29,625.38	3,730.60			9,766.45	10,563.93	197,412.98
23	Cost "Per Lot" (Line 3	34/ 176 lots)	551.20		570.46									1,121.66

Adjustment Factors		
TEC Labor Overhead Factor (excludes engineering)	TLF =	1.062
Contractor Labor Overhead Factor	CLF =	0.2006
Current year material handling charge rate	MHR =	0.1222

#### High Density - 176 Lots - Overhead Material List

This worksheet lists the totals for major materials to be listed on the associated work request print as requested by the PSC.

737.5 Total Connected KVA

800 Total peak demand KVA

2 25 kVA Transformers

5 37.5 kVA Transformers

7 50 kVA Transformers

2 75 kVA Transformers

0 100 kVA Transformers

6165 #2AAAC Primary

**44 Primary Poles** 

5155 2/0 AWG Triplex Secondary

0 4/0 AWG Triplex Secondary

225 #2AAAC Secondary Neutral

965 2-2/0 & 1-1/0 AL Triplex Service Drop (considered secondary)

0 2-4/0 & 1-2/0 AL Triplex Service Drop (considered secondary)

19 Secondary Poles

8960 2-2/0 & 1-1/0 AL Triplex Service Drop

0 2-4/0 & 1-2/0 AL Triplex Service Drop

#### Summary of assemblies (CU's) for High Density Overhead Design - March 2018

Work Request #1	925111	- Transformers (enter the	se Construction Units into V	WorkPro)				
	25 KVA	37.5 KVA	50 KVA	75 KVA	100 KVA	Stirrup	Spacer	Grounding
Assemblies ====>	PKT11W3F	PKT11W4F	PKT11W5F	PKT11W6F	PKT11W7F	ALSTRP1/0	SEWC	GRDMEG1/2
Total Quantities ==>	2	5	7	2	0	16	16	16
·								

Work Request #2	925112 -	Primary							
	#2 AAAC	1st span	Additional	1st span	Additional	Fused cutouts	DE & TAP	Fuses	Grounding
Assemblies ===>	WIOPA	WIO2F	WIO2A	WIO1F	WIO1A	PKP208WB3A	PKP101WA3A	FLOH103	GRDMEG1/2
Total Quantities ==>	6165	1	7	3	32	1	4	2	3

Work Request #3	925113	- Poles and Guys											
Should be ====>	Pole haul	2ø Deadend	2 ø tangent	2 ø Corner	1ø Deadend	1ø angle <20	1ø angle <20	1ø Tangent	1ø angle >20	3 ø	Down guys	Pole hardware	Guy wire
Assemblies ====>	POLE HAUL	STP402 DE 40C2	STP103 TAN 40C2	STP302 RC 40C2	STP401 DE 40C2	STP101 ANG 40C2	STP101 ANG 45C2	STP101 TAN 40C2	STP301 RC 40C2	STP104E4B	PKG12W2H	PKG31W1H	GUYSTR3/
Total Quantities ==>	44	1	6	1	4	5	2	13	11	1	29	4	340
(													

Work Request #4		- Secondary - From Second	lary&Neutral worksheet										
	35' CL 4	0	2/0	4/0	#2 Neutral	Labor	Labor	Eyebolt	Eyenut	DE+Bolt		Pole hardware	Guy wire
Assemblies ===>	STS11C	POLE HAUL	WIO3SB	WIO3SC	C2AAAC	WIOCF	WIOCA	SEW1DEN	SEG1DEN	PKS11W	CABLEOPEN	PKG31W1H	GUYSTR3/8
Total Quantities ==>	0	0	5155	0	225	6	37	2	2	8	14	8	565

More of Work Request	#4	- Secondary continued - I	From Secondary&Neutral	worksheet and SlackSecondar	y (service cable) & Second	dary Poles worksheet				
-		35' Class 4	Deadend	Clamp	2/0 triplex	4/0 triplex	0	Down guys	Pole hardware	Guy wire
Assemblies ===>	POLE HAUL	STS11C	PKS21G	CLMIDSPAN	CA2/0TPX	CA4/0TPX	SVLABOR	PKG11W1H	PKG31W1H	GUYSTR3/8
Total Quantities ==>	19	19	35	3	965	0	19	1	2	50

Work Request #5	927142	- Services		
	2/0 triplex	4/0 triplex	Clamp	
Assemblies	CA2/0TPX	CA4/0TPX	CLMIDSPAN	SVLABOR
Quantities	8960	0	26	0

Work Request #5	927163 - Set Meter
Assemblies	METERLABOR
Quantities	176



### Estimate Summary Design Number 1

Distribution Services HDOH TRANSFORMER **Contact Name:** Tampa Electric

**Printed Date: 3/11/2021** 

District: CSA

Date Required: 4/1/21

WR No. 925111 Date Sched: 4/1/21

Additional Information: Full PSC Filing 10/2010

WR Description: HDOH 1250 sq ft TRANSFORMERS

<u> </u>	<u> </u>		
INSTALLATION:	Capital	Oper./Maint.	Total
MATERIAL:	\$27,751.80	\$0.00	\$27,751.80
OVERHEAD:	\$3,838.05	\$0.00	\$3,838.05
	\$31,589.85	\$0.00	\$31,589.85
LABOR HOURS:	146.26	0	146.26
LABOR COST:	\$6,439.97	\$0.00	\$6,439.97
OVERHEAD:	\$8,532.90	\$0.00	\$8,532.90
	\$14,972.87	\$0.00	\$14,972.87
VEHICLE:	\$0.00	\$0.00	\$0.00
CONTRACTOR:	\$0.00	\$0.00	\$0.00
ADDITIONAL ITEMS:	\$0.00	\$0.00	\$0.00
SUBTOTAL:	\$46,562.72	\$0.00	\$46,562.72
REMOVAL:			
MATERIAL:	\$0.00	\$0.00	\$0.00
OVERHEAD:	\$0.00	\$0.00	\$0.00
	\$0.00	\$0.00	\$0.00
LABOR HOURS:	0	0	0
LABOR COST:	\$0.00	\$0.00	\$0.00
OVERHEAD:	\$0.00	\$0.00	\$0.00
	\$0.00	\$0.00	\$0.00
VEHICLE:	\$0.00	\$0.00	\$0.00
CONTRACTOR:	\$0.00	\$0.00	\$0.00
ADDITIONAL ITEMS:	\$0.00	\$0.00	\$0.00
SUBTOTAL:	\$0.00	\$0.00	\$0.00
TRANSFER:			
LABOR HOURS:	0	0	0
LABOR COST:	\$0.00	\$0.00	\$0.00
OVERHEAD:	\$0.00	\$0.00	\$0.00
	\$0.00	\$0.00	\$0.00
VEHICLE:	\$0.00	\$0.00	\$0.00
CONTRACTOR:	\$0.00	\$0.00	\$0.00
ADDITIONAL ITEMS:	\$0.00	\$0.00	\$0.00
SUBTOTAL:	\$0.00	\$0.00	\$0.00
TOTALS:	\$46,562.72	\$0.00	\$46,562.72



# Work Request Material Summary \*\*\*Includes Truck Stock\*\*\*

Design Number 1

**Printed Date: 3/11/2021** Dist: CSA

> WR No. 925111 Page 1 of 1

Mate	erial Numbe	er Description	Unit Price	Total Cost	Asset?
INSTALL					
16	2003646	ARRESTER, DISTRIBUTION, 10KV, 8.4KV MCOV	\$39.68	\$634.88	Υ
14	2077754	BOLT, MACHINE 5/8" X 10", GALV. FULL	\$1.04	\$14.56	N
32	2077755	BOLT,MACHINE,SQ HEAD,5/8"X12",ONE SQ NUT	\$1.16	\$37.12	N
16	2003690	BRACKET, CUTOUT, ARRESTER & POTHEAD DWG	\$7.22	\$115.52	N
16	2004660	BRACKET,"L" 5-5/8"IN LENGTH FOR MTG CUTO	\$10.41	\$166.56	N
208	2004197	CABLE, HANDCOIL, COPPER, 600V, 2/0 AWG,	\$2.32	\$482.56	N
24	2004199	CABLE, HANDCOIL, COPPER, 600V, 4/0 AWG,	\$3.75	\$90.00	N
16	2077906	CLAMP, GROUND ROD, F/U/W 1/2"ROD	\$1.80	\$28.80	N
16	2077911	CLAMP, HOT LINE CU TO CU #6 SOL- 2 STR T	\$5.73	\$91.68	N
32	2078000	CLAMP,GND,TRANSFORMER,#10 SOL-#1 STR CU	\$2.31	\$73.92	N
640	2078012	CONDUCTOR, COPPERCLAD, 3 STR. #9, DSA 30	\$0.84	\$537.60	N
4	2003528	CONNECTOR, 2-BOLT AL MAIN 336-500MCM TAP	\$25.78	\$103.12	N
42	2077839	CONNECTOR, COMPRESSION H-BLOCK ACSR 1/0-	\$0.53	\$22.26	N
16	2077837	CONNECTOR, COMPRESSION H-BLOCK ACSR 2/0	\$0.66	\$10.56	N
2	2077845	CONNECTOR, COMPRESSION H-BLOCK ACSR 4/0	\$0.68	\$1.36	N
64	2077930	CONNECTOR, VICE CU #4 STR	\$1.91	\$122.24	N
48	2077939	COUPLER, GROUND ROD, F/U/W 1/2"ROD	\$4.78	\$229.44	N
24	2003516	COVER, SNAP-ON SQUEEZON CONNECTOR D DIE	\$0.39	\$9.36	N
16	2003846	CUTOUT, 15KV, 100A FUSE HLDR, 300A UNVRS	\$70.74	\$1,131.84	Υ
7	2077806	FUSE LINK, 10A UNVRSL 100A CUTOUT 23" OA	\$3.91	\$27.37	N
2	2077807	FUSE LINK, 15A UNVRSL 100A CUTOUT 23" OA	\$3.93	\$7.86	N
2	2077804	FUSE LINK, 5A UNVRSL 100A CUTOUT 23" OAL	\$3.90	\$7.80	N
5	2077805	FUSE LINK, 7A UNVRSL 100A CUTOUT 23" OAL	\$3.89	\$19.45	N
32	2077965	MOULDING, GROUND WIRE, PVC 1/2 IN X 8 FT	\$1.74	\$55.68	N
16	2007368	PROTECTOR, WILD LIFE, SLIP-ON TYPE	\$5.35	\$85.60	N
64	2077980	ROD,GROUND,CU BONDED,1/2"X10',THREADLESS	\$13.72	\$878.08	N
16	2077767	ROLLED BOLT, DOUBLE-ARMING, 5/8"X 16"	\$2.65	\$42.40	N
16	2077789	SCREW, LAG PILOT POINT 3/8 X 3	\$0.27	\$4.32	N
16	2077812	SPACER, CABLED SECONDARY	\$6.79	\$108.64	N
140	2077997	STAPLE, SECURES 1/2" PVC MOULDING TO WOO	\$0.27	\$37.80	N
2	2001367	TX,OH,25 kVA,7.62/13.2Y,120/240,FR3	\$1,046.46	\$2,092.92	Υ
5	2001368	TX,OH,37.5 kVA,7.62/13.2Y,120/240,FR3	\$1,253.83	\$6,269.15	Υ
7	2001369	TX,OH,50 kVA,7.62/13.2Y,120/240,FR3	\$1,463.60	\$10,245.20	Υ
2	2001370	TX,OH,75 kVA,7.62/13.2Y,120/240,FR3	\$1,924.56	\$3,849.12	Υ
80	2078006	WASHER, FLAT, GALVANIZED, 2" X 2" X 1/8"	\$0.24	\$19.20	N
48	2078014	WIRE, ALUMINUM, TIE, #4 BARE ANNEALED	\$0.11	\$5.28	N
50	2004184	WIRE, COPPER, BARE, #4 SOFT DRAWN 7 STR	\$0.63	\$31.75	N
160	2078011	WIRE, COPPER, TIE, #6 SOLID SOFT DRAWN	\$0.38	\$60.80	N
			Total	\$27,751.80	



### Estimate Summary Design Number 1

**Contact Name:** Tampa Electric

Distribution Services HDOH PRIMARY

**Printed Date: 3/11/2021** 

District: CSA

WR No. 925112 Date Sched: 4/1/21 Date Required: 4/1/21

Additional Information: Full PSC Filing 10/2010 WR Description: HDOH 1250 sq ft PRIMARY

INSTALLATION:	Capital	Oper./Maint.	Total
MATERIAL:	\$2,267.12	\$0.00	\$2,267.12
OVERHEAD:	\$313.55	\$0.00	\$313.55
	\$2,580.67	\$0.00	\$2,580.67
LABOR HOURS:	73.22	0	73.22
LABOR COST:	\$3,223.42	\$0.00	\$3,223.42
OVERHEAD:	\$4,271.04	\$0.00	\$4,271.04
	\$7,494.46	\$0.00	\$7,494.46
VEHICLE:	\$0.00	\$0.00	\$0.00
CONTRACTOR:	\$0.00	\$0.00	\$0.00
ADDITIONAL ITEMS:	\$0.00	\$0.00	\$0.00
SUBTOTAL:	\$10,075.13	\$0.00	\$10,075.13
REMOVAL:			
MATERIAL:	\$0.00	\$0.00	\$0.00
OVERHEAD:	\$0.00	\$0.00	\$0.00
	\$0.00	\$0.00	\$0.00
LABOR HOURS:	0	0	0
LABOR COST:	\$0.00	\$0.00	\$0.00
OVERHEAD:	\$0.00	\$0.00	\$0.00
	\$0.00	\$0.00	\$0.00
VEHICLE:	\$0.00	\$0.00	\$0.00
CONTRACTOR:	\$0.00	\$0.00	\$0.00
ADDITIONAL ITEMS:	\$0.00	\$0.00	\$0.00
SUBTOTAL:	\$0.00	\$0.00	\$0.00
TRANSFER:			
	0	0	•
LABOR HOURS: LABOR COST:	0	0	0
OVERHEAD:	\$0.00	\$0.00	\$0.00
OVERTIEND.	\$0.00	\$0.00	\$0.00
	\$0.00	\$0.00	\$0.00
VEHICLE:	\$0.00	\$0.00	\$0.00
CONTRACTOR:	\$0.00	\$0.00	\$0.00
ADDITIONAL ITEMS:	\$0.00	\$0.00	\$0.00
SUBTOTAL:	\$0.00	\$0.00	\$0.00
TOTALS:	\$10,075.13	\$0.00	\$10,075.13



# Work Request Material Summary \*\*\*Includes Truck Stock\*\*\*

Design Number 1

**Printed Date: 3/11/2021** Dist: CSA

WR No. 925112

Materi	al Number	Description	Unit Price	<b>Total Cost</b>	Asset?
INSTALL					
3	2003646	ARRESTER, DISTRIBUTION, 10KV, 8.4KV MCOV	\$39.68	\$119.04	Υ
2	2077738	BOLT, 5/8" X 8" EYE GALV RTS 12,400 LBS.	\$2.99	\$5.98	N
4	2077739	BOLT, EYE, 5/8 IN. X 10 IN., GALVANIZED	\$3.12	\$12.48	N
2	2077744	BOLT, MACHINE 1/2 INCH X 7 INCH	\$0.92	\$1.84	N
4	2077754	BOLT, MACHINE 5/8" X 10", GALV. FULL	\$1.04	\$4.16	N
1	2077756	BOLT,MACHINE,SQ HEAD,5/8"X14",ONE SQ NUT	\$1.29	\$1.29	N
3	2003681	BRACKET, "L", LIGHTNING ARRESTER 10 KV	\$7.95	\$23.85	N
2	2004660	BRACKET,"L" 5-5/8"IN LENGTH FOR MTG CUTO	\$10.41	\$20.82	N
8	2077818	CLAMP, DEADEND ACSR OR AAC #2-4/0OR .30-	\$9.12	\$72.96	N
3	2077906	CLAMP, GROUND ROD, F/U/W 1/2"ROD	\$1.80	\$5.40	N
9	2077911	CLAMP, HOT LINE CU TO CU #6 SOL- 2 STR T	\$5.73	\$51.57	N
3	2077813	CLAMP, SLACK SPAN DEADEND #2 ACSR - 2/0	\$10.09	\$30.27	N
6473	2004331	CONDUCTOR, BARE OVERHEAD, 2 AWG, AAAC, 7	\$0.15	\$971.00	Υ
120	2078012	CONDUCTOR, COPPERCLAD, 3 STR. #9, DSA 30	\$0.84	\$100.80	N
11	2077838	CONNECTOR, COMPRESSION H-BLOCK ACSR #2-1	\$0.41	\$4.51	N
7	2077837	CONNECTOR, COMPRESSION H-BLOCK ACSR 2/0	\$0.66	\$4.62	N
6	2077930	CONNECTOR, VICE CU #4 STR	\$1.91	\$11.46	N
9	2077939	COUPLER, GROUND ROD, F/U/W 1/2"ROD	\$4.78	\$43.02	N
1	2002955	CROSSARM, 5' DEADEND COMPOSITE	\$116.70	\$116.70	N
2	2003846	CUTOUT, 15KV, 100A FUSE HLDR, 300A UNVRS	\$70.74	\$141.48	Υ
2	2077794	FUSE LINK, 103A UNVRSL 100A CUTOUT 23" O	\$24.29	\$48.58	N
1	2077954	INSULATOR, PIN TYPE, 10KV, ANSI CLASS 55	\$3.75	\$3.75	N
2	2003882	INSULATOR, POLYMER VERTICAL LINE POST 25	\$50.80	\$101.60	N
4	2077959	INSULATOR, SUSPENSION, POLYMER, 25KV, AP	\$11.86	\$47.44	N
6	2077965	MOULDING, GROUND WIRE, PVC 1/2 IN X 8 FT	\$1.74	\$10.44	N
5	2077783	NUT, EYE, STANDARD, 1-1/2" GALVANIZED FO	\$1.51	\$7.55	N
1	2077971	PIN, CROSSARM 5/8" X 6-1/2" BOLT, 1" LEA	\$5.16	\$5.16	N
12	2077980	ROD,GROUND,CU BONDED,1/2"X10',THREADLESS	\$13.72	\$164.64	N
3	2077789	SCREW, LAG PILOT POINT 3/8 X 3	\$0.27	\$0.81	N
30	2077997	STAPLE, SECURES 1/2" PVC MOULDING TO WOO	\$0.27	\$8.10	N
2	2077828	STIRRUP, AL BODY & CU BAIL 1/0-397	\$17.19	\$34.38	N
7	2077826	STIRRUP, AL BODY & CU BAIL 2-4/0	\$10.18	\$71.26	N
2	2004029	STUD-LINEPOST INSULATOR 3/4"X5/8 7"BOLT	\$4.09	\$8.18	N
1	9999999	USED AS A STOCK NUMBER PLACEHOLDER	\$0.00	\$0.00	N
4	2078005	WASHER, FLAT, GALVANIZED, 2" X 2" X 1/8	\$0.23	\$0.92	N
13	2078006	WASHER, FLAT, GALVANIZED, 2" X 2" X 1/8"	\$0.24	\$3.12	N
2	2008135	WASHER, LOCK T316SS 1/2 IN	\$0.18	\$0.36	N
3	2004184	WIRE, COPPER, BARE, #4 SOFT DRAWN 7 STR	\$0.63	\$1.89	N
15	2078011	WIRE, COPPER, TIE, #6 SOLID SOFT DRAWN	\$0.38	\$5.70	N
			Total	\$2,267.12	



Estimate Summary
Design Number 1

Distribution Services HDOH POLES **Contact Name:** Tampa Electric

**Printed Date: 3/11/2021** 

District: CSA

WR No. 925113

Date Sched: 4/1/21 Date Required: 4/1/21

Additional Information: Full PSC Filing 10/2010 WR Description: HDOH 1250 sq ft POLES

INSTALLATION:	Capital	Oper./Maint.	Total
MATERIAL:	\$20,059.40	\$0.00	\$20,059.40
OVERHEAD:	\$2,774.22	\$0.00	\$2,774.22
	\$22,833.62	\$0.00	\$22,833.62
LABOR HOURS:	427.97	0	427.97
LABOR COST:	\$18,838.88	\$0.00	\$18,838.88
OVERHEAD:	\$24,961.48	\$0.00	\$24,961.48
	\$43,800.36	\$0.00	\$43,800.36
VEHICLE:	\$0.00	\$0.00	\$0.00
CONTRACTOR:	\$0.00	\$0.00	\$0.00
ADDITIONAL ITEMS:	\$0.00	\$0.00	\$0.00
SUBTOTAL:	\$66,633.98	\$0.00	\$66,633.98
REMOVAL:			
MATERIAL:	\$0.00	\$0.00	\$0.00
OVERHEAD:	\$0.00	\$0.00	\$0.00
	\$0.00	\$0.00	\$0.00
LABOR HOURS:	0	0	0
LABOR COST:	\$0.00	\$0.00	\$0.00
OVERHEAD:	\$0.00	\$0.00	\$0.00
	\$0.00	\$0.00	\$0.00
VEHICLE:	\$0.00	\$0.00	\$0.00
CONTRACTOR:	\$0.00	\$0.00	\$0.00
ADDITIONAL ITEMS:	\$0.00	\$0.00	\$0.00
SUBTOTAL:	\$0.00	\$0.00	\$0.00
TRANSFER:			
LABOR HOURS:	0	0	0
LABOR COST:	\$0.00	\$0.00	\$0.00
OVERHEAD:	\$0.00	\$0.00	\$0.00
	\$0.00	\$0.00	\$0.00
VEHICLE:	\$0.00	\$0.00	\$0.00
CONTRACTOR:	\$0.00	\$0.00	\$0.00
ADDITIONAL ITEMS:	\$0.00	\$0.00	\$0.00
SUBTOTAL:	\$0.00	\$0.00	\$0.00
TOTALS:	\$66,633.98	\$0.00	\$66,633.98



## Work Request Material Summary \*\*\*Includes Truck Stock\*\*\*

Design Number 1

**Printed Date: 3/11/2021** Dist: CSA

WR No. 925113

			1 ago 1 oi 1		
Mate	rial Numbe	er Description	Unit Price	Total Cost	Asset?
INSTALL					
29	2003632	ANCHOR,SCRW GALV 10" WING 1-1/4" ROD 8"	\$48.15	\$1,396.35	N
20	2077739	BOLT, EYE, 5/8 IN. X 10 IN., GALVANIZED	\$3.12	\$62.40	N
62	2077764	BOLT, MACHINE 3/4" X 12", GALV	\$2.41	\$149.42	N
40	2077754	BOLT, MACHINE 5/8" X 10", GALV. FULL	\$1.04	\$41.60	Ν
19	2077753	BOLT, MACHINE 5/8" X 8", GALV.	\$1.05	\$19.95	N
1	2077780	BOLT, SPOOL, 5/8" X 10", GALV. SINGLE UP	\$4.16	\$4.16	N
45	2077755	BOLT,MACHINE,SQ HEAD,5/8"X12",ONE SQ NUT	\$1.16	\$52.20	Ν
8	2003686	BRACKET, FIBERGLASS STANDOFF VERTICAL24"	\$48.88	\$391.04	Ν
7	2077818	CLAMP, DEADEND ACSR OR AAC #2-4/0OR .30-	\$9.12	\$63.84	Ν
13	2003508	CLAMP, SUSPENSION AL ANGLE RANGE .50 TO	\$13.95	\$181.35	N
19	2077924	CLEVIS, STEEL LESS INSULATOR 5/8 IN PIN	\$9.38	\$178.22	N
105	2078012	CONDUCTOR, COPPERCLAD, 3 STR. #9, DSA 30	\$0.84	\$88.20	N
25	2077837	CONNECTOR, COMPRESSION H-BLOCK ACSR 2/0	\$0.66	\$16.50	N
21	2077930	CONNECTOR, VICE CU #4 STR	\$1.91	\$40.11	N
2	2077765	DOUBLE-ARMING, GALVANIZED 5/8 "X 12"	\$2.35	\$4.70	N
29	2003636	EXTENSION ROD, ANCHOR 1-1/4 X 72 6 FT	\$50.54	\$1,465.66	N
27	2077901	FIBERGLASS RIDGE-PIN	\$28.87	\$779.49	N
120	2077949	GRIP,GUY,FORMED WIRE DEADEND,3/8"EHS	\$2.27	\$272.40	N
22	2077862	GUARD, LINE #2 ACSR & AAAC STR 6/1, 7	\$1.95	\$42.90	N
3	2077863	GUARD, LINE 2/0 ACSR & AAAC STR 6/1, 7	\$2.68	\$8.04	N
62	2077951	HOOK, GUY	\$2.73	\$169.26	N
35	2077954	INSULATOR, PIN TYPE, 10KV, ANSI CLASS 55	\$3.75	\$131.25	N
1	2077952	INSULATOR, SPOOL, ANSI CLASS 53-3, TRANS	\$1.21	\$1.21	N
33	2077961	INSULATOR, STRAIN FIBERGLASS 36 IN 15,00	\$14.73	\$486.09	N
19	2077959	INSULATOR, SUSPENSION, POLYMER, 25KV, AP	\$11.86	\$225.34	N
29	2077979	MARKER, GUY WIRE PLASTIC 8' IN LENGTH CO	\$4.43	\$128.47	N
42	2002857	POLE, WOOD, 40FT CLASS 2, CCA TREATED	\$272.68	\$11,452.56	Υ
2	2002858	POLE, WOOD, 45 FT CLASS 2, CCA TREATED.	\$323.31	\$646.62	Υ
23	2077767	ROLLED BOLT, DOUBLE-ARMING, 5/8"X 16"	\$2.65	\$60.95	N
62	2077790	SCREW, LAG 1/2" X 4", GALV., TWIST DRIVE	\$0.47	\$29.14	N
48	2077812	SPACER, CABLED SECONDARY	\$6.79	\$325.92	N
7	2003612	TIE, PREFORMED SIDE TIE #2 ACSR OR #2 A	\$2.64	\$18.48	N
28	2003613	TIE, TOP, FORMED WIRE #2 ACSR OR #2 AAAC	\$2.87	\$80.36	N
62	2078002	WASHER, CURVED, MALLEABLE, 3" X 3"	\$1.22	\$75.64	N
156	2078006	WASHER, FLAT, GALVANIZED, 2" X 2" X 1/8"	\$0.24	\$37.44	N
146	2078014	WIRE, ALUMINUM, TIE, #4 BARE ANNEALED	\$0.11	\$16.06	N
2776	2005879	WIRE,GUY,EHS STEEL,GALV,3/8",15.4K RBS	\$0.33	\$916.08	N
			Total	\$20,059.40	



### Estimate Summary Design Number 1

Dist Eng HDOH SECONDARY

**Printed Date:** 3/11/2021

District: CSA

WR No. 925114

Date Sched: 4/1/21 Date Required: 4/1/21

Additional Information: Full PSC Filing 10/2010 WR Description: HDOH 1250 sq ft SECONDARY

	<u> </u>		
INSTALLATION:	Capital	Oper./Maint.	Total
MATERIAL:	\$11,334.69	\$0.00	\$11,334.69
OVERHEAD:	\$1,567.60	\$0.00	\$1,567.60
	\$12,902.29	\$0.00	\$12,902.29
LABOR HOURS:	221.46	0	221.46
LABOR COST:	\$9,748.02	\$0.00	\$9,748.02
OVERHEAD:	\$12,916.13	\$0.00	\$12,916.13
	\$22,664.15	\$0.00	\$22,664.15
VEHICLE:	\$0.00	\$0.00	\$0.00
CONTRACTOR:	\$0.00	\$0.00	\$0.00
ADDITIONAL ITEMS:	\$0.00	\$0.00	\$0.00
SUBTOTAL:	\$35,566.44	\$0.00	\$35,566.44
REMOVAL:			
MATERIAL:	\$0.00	\$0.00	\$0.00
OVERHEAD:	\$0.00	\$0.00	\$0.00
	\$0.00	\$0.00	\$0.00
LABOR HOURS:	0	0	0
LABOR COST:	\$0.00	\$0.00	\$0.00
OVERHEAD:	\$0.00	\$0.00	\$0.00
	\$0.00	\$0.00	\$0.00
VEHICLE:	\$0.00	\$0.00	\$0.00
CONTRACTOR:	\$0.00	\$0.00	\$0.00
ADDITIONAL ITEMS:	\$0.00	\$0.00	\$0.00
SUBTOTAL:	\$0.00	\$0.00	\$0.00
TRANSFER:			
LABOR HOURS:	0	0	0
LABOR COST:	\$0.00	\$0.00	\$0.00
OVERHEAD:	\$0.00	\$0.00	\$0.00
	\$0.00	\$0.00	\$0.00
VEHICLE:	\$0.00	\$0.00	\$0.00
CONTRACTOR:	\$0.00	\$0.00	\$0.00
ADDITIONAL ITEMS:	\$0.00	\$0.00	\$0.00
SUBTOTAL:	\$0.00	\$0.00	\$0.00
TOTALS:	\$35,566.44	\$0.00	\$35,566.44



## Work Request Material Summary \*\*\*Includes Truck Stock\*\*\*

Design Number 1

**Printed Date: 3/11/2021** Dist: CSA

WR No. 925114

			i ago	1 01 1	
Mate	erial Numbe	r Description	Unit Price	Total Cost	Asset?
NSTALL					
1	2003632	ANCHOR,SCRW GALV 10" WING 1-1/4" ROD 8"	\$48.15	\$48.15	N
10	2077739	BOLT, EYE, 5/8 IN. X 10 IN., GALVANIZED	\$3.12	\$31.20	N
11	2077764	BOLT, MACHINE 3/4" X 12", GALV	\$2.41	\$26.51	N
1	2077755	BOLT,MACHINE,SQ HEAD,5/8"X12",ONE SQ NUT	\$1.16	\$1.16	N
5413	2004338	CABLE, OVERHEAD SECONDARY, TRIPLEX, 2/0	\$1.15	\$6,224.72	Υ
1013	2004364	CABLE, SERVICE DROP AL 2-2/0 & 1-1/0 NEU	\$0.96	\$972.77	Υ
43	2077818	CLAMP, DEADEND ACSR OR AAC #2-4/0OR .30-	\$9.12	\$392.16	N
3	2003770	CLAMP, MID SPAN ALUMINUM 1/4 IN - 1/2 IN	\$7.09	\$21.27	N
236	2004331	CONDUCTOR, BARE OVERHEAD, 2 AWG, AAAC, 7	\$0.15	\$35.45	Υ
129	2077839	CONNECTOR, COMPRESSION H-BLOCK ACSR 1/0-	\$0.53	\$68.37	N
8	2077837	CONNECTOR, COMPRESSION H-BLOCK ACSR 2/0	\$0.66	\$5.28	N
8	2077931	CONNECTOR, VICE CU #2 STR	\$2.38	\$19.04	N
86	2003516	COVER, SNAP-ON SQUEEZON CONNECTOR D DIE	\$0.39	\$33.54	N
1	2003636	EXTENSION ROD, ANCHOR 1-1/4 X 72 6 FT	\$50.54	\$50.54	N
12	2077949	GRIP,GUY,FORMED WIRE DEADEND,3/8"EHS	\$2.27	\$27.24	N
11	2077951	HOOK, GUY	\$2.73	\$30.03	N
10	2077961	INSULATOR, STRAIN FIBERGLASS 36 IN 15,00	\$14.73	\$147.30	N
1	2077979	MARKER, GUY WIRE PLASTIC 8' IN LENGTH CO	\$4.43	\$4.43	N
37	2077783	NUT, EYE, STANDARD, 1-1/2" GALVANIZED FO	\$1.51	\$55.87	N
19	2002842	POLE, WOOD, 35 FT, CLASS 4, CCA TREATED.	\$141.93	\$2,696.67	Υ
19	2077767	ROLLED BOLT, DOUBLE-ARMING, 5/8"X 16"	\$2.65	\$50.35	N
11	2077790	SCREW, LAG 1/2" X 4", GALV., TWIST DRIVE	\$0.47	\$5.17	N
19	2077812	SPACER, CABLED SECONDARY	\$6.79	\$129.01	N
11	2078002	WASHER, CURVED, MALLEABLE, 3" X 3"	\$1.22	\$13.42	N
50	2078006	WASHER, FLAT, GALVANIZED, 2" X 2" X 1/8"	\$0.24	\$12.00	N
57	2078014	WIRE, ALUMINUM, TIE, #4 BARE ANNEALED	\$0.11	\$6.27	N
16	2004184	WIRE, COPPER, BARE, #4 SOFT DRAWN 7 STR	\$0.63	\$10.08	N
657	2005879	WIRE,GUY,EHS STEEL,GALV,3/8",15.4K RBS	\$0.33	\$216.81	N
			Total	\$11,334.69	



### Estimate Summary Design Number 1

Distribution Services HDOH SERVICE

**Printed Date: 3/11/2021** 

District: CSA

WR No. 927142

Date Sched: 4/1/21 Date Required: 4/1/21

Additional Information: Full PSC Filing 10/2010 WR Description: HDOH 1250 sq ft SERVICE

INSTALLATION:	Capital	Oper./Maint.	Total
MATERIAL:	\$9,216.02	\$0.00	\$9,216.02
OVERHEAD:	\$1,274.57	\$0.00	\$1,274.57
	\$10,490.59	\$0.00	\$10,490.59
LABOR HOURS:	151.98	0	151.98
LABOR COST:	\$6,690.19	\$0.00	\$6,690.19
OVERHEAD:	\$8,864.50	\$0.00	\$8,864.50
	\$15,554.69	\$0.00	\$15,554.69
VEHICLE:	\$0.00	\$0.00	\$0.00
CONTRACTOR:	\$0.00	\$0.00	\$0.00
ADDITIONAL ITEMS:	\$0.00	\$0.00	\$0.00
SUBTOTAL:	\$26,045.28	\$0.00	\$26,045.28
REMOVAL:			
MATERIAL:	\$0.00	\$0.00	\$0.00
OVERHEAD:	\$0.00	\$0.00	\$0.00
	\$0.00	\$0.00	\$0.00
LABOR HOURS:	0	0	0
LABOR COST:	\$0.00	\$0.00	\$0.00
OVERHEAD:	\$0.00	\$0.00	\$0.00
	\$0.00	\$0.00	\$0.00
VEHICLE:	\$0.00	\$0.00	\$0.00
CONTRACTOR:	\$0.00	\$0.00	\$0.00
ADDITIONAL ITEMS:	\$0.00	\$0.00	\$0.00
SUBTOTAL:	\$0.00	\$0.00	\$0.00
TRANSFER:			
LABOR HOURS:	0	0	0
LABOR COST:	\$0.00	\$0.00	\$0.00
OVERHEAD:	\$0.00	\$0.00	\$0.00
	\$0.00	\$0.00	\$0.00
VEHICLE:	\$0.00	\$0.00	\$0.00
CONTRACTOR:	\$0.00	\$0.00	\$0.00
ADDITIONAL ITEMS:	\$0.00	\$0.00	\$0.00
SUBTOTAL:	\$0.00	\$0.00	\$0.00
TOTALS:	\$26,045.28	\$0.00	\$26,045.28



## Work Request Material Summary \*\*\*Includes Truck Stock\*\*\*

Design Number 1

**Printed Date: 3/11/2021** 

Dist: CSA

WR No. 927142

			•		
Mat	erial Number	Description	Unit Price	Total Cost	Asset?
INSTALL					
9408	2004364	CABLE, SERVICE DROP AL 2-2/0 & 1-1/0 NEU	\$0.96	\$9,031.68	Υ
0	2004366	CABLE, SERVICE DROP AL 2-4/0 & 1-2/0 NEU	\$1.42	\$0.00	Υ
26	2003770	CLAMP, MID SPAN ALUMINUM 1/4 IN - 1/2 IN	\$7.09	\$184.34	N
			Total	\$9,216.02	



#### **Estimate Summary**

Design Number 1

Dist Svcs HDOH METERS **Printed Date: 3/11/2021** 

District: CSA

WR No. 927163

Date Sched: 4/1/21 Date Required: 4/1/21

Additional Information: Full PSC Filing 10/2010 WR Description: HDOH 1250 sq ft METERS

INSTALLATION:	Capital	Oper./Maint.	Total
MATERIAL:	\$0.00	\$0.00	\$0.00
OVERHEAD:	\$0.00	\$0.00	\$0.00
	\$0.00	\$0.00	\$0.00
LABOR HOURS:	35.27	0	35.27
LABOR COST:	\$1,552.59	\$0.00	\$1,552.59
OVERHEAD:	\$2,057.18	\$0.00	\$2,057.18
	\$3,609.77	\$0.00	\$3,609.77
VEHICLE:	\$0.00	\$0.00	\$0.00
CONTRACTOR:	\$0.00	\$0.00	\$0.00
ADDITIONAL ITEMS:	\$0.00	\$0.00	\$0.00
SUBTOTAL:	\$3,609.77	\$0.00	\$3,609.77
REMOVAL:			
MATERIAL:	\$0.00	\$0.00	\$0.00
OVERHEAD:	\$0.00	\$0.00	\$0.00
	\$0.00	\$0.00	\$0.00
LABOR HOURS:	0	0	0
LABOR COST:	\$0.00	\$0.00	\$0.00
OVERHEAD:	\$0.00	\$0.00	\$0.00
	\$0.00	\$0.00	\$0.00
VEHICLE:	\$0.00	\$0.00	\$0.00
CONTRACTOR:	\$0.00	\$0.00	\$0.00
ADDITIONAL ITEMS:	\$0.00	\$0.00	\$0.00
SUBTOTAL:	\$0.00	\$0.00	\$0.00
TRANSFER:			
LABOR HOURS:	0	0	0
LABOR COST:	\$0.00	\$0.00	\$0.00
OVERHEAD:	\$0.00	\$0.00	\$0.00
	\$0.00	\$0.00	\$0.00
VEHICLE:	\$0.00	\$0.00	\$0.00
CONTRACTOR:	\$0.00	\$0.00	\$0.00
ADDITIONAL ITEMS:	\$0.00	\$0.00	\$0.00
SUBTOTAL:	\$0.00	\$0.00	\$0.00
TOTALS:	\$3,609.77	\$0.00	\$3,609.77

Differential costs for single phase (1ø) services from an overhead source

OVERHEAD SERVICE

OH Service Material Cost Per Foot

OH Service Cable - Fixed Cost

Fixed Cost = TEC labor plus Contractor labor cost to install the service cable, includes labor plus overheads and vehicle plus the Net Present Value of Operation Cost with Storm Cost.

OH Service - Net Present Value of Operation Cost with Storm Cost \$104.26 \$151.14 Labor cost to install 4/0 triplex service cable \$151.92

OH SERVICE CABLE - Cost Table

 
 Metallation Cost

 OH Description
 Fixed
 Per Fo

 1e - 2/0 AWG Triplex
 \$104.26
 +\$151.14=
 \$255.40
 \$1.36

 1e - 4/0 AWG Triplex
 \$104.26
 +\$151.92=
 \$256.18
 \$2.08
 Per Foot \$1.36 \$2.08

OH Service - Poles
This is the cost to haul a service pole to the site and install an overhead service pole.

Action
Description
Total
Accessible 35 wood pole
Install
Average cost to install a service pole
\$801.36

s the material cost of the	Source - Per Foot Cost conduit and cable in the trench, plus the contra	ictor labor to dig th	ie trench	and install the condu	uit and cable	in the trench,					
the cost of the TEC inspe  Action install install	Description  10 - 210 AWG Triplex 10 - 410 AWG Triplex	UG Cable Material Cost Per Foot \$1.19 \$1.56	+ +	UG Conduit Material Cost Per Foot \$1.45 \$2.36	÷ +	Teco Inspection Labor Per Foot \$1.16 \$1.16	+ +	Contractor labor Machine Trench Per Foot \$9.17 \$9.17	= =	UG Cable Machine Trench Total Cost Per Foo \$12.98 \$14.26	
s the cost for the materia	METER FROM OH SOURCE - Fixed Of down the pole and the material at the house ring on the pole, plus the Net Present Value of Op	ser to the meter ca			install the o	onduit,					
Service - Net Present  Action	Value of Operation Cost with Storm Cos	Material		\$81.58 (Material Handling) Overhead		Contractor <u>Labor</u>		NPV OC + SC		Total Fixed <u>Cost</u>	
install install	1ø - 2/0 AWG Tpx - 2" conduit 1ø - 4/0 AWG Tpx - 3" conduit	\$93.50 \$160.21	+	\$11.42 \$19.58	+	\$87.62 \$87.62	+	\$81.58 \$81.58	=	\$274.12 \$348.99	
	n OH Source - Cost Table										
Service Cable from a						OH So	rvice Eau	iivalent	Installa	ation Cost	Service Differential Co
Service Cable from a	UG Service Cable from an OH Source to a meter can Cable & Conduit With Machine Trench 10 - 2/0 AWG Triplex 10 - 4/0 AWG Triplex	Fixed \$274.12 \$348.99	In	Stallation Cost   Per Foot   \$12.98   \$14.26		1Ø - 2	escription 2/0 AWG 1/0 AWG	on Triplex	Fixed \$255.40 \$256.18	\$1.36 \$2.08	Fixed         Per F           \$18.72         \$11.           \$92.80         \$12.
	Source to a meter can Cable & Conduit With Machine Trench 10 - 2/0 AWG Triplex 10 - 4/0 AWG Triplex	\$274.12 \$348.99		<u>Per Foot</u> \$12.98 \$14.26		1Ø - 2	escription 0 AWG	on Triplex	\$255.40	\$1.36	\$18.72 \$11.
erential costs for	Source to a meter can <u>Cable &amp; Conduit With Machine Trench</u> 1ø - 2/0 AWG Triplex	\$274.12 \$348.99 an overhead s		<u>Per Foot</u> \$12.98 \$14.26		1Ø - 2	escription 0 AWG	on Triplex	\$255.40	\$1.36	\$18.72 \$11.

	t - Conversions of single phase (1ø) OH Se is the sum of: 1) the cost to remove whatever overhead facilit	ities exist;			
A40	2) the cost of the remaining book value to				
	remove and the book value, the Customer essentially become				
	new underground service. The OH Service Cable Removal C o calculate the Conversion Cost. The total cost for a custome				
	the applicable Differential Cost for the new underground serv				
underground service is	the applicable billerential Cost for the new underground serv	rice plus tile conversion cost.			
4\ 4ha aa	at to name or other or a comband facilities assist				
1) the co	st to remove whatever overhead facilities exist	Total		Cuetam	
		Removal	Cuetem	System	
	Account to the contract		System	Average	
Action	Average length service	Cost	<u>%</u>	Cost	
remove	1ø - #2 AWG Triplex	\$87.60	10%	\$8.76	
remove	1ø - 2/0 AWG Triplex	\$87.60	70%	\$61.32	
remove	1ø - 4/0 AWG Triplex	\$87.60	20%	\$17.52	
	System Average cost to remove average length 1ø service			\$87.60	
		Total		System	
		Removal	System	Average	J
Action	Service length with a service pole	Cost	<u>%</u>	Cost	J
remove	1ø - #2 AWG Triplex	\$147.57	10%	\$14.76	J
remove	1ø - 2/0 AWG Triplex	\$147.57	70%	\$103.30	
remove	1ø - 4/0 AWG Triplex	\$147.57	20%	\$29.51	
remove	30' wood pole, drive hook	\$303.06	50%	\$151.53	
remove	35' wood pole, drive hook	\$313.38	50%	\$156.69	
	System Average cost to remove average long 1ø service w	vith service pole		\$455.79	
2) the co	st of the remaining book value for those overhea	ad facilities.			
	e Assumptions:				
Dook value	Average depreciation	0.036			
	Age of pole & service, yrs.	11			
	Handy Whitman Ratio, total dist.plant, 2007/2017	0.74			
Rook Value	= (System Value Today) x (Handy Whitman Ratio) x (1 - (Std Dep				
DOOK Value	- (System value Today) x (Halley William Ratio) x (1 - (Sid De)	p. x Age))			
		Total		System	
		Installation	System	Average	
Action	Average length service	Cost	%	Cost	
install	1ø - #2 AWG Triplex	\$219.14	10%	\$21.91	
install	1ø - 2/0 AWG Triplex	\$254.54	70%	\$178.18	
install	1ø - 4/0 AWG Triplex	\$310.07	20%	\$62.01	
ilistali	System Average cost to install average length 1ø service	ψ510.07	2070	\$262.11	
	Book Value for average length 1ø service			\$117.48	
	Book value for average length to service	Total		System	
		Installation	System	Average	
A =4! = =	Coming loweth that requires a coming well				
Action	Service length that requires a service pole	Cost	<u>%</u>	Cost	
install	1ø - #2 AWG Triplex	\$377.23	10%	\$37.72	J
install	1ø - 2/0 AWG Triplex	\$447.11	70%	\$312.98	J
install	1ø - 4/0 AWG Triplex	\$555.30	20%	\$111.06	J
install	35' wood pole, cable spacer	\$606.95	50%	\$303.48	J
	Haul pole to job site	\$194.41	100%	\$194.41	
	System Average cost to install average long 1ø service with	h service pole		\$959.65	J
	Book Value for average long 1ø service with service pole			\$430.12	
			Remove	Book value	Conversion
1a Conversion	Cost from OH to UG service		Cost	Cost	Cost
	00 ft or less(Svc without pole) = (book value + removal)		\$87.60	\$117.48	\$205.08
ile Average Long Servi	ce- Greater than 100 ft (svc with one pole) = (book value + re	emovarj	\$455.79	\$430.12	\$885.91

#### Tariff Sheet No. 5.516 (3.7.2)

	Current			CPI -U		Propos	sed
	Deposit					Depos	sit
Density Class	2018		2018	2019	2020	2021	1
Urban commercial or residential (\$/mile)	\$	9,896	2.40%	1.80%	0.80%	\$ 10,3	391
Rural commercial or residential (\$/mile)	\$	5,657	2.40%	1.80%	0.80%	\$ 5,9	940
Per Lot Subdivisions (\$/lot)	\$	47	2.40%	1.80%	0.80%	\$	49

#### Table I OPERATING COSTS

Ouerhood Planket Associat	New CARE unding resises	2016 Actual \$	2017 Actual \$	2018 Actual \$	2019 Actual \$	2020 Actual \$	5-Yr Average \$	OH Ratio	UG Ratio	5-Yr Average Allocated Overhead \$	5-Yr Average Allocated Underground \$
Overhead - Blanket Account D-CRR-Voltago-OH (NEW) PRE: Dist Line - Fault Indicators Distr - Maint - Corrective - OH Line Distribution - Maint - OH System Improvements Distr - Maint - Corrective - OH Line Distribution - Maint - Mgmt & Coordination Distr - Maint - Perventative - OH Line Distr - Maint - Pele Inspect & Change-Outs Distr - Maint - Pole Inspect & Change-Outs Distr - Maint - Del Inspect & Change-Outs Distr - Maint - Pole Inspect & Change-Outs Distr - Maint - Trouble - Non-Storm Distr - Maint - Troe Trimming - Unplanned Distr - Maint - Troe Trimming - Unplanned Distr - Maint - Indraed Thermography Distr - Maint - Infrared Thermography Distr - Maint - Infrared Thermography	New SAP/Funding project CRR-02630, CRR-02879 PRE-05080 CRR-02682, CRR-03641, PRE-04820  PRE-02805, PRE-02827 CRR-02625, CRR-07052 PRE-02624 CRR-07052 CRR-07072 CRR-07171 CRR-07171 PRE-02631, CRR-02628  PRE-03640 CRR-03640 CRR-02680  Subtotal	\$46.177 \$172,262 \$12,492,806 \$0 \$0 \$4,852,428 \$1,586,273 \$29,189,331 \$1,205,163 \$0 \$0 \$0 \$1,370,240 \$0 \$1,370,240 \$1,370,	\$126,412 \$250,315 \$9,071,353 \$0 \$6,321,911 \$3,889,120 \$25,618,395 \$1,240,937 \$748,303 \$0 \$0 \$232,391 \$620,240 \$25,618,40 \$232,391 \$620,250 \$25,618,40 \$25,	\$5,602 \$9,965,721 \$0 \$6,761,430 \$2,215,981 \$15,267,786 \$1,689,413 \$229,616 \$435,897 \$0 \$0 \$0 \$467,400 \$254,663 \$0 \$7,74,551	\$236,000 \$6,977 \$11,118,166 \$0 \$9,140,424 \$7,584,782 \$19,949,764 \$2,037,373 \$240,114 \$131,914 \$0 \$0 \$0 \$401,509 \$84,313 \$9 \$82,002 \$51,823,336	\$263,090 \$13,005 \$10,246,537 \$0 \$6,448,231 \$687,761 \$11,097,693 \$2,655,044 \$512,584 \$298,534 \$0 \$0 \$0 \$0 \$67,705 \$0 \$33,690,986	\$169,105 \$89,632 \$10,578,917 \$0 \$6,704,885 \$3,192,733 \$20,224,594 \$1,765,584 \$1,765,584 \$0 \$0 \$0 \$0 \$307,106 \$479,468 \$0 \$85,403 \$43,4	100.0% 100.0% 100.0% 100.0% 100.0% 100.0% 100.0% 100.0% 100.0% 100.0% 0.0%	0.0% 0.0% 0.0% 0.0% 0.0% 0.0% 0.0% 0.0%	\$169,105 \$89,632 \$10,578,917 \$0 \$6,704,885 \$3,192,783 \$20,224,594 \$1,765,596 \$327,438 \$429,409 \$0 \$0 \$0 \$307,106 \$479,468 \$0 \$0	\$0 \$0 \$0 \$0 \$0 \$0 \$0 \$0 \$0 \$0 \$0 \$0 \$0 \$
Underground - Blanket Account D-CRR-Voltage-UG D-CRR-Voltage-UG D-CRR-Voltage-UG D-CRR-Voltage-UG D-CRR-Voltage-UG D-CRR-Voltage-UG Distr-Maint - UG System Improvements Distr-Maint - Maint - Mgm 8 Coordination Distr - Maint - Network Corrective Distr - Maint - Network Crecetive Distr - Maint - Network Crecetive Distr - Maint - Network Preventative Distr - Maint - Network Preventative Distr - Maint - Toughe-UG Storm Distr - Maint - Toughe-UG Storm Distr - Maint - Toughe-UG Storm Distr - Maint - UG Cable Rigitemt - Planned Distr - Maint - UG Cable Rigitemt - UG Line Distr - Maint - UG Cable Rigitemt - Uplanned Distr - Maint - UG Cable Rigitemt - Uplanned Distr - Maint - UG Cable Rigitemt - Uplanned Distr - Maint - Services - UG Line Overhead - O&M Account	CRR-03814 PRE-03623 CRR-02644, CRR-03642  PRE-02809, PRE-02646 CRR-02639 PRE-04557 CRR-02651, PRE-03813 CRR-02649 CRR-02645 CRR-02652 CRR-02679  Subtotal	\$331 \$485,277 \$9,578,832 \$0 \$0 \$1,025,001 \$240,413 \$48,820 \$3,267 \$3,719,963 \$226,400 \$718,093 \$911,653 \$16,958,141	\$393 \$5,792,966 \$11,149,781 \$0 \$1,115,881 \$261,404 \$21,699 \$3,428,731 \$803,417 \$692,148 \$0 \$1,054,181 \$24,310,029	\$3,504,752 \$13,068,396 \$0 \$1,084,178 \$77,136 \$762,566 \$12,430 \$3,724,487 \$838,010 \$586,171 \$1,089,934	\$10,670 \$1,551,277 10,753,405 0 0 \$3,983,848 \$250,177 \$1,290,770 \$396 \$3,944,431 \$629,674 \$1,105,493 \$0 \$895,524 \$24,415,665	\$23,632 \$2,084,383 \$10,427,986 \$0 \$9,506,194 \$33,100 \$25,243 \$53,629 \$2,996,062 \$265,878 \$1,211,387 \$0 \$2,295,60,602 \$2,295,600	\$8,523 \$2,683,731 \$10,995,680 \$0 \$3,343,038 \$172,446 \$423,371 \$18,278 \$3,544,735 \$552,676 \$62,658 \$0 \$952,857 \$23,557,994	0.0% 0.0% 0.0% 0.0% 0.0% 0.0% 0.0% 0.0%	100.0% 100.0% 100.0% 100.0% 100.0% 100.0% 100.0% 100.0% 100.0% 100.0% 100.0% 100.0% 100.0%	\$0 \$0 \$0 \$0 \$0 \$0 \$0 \$0 \$0 \$0 \$0 \$0 \$0 \$	\$8,523 \$2,683,731 \$10,995,680 \$0 \$3,343,038 \$172,446 \$423,7172,446 \$423,544,735 \$552,676 \$862,658 \$0 \$0
D-CRR-Voltage-OH (NEW) Distr -Maint - Corrective - OH Line Distribution - Maint - OH System Improvements Distribution - Maint - Mgmt & Coordination Distr - Maint - Mgmt & Coordination Distr - Maint - Trouble - OH Store Distr - Maint - Trouble - Non-Storm CRR - Dist Line - Recidence / Trip-savers Distr - Maint - Trouble - Non-Storm CRR - Dist Line - Recidence / Trip-savers Distr - Maint - Trouble - Non-Storm Distr - Maint - Troe Trimming - Planned Distr - Maint - Tree Trimming - Unplanned Distr - Maint - Pele CRA & Change-Outs Distr - Maint - Pele CRA & Change-Outs Distr - Maint - Pele CRA & Change-Outs Distr - Maint - Infrared Thermography Distr - Maint - Services - OH Line	CRR-02830, CRR-02879 CRR-02883, CRR-02882  PRE-02827, PRE-02867, PRE-02868 CRR-02625, CRR-02877 PRE-40409, PRE-02659 CRR-02281, CRR-02659 CRR-02283, CRR-02857 CRR-02286, CRR-02857 CRR-02860, CRR-02857 CRR-02860 CRR-03861 PRE-04067 OPS-04740, PRE-04060 CRR-039621 PRE-04062 CRR-02680, CRR-02871 Subtotal	\$36.013 \$6,702,046 \$0 \$338,407 \$1,701,574 \$3,037,800 \$162,903 \$162,907 \$1,971,141 \$4,473 \$10,947,625 \$129,867 \$1,415,113	\$49.248 \$5.549,490 \$0 \$177,398 \$3.374,032 \$906,761 \$109,586 \$238,305 \$2,299,168 \$409,147 \$6,994,398 \$24,955 \$1,443,955 \$0 \$0 \$0 \$771,285 \$22,347,728	\$5,989,559 \$0 \$98,503 \$1,308,631 \$1,929,160 \$178,520 \$190,258 \$2,387,796 \$7 \$10,316,539 \$1,562,584 \$0 \$0 \$786,519	\$61,979 \$6,759,090 \$0 \$176,940 \$1,221,253 \$1,959,009 \$257,726 \$149,581 \$2,807,237 \$13,6336 \$6,425 \$13,767,350 \$13,489 \$2,222,800 \$0 \$0 \$0 \$0 \$0 \$1,959,000 \$2,776,350 \$1,489 \$2,222,800 \$0 \$0 \$0 \$0 \$0 \$1,49,51 \$0 \$0 \$0 \$0 \$1,49,51 \$0 \$0 \$0 \$0 \$0 \$0 \$0 \$0 \$0 \$0 \$0 \$0 \$0	\$45,644 \$7,002,950 \$0 \$124,407 \$593,755 \$904,908 \$184,081 \$29,990 \$2,814,800 \$0 \$16,990,720 \$26,693 \$0 \$0 \$0 \$0 \$1,754 \$1,755	\$46,279 \$6,400,627 \$0 \$1 \$1,539,649 \$1,747,528 \$176,963 \$158,187 \$2,456,028 \$45,451 \$2,190 \$11,803,326 \$43,255 \$1,734,230 \$0 \$0 \$790,488 \$27,267,533	100.0% 100.0% 100.0% 100.0% 100.0% 100.0% 100.0% 100.0% 0.0%	0.0% 0.0% 0.0% 0.0% 0.0% 0.0% 0.0% 0.0%	\$46,279 \$6,400,627 \$0 \$183,131 \$1,639,849 \$1,747,528 \$176,963 \$158,187 \$0 \$0 \$0 \$0 \$43,255 \$0 \$0 \$0 \$0 \$0 \$0 \$0 \$0 \$0 \$0 \$0 \$0 \$0	\$0 \$0 \$0 \$0 \$0 \$0 \$0 \$0 \$0 \$0 \$0 \$0 \$0 \$
Underground - O&M Account D-RE-Transformers-UG Distr - Maint - LO System Improvements Distribution - Maint - UG System Improvements Distribution - Maint - Mgmt & Coordination Distr - Maint - Treventative - UG Line Distr - Maint - Network Corrective Distr - Locate Facilities Distr - Maint - Network Preventative Distr - Locate Facilities Distr - Maint - LUG Cable Rp/cmnt - Planned Distr - Maint - LUG Cable Rp/cmnt - Planned Distr - Maint - Trouble - UG Storm D-CRR-Capacitors-UG D-CRR-Storms-UG Distr - Maint - Damage Replacement - UG Line Distr - Maint - Damage Replacement - UG Line Distr - Maint - Damage Replacement - UG Line	PRE-03623 CRR-02860, CRR-02644  PRE-02869, PRE-02809, PRE-02646, PRE-02870 CRR-02636, CRR-02663 PRE-02686 PRE-04063 CRR-02636, CRR-02649 CRR-02678 CRR-02678 CRR-02678 CRR-02661 CRR-02662 CRR-02662 CRR-02679, CRR-02672  Subtotal	\$834 \$1.500.889 \$0 \$1,5197.377 \$3.992 \$503.523 \$997.466 \$76.868 \$0 \$1,429 \$5,697 \$3,929.366	\$2,330 \$1,524,122 \$0 \$197,174 \$9,010 \$405,693 \$792,820 \$80,912 \$115,240 \$4,698 \$683 \$26,921 \$0 \$3,40,185	\$1,549,934 \$0 \$0 \$306,486 \$20,524 \$513,913 \$760,488 \$127,829 \$120,874 \$0 \$0 \$103,901 \$0 \$423,145	\$0 1,449,637 \$0 \$00,272 \$7,379 \$635,686 \$912,001 \$71,431 \$29,492 \$773 \$0 \$173,424 \$0 \$654,095 \$4,234,190	\$0 \$1,710,255 \$0 \$220,874 \$5,573 \$660,604 \$348,183 \$23,766 \$19,316 \$0 \$0 \$714,701 \$0 \$712,258 \$4,475,530	\$1,329 \$1,546,768 \$0 \$0 \$244,437 \$9,296 \$543,884 \$882,179 \$80,281 \$72,358 \$1,094 \$422 \$96,929 \$0 \$534,710 \$4,013,685	0.0% 0.0% 0.0% 0.0% 0.0% 0.0% 0.0% 0.0%	100.0% 100.0% 100.0% 100.0% 100.0% 100.0% 100.0% 100.0% 100.0% 100.0% 100.0% 100.0%	\$0 \$0 \$0 \$0 \$0 \$0 \$0 \$0 \$0 \$0 \$0 \$0 \$0 \$	\$1,329 \$1,546,768 \$0 \$0 \$244,437 \$9,296 \$543,864 \$882,179 \$80,281 \$72,358 \$1,094 \$422 \$96,929 \$0 \$0 \$0

#### <u>Table II</u> PRIMARY VOLTAGE SYSTEM

Distribution - Maint - Trouble Calls - Non-storm	2016 Actual \$	2017 Actual \$	2018 Actual \$	2019 Actual \$	2020 Actual \$	5-Yr Average \$	OH Ratio	UG Ratio	Allocated Overhead \$	Allocated Underground \$
Blanket O&M	\$0 \$1,971,141	\$0 \$2,299,168		\$0 \$2,807,237	\$0 \$2,814,800	\$0 \$2,456,028	77.7% 77.7%	22.3% 22.3%	\$0 \$1,908,334	\$0 \$547,694
Operating Cost Total from Table I					(A)	) 5 Yr Avg Annual	Operatio	nal Cost	\$54,664,741 \$56,573,076	\$26,084,112 <b>\$26,631,806</b>
Distr - Maint - Tree Trimming - Planned	2016 Actual \$	2017 Actual \$	2018 Actual \$	2019 Actual \$	2020 Actual \$	5-Yr Average \$	OH Ratio	UG Ratio	Allocated Overhead \$	Allocated Underground \$
Blanket O&M Distr - Maint - Tree Trimming - Unplanned	\$0 \$10,947,625	\$0 \$6,994,398	\$0 \$10,316,539	\$0 \$13,767,350	\$0 \$16,990,720	\$0 \$11,803,326	96.1% 96.1%	3.9% 3.9%	\$0 \$11,343,279	\$0 \$460,047
Blanket O&M	\$0 \$1,415,113	\$0 \$1,443,955		\$0 \$2,222,800	\$0 \$2,026,699	\$0 \$1,734,230	96.1% 96.1%	3.9% 3.9%	\$0 \$1,666,637	\$0 \$67,593
					(B) 5 '	Yr Avg Annual Lir	ne Clearar	ice Cost	\$13,009,916	\$527,640
Annual Estimated Storm Costs Storm Damage Annual Accrual Percent for Distribution Lines & Substations Percent for Substations Percent for Distribution Lines Overall Distribution Percent										
Storm Cost Distribution Lines	\$ 8,948,000.0	\$ 92,818,327.0	\$43,133	\$7,219,800	\$794,787	\$ 21,964,810 (C) Estimated A			\$21,086,217 \$21,086,217	\$107,436 <b>\$107,436</b>
Pole Attachment Revenue	\$4,315,418	\$4,375,284	\$4,429,688	\$4,495,861	\$4,591,960 (D) 5 Yr Avg	\$4,441,642 3 Annual Pole Atta		0.0% _ Revenue	\$4,441,642 \$4,441,642	\$0 \$0
Table III SERVICE CONDUCTOR										
Distr - Maint - Services - OH Line Blanket O&M	\$833,061 \$746,690	\$825,826 \$771,285		\$892,002 \$808,204	\$966,573 \$839,741	\$858,403 \$790,488	100.0% 100.0%	0.0% 0.0%	\$858,403 \$790,488	\$0 \$0
Distr - Maint - Services - UG Line Blanket O&M	\$911,653 \$543,869			\$895,524 \$654,095	\$812,991 \$712,258	\$952,857 \$534,710	0.0% 0.0%	100.0% 100.0%	\$0 \$0	\$952,857 \$534,710
					(A)	5 Yr Avg Annual	Operatio	nal Cost	\$1,648,890	\$1,487,567
<u>Table IV</u> <u>ALLOCATION FACTORS</u>										
Line Clearance 2020 No. of company owned distribution poles 2020 No. of Terminal Poles on System	418,770 16,322									
Distribution - Maint - Trouble Calls - Non-storm		2020	2020							
No Outage Events (N) Outage Sys Avg Duration (L-Bar) Trouble Calls Weighted Avg Proportion (N) X (L-Bar) Allocation Percentage	2020 Entire System 9,810 166.49 1,633,267									
Service Count (Based on Metered Accounts)	No of Services (E	Based on Metered	Accounts)							
Overhead Single & Three Phase (Excluding Multi-Family) Underground Single Phase (Excluding Multi-Family)	246,960 284,735									

#### <u>Table V (A)</u> <u>NET PRESENT VALUE LIFECYCLE COST CALCULATION</u> (Primary Voltage System - Installation of Facilities In Subdivisions)

Assumptions: Inflation Rate 0.80 % 6.70 % 35 Yrs 2.1 % Discount Rate Book Life Pole Attach Revenue Increase

				Overhead S	system			Overhead System									
Yr	(A) 3 Yr Avg Annual Operational Cost (\$)	(D) 3 Yr Avg Annual Pole Attachment Revenue (\$)	(A)+(D) 3 Yr Avg Annual Operational Cost Incl Lost Attachment Revenue(\$)	(B) 3 Yr Avg Annual Line Clearance Cost (\$)	(C) Estimated Annual Storm Cost (\$)	+(B)+(C)+ (D) PV Incl Storm (\$)	(A)+(B)+(D) <u>NPV Excl Storm</u> (\$)	(C) NPV Storm Only (\$)									
1	\$ 56,573,076	\$ (4,441,642)	\$ 52,131,433	\$ -	\$ 21,086,217	\$ 73,217,650	\$52,131,433	\$21,086,217									
2	57,025,660			-	21,254,907	\$ 69,113,388	\$49,193,138	\$19,920,250									
3	57,481,865	(4,633,552)		-	21,424,946	\$ 65,238,452	\$46,419,696	\$18,818,755									
4	57,941,720	(4,732,594)		_	21,596,346	\$ 61,580,060	\$43,801,892	\$17,778,168									
5	58,405,254	(4,833,753)		-	21,769,116	\$ 58,126,142	\$41,331,021	\$16,795,121									
6	58,872,496	(4,937,075)		-	21,943,269	\$ 54,865,297	\$38,998,866	\$15,866,431									
7	59,343,476	(5,042,605)		-	22,118,816	\$ 51,786,760	\$36,797,667	\$14,989,093									
8	59,818,224	(5,150,390)		-	22,295,766	\$ 48,880,364	\$34,720,097	\$14,160,268									
9	60,296,770	(5,260,480)	\$ 55,036,290	-	22,474,132	\$ 46,136,511	\$32,759,238	\$13,377,273									
10	60,779,144	(5,372,923)		-	22,653,925	\$ 43,546,132	\$30,908,559	\$12,637,573									
11	61,265,377	(5,487,769)		-	22,835,157	\$ 41,100,668	\$29,161,892	\$11,938,776									
12	61,755,500	(5,605,070)		_	23,017,838	\$ 38,792,032	\$27,513,413	\$11,278,619									
13	62,249,544	(5,724,878)		-	23,201,981	\$ 36,612,591	\$25,957,626	\$10,654,965									
14	62,747,540	(5,847,248)	\$ 56,900,293	-	23,387,596	\$ 34,555,134	\$24,489,338	\$10,065,796									
15	63,249,521	(5,972,233)		14,545,275	23,574,697	\$ 38,479,909	\$28,970,703	\$9,509,206									
16	63,755,517	(6,099,889)	\$ 57,655,628	14,661,638	23,763,295	\$ 36,321,957	\$27,338,564	\$8,983,392									
17	64,265,561	(6,230,274)		14,778,931	23,953,401	\$ 34,284,620	\$25,797,967	\$8,486,654									
18	64,779,685	(6,363,446)		14,897,162	24,145,028	\$ 32,361,175	\$24,343,793	\$8,017,382									
19	65,297,923	(6,499,465)		15,016,339	24,338,189	\$ 30,545,270	\$22,971,211	\$7,574,059									
20	65,820,306	(6,638,391)		15,136,470	24,532,894	\$ 28,830,908	\$21,675,658	\$7,155,250									
21	66,346,869	(6,780,287)		15,257,562	24,729,157	\$ 27,212,427	\$20,452,828	\$6,759,599									
22	66,877,644	(6,925,215)		15,379,622	24,926,991	\$ 25,684,478	\$19,298,652	\$6,385,825									
23	67,412,665	(7,073,242)		15,502,659	25,126,406	\$ 24,242,010	\$18,209,290	\$6,032,720									
24	67,951,966	(7,224,432)		15,626,681	25,327,418	\$ 22,880,255	\$17,181,116	\$5,699,139									
25	68,495,582	(7,378,855)		15,751,694	25,530,037	\$ 21,594,709	\$16,210,705	\$5,384,004									
26	69,043,547	(7,536,578)		15,877,708	25,734,277	\$ 20,381,118	\$15,294,824	\$5,086,294									
27	69,595,895	(7,697,672)		16,004,729	25,940,152	\$ 19,235,468	\$14,430,421	\$4,805,047									
28	70,152,662	(7,862,210)		16,132,767	26,147,673	\$ 18,153,965	\$13,614,614	\$4,539,350									
29	70,713,883	(8,030,265)		16,261,829	26,356,854	\$ 17,133,028	\$12,844,682	\$4,288,346									
30	71,279,595	(8,201,912)		16,391,924	26,567,709	\$ 16,169,276	\$12,118,054	\$4,051,221									
31	71,849,831	(8,377,227)		16,523,059	26,780,251	\$ 15,259,514	\$11,432,307	\$3,827,208									
32	72,424,630	(8,556,291)		16,655,244	26,994,493	\$ 14,400,729	\$10,785,148	\$3,615,582									
33	73,004,027	(8,739,181)		16,788,486	27,210,449	\$ 13,590,072	\$10,174,415	\$3,415,657									
34	73,588,059	(8,925,981)		16,922,794	27,428,132	\$ 12,824,855	\$9,598,067	\$3,226,788									
35	74,176,764	(9,116,774)		17,058,176	27,647,557	\$ 12,102,539	\$9,054,177	\$3,048,362									
	1-1,110,104	(0,110,114)	Ψ 00,000,000	11,000,110		,205,239,461	\$ 875,981,071	\$ 329,258,390									

NPV = (Annual Cost)/(1+(Discount Rate/100))^(Year -1)

# Table V (B) NET PRESENT VALUE LIFECYCLE COST CALCULATION (Primary Voltage System - Installation of Facilities In Subdivisions)

Assumptions: Inflation Rate Discount Rate Book Life 0.80 % 6.70 % 35 Yrs 2.1 % Pole Attach Revenue Increase

			Undergrou	nd	System			
Yr	(A) 3 Yr Avg Annual Operational Cost (\$)	(B) 3 Yr Avg Annual Line Clearance Cost (\$)	(C) Estimated Annual Storm Cost		( <u>A</u> )+( <u>B</u> )+( <u>C</u> ) PV Incl Storm	NF	(A)+(B) PV Excl Storm	(C) NPV Storm Only (\$)
			<u>(\$)</u>	_	<u>(\$)</u>	_	<u>(\$)</u>	
1	\$ 26,631,806	\$ -	\$ 107,436	\$	26,739,242	\$	26,631,806	\$107,436
2	26,844,861	-	108,296	\$	25,260,690	\$	25,159,195	\$101,496
3	27,059,620	-	109,162	\$	23,863,895	\$	23,768,011	\$95,883
4	27,276,097	-	110,035	\$	22,544,335	\$	22,453,754	\$90,581
5	27,494,305	-	110,916	\$	21,297,741	\$	21,212,169	\$85,573
6	27,714,260	-	111,803	\$	20,120,078	\$	20,039,237	\$80,841
7	27,935,974	-	112,697	\$	19,007,534	\$	18,931,163	\$76,371
8	28,159,462	-	113,599	\$	17,956,508	\$	17,884,360	\$72,148
9	28,384,737	-	114,508	\$	16,963,599	\$	16,895,441	\$68,158
10	28,611,815	-	115,424	\$	16,025,593	\$	15,961,204	\$64,390
11	28,840,710	-	116,347	\$	15,139,454	\$	15,078,625	\$60,829
12	29,071,435	-	117,278	\$	14,302,315	\$	14,244,849	\$57,466
13	29,304,007	-	118,216	\$	13,511,465	\$	13,457,177	\$54,288
14	29,538,439		119,162	\$	12,764,346	\$	12,713,060	\$51,286
15	29,774,746	589,910	120,115	\$	12,296,487	\$	12,248,037	\$48,450
16	30,012,944	594,629	121,076	\$	11,616,550	\$	11,570,779	\$45,771
17	30,253,048	599,386	122,045	\$	10,974,211	\$	10,930,970	\$43,240
18	30,495,072	604,181	123,021	\$	10,367,389	\$	10,326,540	\$40,849
19	30,739,033	609,015	124,005	\$	9,794,122	\$	9,755,532	\$38,591
20	30,984,945	613,887	124,997	\$	9,252,554	\$	9,216,097	\$36,457
21	31,232,825	618,798	125,997	\$	8,740,932	\$	8,706,491	\$34,441
22	31,482,687	623,748	127,005	\$	8,257,600	\$	8,225,064	\$32,536
23	31,734,549	628,738	128,021	\$	7,800,995	\$	7,770,257	\$30,737
24	31,988,425	633,768	129,046	\$	7,369,637	\$	7,340,599	\$29,038
25	32,244,333	638,838	130,078	\$	6,962,131	\$	6,934,699	\$27,432
26	32,502,287	643,949	131,119	\$	6,577,159	\$	6,551,243	\$25,915
27	32,762,306	649,100	132,168	\$	6,213,473	\$	6,188,991	\$24,482
28	33,024,404	654,293	133,225	\$	5,869,898	\$	5,846,769	\$23,128
29	33,288,599	659,528	134,291	\$	5,545,320	\$	5,523,471	\$21,850
30	33,554,908	664,804	135,365	\$	5,238,691	\$	5,218,049	\$20,641
31	33,823,347	670,122	136,448	\$	4,949,016	\$	4,929,516	\$19,500
32	34,093,934	675,483	137,539	\$	4,675,359	\$	4,656,938	\$18,422
33	34,366,686	680,887	138,640	\$	4,416,834	\$	4,399,431	\$17,403
34	34,641,619	686,334	139,749	\$	4,172,604	\$	4,156,164	\$16,441
35	34,918,752	691,825	140,867	\$	3,941,879	\$	3,926,348	\$15,532
			SUM	\$	420,529,641	\$	418,852,039	\$ 1,677,603

#### Table VI (A) NET PRESENT VALUE LIFECYCLE COST CALCULATION (Services)

Assumptions: Inflation Rate Discount Rate Book Life 0.80 % 6.70 % 35 Yrs 2.1 % Pole Attach Revenue Increase

					Overhead S	ystem			
Yr	(A) 3 Yr Avg Annual Operational Cost (\$)	(D) 3 Yr Avg Annual Pole Attachment Revenue (\$)	<u>O</u> <u>Co</u>	(A)+(D) 3 Yr Avg Annual perational st Incl Lost ttachment evenue(\$)	(B) 3 Yr Avg Annual Line Clearance Cost (\$)	(C) Estimated Annual Storm Cost (\$)	+(B)+(C)+ (D) V Incl Storm (\$)	(A)+(B)+(D) NPV Excl Storm (\$)	(C) NPV Storm Only (\$)
1		\$ -	\$	1,648,890	\$ -	\$ -	\$ 1,648,890	\$1,648,890	\$0
2		· -	\$	1,662,081	· -	Ψ - -	\$ 1,557,715	\$1,557,715	\$0
3	1,675,378	-	\$	1,675,378	-	-	\$ 1,471,580	\$1,471,580	\$0 \$0
4	1,688,781		\$	1,688,781	-	-	\$ 1,390,209	\$1,390,209	\$0
5	1,702,291	-	\$	1,702,291	-	-	\$ 1,313,337	\$1,313,337	\$0 \$0
6	1,715,910	_	\$	1,715,910		_	\$ 1,240,716	\$1,240,716	\$0
7		_	\$	1,729,637		_	\$ 1,172,110	\$1,172,110	\$0
8	1,743,474	_	\$	1,743,474	_	_	\$ 1,107,298	\$1,107,298	\$0
9	1,757,422	_	\$	1,757,422	_	_	\$ 1,046,070	\$1,046,070	\$0
10	1,771,481	_	\$	1,771,481			\$ 988,227	\$988,227	\$0
11	1,785,653	_	\$	1,785,653		_	\$ 933,583	\$933,583	\$0
12		_	\$	1,799,938			\$ 881,960	\$881,960	\$0
13			\$	1,814,338			\$ 833,192	\$833,192	\$0
14		_	\$	1,828,853			\$ 787,121	\$787,121	\$0
15		_	\$	1,843,483			\$ 743,597	\$743,597	\$0
16		_	\$	1,858,231		_	\$ 702,479	\$702,479	\$0
17		_	\$	1,873,097		_	\$ 663,635	\$663,635	\$0
18		_	\$	1,888,082			\$ 626,940	\$626,940	\$0
19	1,903,186		\$	1,903,186			\$ 592,273	\$592,273	\$0
20	1,918,412	_	\$	1,918,412			\$ 559,523	\$559,523	\$0
21	1,933,759		\$	1,933,759			\$ 528,584	\$528,584	\$0
22		_	\$	1,949,229			\$ 499,356	\$499,356	\$0
23	1,964,823	_	\$	1,964,823			\$ 471,744	\$471,744	\$0
24		_	\$	1,980,542		_	\$ 445,659	\$445,659	\$0
25		_	\$	1,996,386			\$ 421,016	\$421,016	\$0
26		-	\$	2,012,357	_	<u>-</u>	\$ 397,736	\$397,736	\$0
27	2,028,456	-	\$	2,012,337	-	-	\$ 375,743	\$375,743	\$0 \$0
28	2,044,684	-	\$	2,020,430	_	-	\$ 354,966	\$354,966	\$0
29	2,061,041	-	\$	2,044,004	-	-	\$ 335,338	\$335,338	\$0 \$0
30	2,077,529	-	\$	2,001,041	_	-	\$ 316,796	\$316,796	\$0
31	2,077,329	-	\$	2,077,329	-	-	\$ 299,278	\$299,278	\$0 \$0
32		-	\$	2,110,903	-	-	\$ 282,730	\$282,730	\$0
33		-	\$	2,110,903	-	-	\$ 267,096	\$267,096	\$0 \$0
34	2,144,812	_	\$	2,144,812	_	<u>-</u>	\$ 252,327	\$252,327	\$0
35		-	\$	2,161,971	-	-	\$ 238,374	\$238,374	\$0 \$0
55	۱ / ۱۵۱ م	-	Ψ	£, 101,311	-	SUM	25,747,196		\$ .

NPV = (Annual Cost)/(1+(Discount Rate/100))^(Year -1)

#### <u>Table VI (B)</u> NET PRESENT VALUE LIFECYCLE COST CALCULATION (Services)

Assumptions: Inflation Rate Discount Rate Book Life 0.80 % 6.70 % 35 Yrs 2.1 % Pole Attach Revenue Increase

			Undergroui	nd	System				
Yr	(A) 3 Yr Avg Annual Operational Cost (\$)	(B) 3 Yr Avg Annual Line Clearance Cost (\$)	(C) Estimated Annual Storm Cost (\$)		(A)+(B)+(C) PV Incl Storm (\$)	(A)+(B) PV Excl Storm (\$)	(C) NPV Sto Only (S	_	
1	\$ 1,487,567	\$ -	\$ -	\$	1,487,567	\$	1,487,567	\$0	
2	1,499,468	_	_	\$	1,405,312	\$	1,405,312	\$0	
3	1,511,463	-	-	\$	1,327,605	\$	1,327,605	\$0	
4	1,523,555	-	_	\$	1,254,194	\$	1,254,194	\$0	
5	1,535,743	-	-	\$	1,184,844	\$	1,184,844	\$0	
6	1,548,029	_	_	\$	1,119,327	\$	1,119,327	\$0	
7	1,560,414	_	_	\$	1,057,434	\$	1,057,434	\$0	
8	1,572,897	_	_	\$	998,963	\$	998.963	\$0	
9	1,585,480	_	_	\$	943,725	\$	943,725	\$0	
10	1,598,164	_	_	\$	891,542	\$	891,542	\$0	
11	1,610,949			\$	842,244	\$	842,244	\$0	
12	1,623,837	_	_	\$	795,671	\$	795,671	\$0	
13	1,636,828	-	-	\$	751,675	\$	751.675	\$0	
14	1,649,922	-	-	\$	710,111	\$	710,111	\$0 \$0	
15		-	-	\$	,	\$	,	\$0 \$0	
16	1,663,122	-	-	φ \$	670,845	\$	670,845	\$0 \$0	
17	1,676,427	-	-		633,750	\$	633,750		
	1,689,838	-	-	\$	598,707		598,707	\$0	
18	1,703,357	-	-	\$	565,601	\$	565,601	\$0	
19	1,716,984	-	-	\$	534,326	\$	534,326	\$0	
20	1,730,719	-	-	\$	504,781	\$	504,781	\$0	
21	1,744,565	-	-	\$	476,869	\$	476,869	\$0	
22	1,758,522	-	-	\$	450,500	\$	450,500	\$0	
23	1,772,590	-	-	\$	425,590	\$	425,590	\$0	
24	1,786,771	-	-	\$	402,057	\$	402,057	\$0	
25	1,801,065	-	-	\$	379,825	\$	379,825	\$0	
26	1,815,473	-	-	\$	358,822	\$	358,822	\$0	
27	1,829,997	-	-	\$	338,981	\$	338,981	\$0	
28	1,844,637	-	-	\$	320,237	\$	320,237	\$0	
29	1,859,394	-	-	\$	302,529	\$	302,529	\$0	
30	1,874,269	-	-	\$	285,801	\$	285,801	\$0	
31	1,889,263	-	_	\$	269,998	\$	269,998	\$0	
32	1,904,378	_	_	\$	255,068	\$	255,068	\$0	
33	1,919,613	_	_	\$	240,964	\$	240,964	\$0	
34	1,934,969	_	_	\$	227,640	\$	227,640	\$0	
35	1,950,449	-	_	\$	215.052	\$	215.052	\$0	
55	1,330,448	-	SUM.	\$	23,228,156	\$	23,228,156	\$	
			SUIVI	Φ	23,220,130	Φ	∠3,∠∠0,130	φ	-

#### Table VII Net Present Value of Operational Costs Per Mile & Per Service Calculations

	Overhead		
Primary Voltage System  NPV Life Cycle Cost  System Miles OH  NPV Life Cycle Cost / Mile	Incl Storm \$1,205,239,461 6,246 \$192,961.81	Excl Storm \$875,981,071 6,246 \$140,246.73	Storm Only \$329,258,390 6,246 \$52,715.08
Services  NPV Life Cycle Cost  Number of Services  NPV Life Cycle Cost / Service	Incl Storm \$25,747,196 246,960 \$104.26	Excl Storm \$25,747,196 246,960 \$104.26	\$0 246,960 \$0.00
	Underground		
Primary Voltage System  NPV Life Cycle Cost  System Miles OH  NPV Life Cycle Cost / Mile	Incl Storm \$420,529,641 5,715 \$73,583.49	Excl Storm \$418,852,039 5,715 \$73,289.95	\$1,677,603 5,715 \$293.54
Services  NPV Life Cycle Cost  Number of Services  NPV Life Cycle Cost / Service	Incl Storm \$23,228,156 284,735 \$81.58	Excl Storm \$23,228,156 284,735 \$81.58	\$0 284,735 \$0.00
Primary Voltage System  NPV Life Cycle Cost / Mile	<u>Differential</u> Incl Storm -\$119,378.32	Excl Storm -\$66,956.78	Storm Only -\$52,421.54
Services  NPV Life Cycle Cost / Service	Incl Storm -\$22.68	Excl Storm -\$22.68	Storm Only \$0.00

### Table VIII Net Present Value of Operational Costs Per Lot Calculations

#### Low Density Subdivision Overhead

			Incl Storm	Excl Storm	Storm Only
	Number of Lots	Miles of Line	\$ / Lot	\$ / Lot	\$ / Lot
Primary Voltage System <sup>1</sup>	210	1.92	\$1,764.22	\$1,282.26	\$481.97
Services	NA	NA	\$104.26	\$104.26	\$0.00
Primary & Service			\$1,868.48	\$1,386.52	\$481.97
		Underground			
Primary Voltage System <sup>1</sup>	210	2.99	\$1,047.69	\$1,043.51	\$4.18
Services	NA	NA	\$81.58	\$81.58	\$0.00
Primary & Service			\$1,129.27	\$1,125.09	\$4.18
Primary & Service		Differential	-\$739.21	-\$261.43	-\$477.79
Filliary & Service		Dilletelltial	-ψ1 33.21	-ψ201.43	-ψ11.13

#### High Density Subdivision

		Overhead			
			Incl Storm	Excl Storm	Storm Only
	Number of Lots	Miles of Line	\$ / Lot	\$ / Lot	\$ / Lot
Primary Voltage System <sup>1</sup>	176	1.17	\$1,282.76	\$932.32	\$350.44
Services	NA	NA	\$104.26	\$104.26	\$0.00
Primary & Service			\$1,387.02	\$1,036.58	\$350.44
		Underground			
Primary Voltage System <sup>1</sup>	176	1.07	\$447.35	\$445.57	\$1.78
Services	NA	NA	\$81.58	\$81.58	\$0.00
Primary & Service			\$528.93	\$527.15	\$1.78
Primary & Service		<u>Differential</u>	-\$858.09	-\$509.43	-\$348.66

| Note | 1. Formula = (NPV Life Cycle Cost / Mile) x (Miles of Line) / (Number of Lots)

#### <u>Table IX</u> 2020 O&M - FORM 13

			ОН	UG	2020 Allocated Overhead	2020 Allocated Underground
Overhead Blanket Assesset		2020 Actual \$	Ratio	Ratio	\$	\$
Overhead - Blanket Account D-CRR-Voltage-OH (NEW)		\$263,090	100.0%	0.0%	\$263,090	\$0
PRE - Dist Line - Fault Indicators		\$13,005		0.0%	\$13,005	\$0
Distr - Maint - Corrective - OH Line Distribution - Maint - OH System Improvements		\$10,246,537 \$0	100.0% 100.0%	0.0%	\$10,246,537 \$0	\$0 \$0
Distribution - Maint - Mgmt & Coordination			100.0%	0.0%	\$0	\$0
Distr - Maint - Preventative - OH Line Distr - Maint - Trouble - OH Storm		\$6,448,231 \$687,761		0.0%		\$0 \$0
Distr - Maint - Pole Inspect & Change-Outs		\$11,097,693				\$0
Distr - Maint - Damage Replacement - OH Line		\$2,655,044	100.0%	0.0%	\$2,655,044	\$0
Distr - Maint - Capacitors Distr - Maint - Trouble - Non-Storm		\$298,534 \$0	100.0%	0.0%		\$0 \$0
Distr - Maint - Tree Trimming - Planned		\$0	0.0%			\$0
Distr - Env - Train/Permit/Inspect/Audit/Protect		\$0	100.0%	0.0%	\$0	\$0
Distr - Maint - Tree Trimming - Unplanned Distr - Maint - Pole Reinforcements		\$0 \$434,229	0.0%	0.0%	\$0 \$434.229	\$0 \$0
Distr - Maint - Pole CLAs & Change-Outs		\$67,705	100.0%	0.0%	\$67,705	\$0
Distr - Maint - Infrared Thermography Distr - Maint - Services - OH Line		\$0 \$966,573	100.0%	0.0%		\$0 \$0
Disti - Maint - Services - OTI Line	Subtotal	\$33,178,402	0.076	0.076	φυ	90
Underground - Blanket Account						
D-CRR-Voltage-UG		\$23,632		100.0%		\$23,632
D-PRE-Transformers-UG Distr - Maint - Corrective - UG Line		\$2,084,383 \$10,427,986	0.0%	100.0% 100.0%	\$0 \$0	\$2,084,383 \$10,427,986
Distribution - Maint - UG System Improvements		\$10,427,980		100.0%		\$10,427,980
Distribution - Maint - Mgmt & Coordination		\$0		100.0%		\$0
Distr - Maint - Preventative - UG Line Distr - Maint - Network Corrective		\$9,506,194 \$33,100		100.0% 100.0%	\$0 \$0	\$9,506,194 \$33,100
Distr - Maint - Network Preventative		\$25,243	0.0%	100.0% 100.0%	\$0	\$25,243
Distr - Maint - Capacitors - UG		\$53,629	0.0%	100.0%	\$0	\$53,629
Distr - Maint - UG Cable Rplcmnt - Planned Distr - Maint - Trouble - UG Storm		\$2,906,062 \$265,878	0.0%	100.0% 100.0%	\$0 \$0	\$2,906,062 \$265,878
Distr - Maint - Trouble - UG Storm  Distr - Maint - Damage Replacement - UG Line		\$205,878		100.0%		\$265,878 \$1,211,387
Distr - Maint - UG Cable Rplcmnt - Unplanned		\$0	0.0%	100.0%	\$0	\$0
Distr - Maint - Services - UG Line	Subtotal	\$812,991 \$27,350,485	0.0%	0.0%	\$0	\$0
Outstand COMA						
Overhead - O&M Account D-CRR-Voltage-OH (NEW)			100.0%	0.0%		\$0
Distr - Maint - Corrective - OH Line		\$7,002,950	100.0%	0.0%		\$0
Distribution - Maint - OH System Improvements Distribution - Maint - Mgmt & Coordination			100.0%	0.0%		\$0 \$0
Distr - Maint - Preventative - OH Line		\$124,407 \$593,755	100.0%	0.0%		\$0
Distr - Maint - Trouble - OH Storm		\$593,755	100.0%	0.0%	\$593,755	\$0
Distr - Maint - Pole Inspect & Change-Outs		\$904,908 \$184.081		0.0%		\$0 \$0
Distr - Maint - Damage Replacement - OH Line Distr - Maint - Capacitors			100.0%			\$0 \$0
Distr - Maint - Trouble - Non-Storm		\$2,814,800	0.0%	0.0%	\$0	\$0
CRR - Dist Line - Storms - OH - Restoration		\$0	0.0%			\$0
Distr - Maint - Tree Trimming - Planned Distr - Env - Train/Permit/Inspect/Audit/Protect		\$16,990,720 \$26,923	0.0%	0.0%		\$0 \$0
Distr - Maint - Tree Trimming - Unplanned		\$2,026,699	0.0%			\$0
Distr - Maint - Pole Reinforcements			100.0%			\$0
Distr - Maint - Pole CLAs & Change-Outs Distr - Maint - Infrared Thermography			100.0% 100.0%	0.0%	\$0 \$0	\$0 \$0
Distr - Maint - Illifared Thermography  Distr - Maint - Services - OH Line		\$839,741	0.0%	0.0%	\$0	\$0
	Subtotal	\$31,584,618				
Underground - O&M Account						
D-PRE-Transformers-UG Distr - Maint - Corrective - UG Line		\$0 \$1,710,255		100.0% 100.0%	\$0 \$0	\$0 \$1,710,255
Distribution - Maint - UG System Improvements		\$1,710,233		100.0%	\$0	\$1,710,233
Distribution - Maint - Mgmt & Coordination		\$0		100.0%		\$0
Distr - Maint - Preventative - UG Line Distr - Maint - Network Corrective		\$220,874 \$5,573	0.0%	100.0%	\$0 \$0	\$220,874 \$5,573
Distr - Maint - Network Corrective		\$660,604	0.0%	100.0% 100.0%	\$0	\$660,604
Distr - Locate Facilities		\$948,183	0.0%	100.0%	\$0	\$948,183
Distr - Maint - UG Cable Rplcmnt - Planned Distr - Maint - Trouble - UG Storm		\$23,766 \$19,316		100.0%		\$23,766
D-CRR-Capacitors-UG		\$19,316		100.0% 100.0%	\$0 \$0	\$19,316 \$0
D-CRR-Storms-UG		\$0	0.0%	100.0%	\$0	\$0
Distr - Maint - Damage Replacement - UG Line Distr - Maint - UG Cable Rplcmnt - Unplanned		\$174,701 \$0	0.0%		\$0 \$0	\$174,701 \$0
Distr - Maint - OG Cable Ripidhilit - Ohplanned		\$712,258	0.0%	0.0%	\$0	\$0
	Subtotal	\$4,475,530			\$41,124,487	\$30,300,766
					V11,121,101	400,000,700
Distribution - Maint - Trouble Calls - Non-storm						
Blanket		\$0	77.7%			\$0
O&M		\$2,814,800	77.7%	22.3%	\$2,187,100	\$627,700
Distr - Maint - Tree Trimming - Planned Blanket		\$0	96.1%	3.9%	\$0	\$0
O&M		\$16,990,720	96.1%	3.9%		\$662,231
Distr - Maint - Tree Trimming - Unplanned		***	00.48/	0.00/		
Blanket O&M		\$0 \$2,026,699	96.1% 96.1%	3.9% 3.9%		\$0 \$78,993
Distr - Maint - Services - OH Line		****			****	
Blanket O&M		\$966,573 \$839,741		0.0%	\$966,573 \$839,741	\$0 \$0
		,		,	,	+5
Distr - Maint - Services - UG Line						
Blanket O&M		\$812,991 \$712,258		100.0% 100.0%	\$0 \$0	\$812,991 \$712.258
		2020 O8	kM Cost -	Form 13	\$63,394,096	\$33,194,939

OC-8

# ENERGY DELIVERY "2021" ADDER STUDY Provided by ED Business Planning

	<u>Toolkit</u>				
	Distribution CIAC				
Total Corporate Accounting FRINGE Rates per Activity	72.62%				
A&G (for PSTEW)	12.0270				
Other "Operating Labor" related adders:					
Non-Productive Time*	13.00%				
Energy Delivery (Supervisory/Administrative)	15.18%				
Energy Delivery Engineering	0.00%				
Small Tools *	5.39%				
TOTAL Other "Labor" related Adders	33.58%				
TOTAL Fully Loaded "Labor" adders	106.20%				
	44.040/				
Fleet* as a % of Labor (rate of settled labor w/ fringe)	14.81%				
Fleet* as a % of Labor (rate excluding 37% fringe)	20.29%				
"Material" related adders:					
	4 200/				
Stores Carrying Cost (ED Stores Clearing) * Stores Carrying Cost (WH Space, Taxes, Insurance & Obsolete Mat)	4.30% 4.83%				
Stores Carrying Cost (WTT Space, Taxes, Insurance & Obsolete Mat)  Stores Carrying Cost (Cost of Money - PDR only)	0.00%				
Self Help *	3.09%				
TOTAL "Material" related Adders	12.22%				
Other "Contractor" related adders:					
Energy Delivery (Supervisory/Administrative/Engineering)	20.06%				
TOTAL Fully Loaded "Contractor" adders					
* When determining final bill true up or calculating pay-after invoice using actual results, exclude these items, which will already be included in actuals					